



Dzilth-Na-O-Dith-Hle

Student Dormitories

CONSTRUCTION DOCUMENTS

DECEMBER 4, 2020

GENERAL

G-000 COVER SHEET
G-001 BUILDING CODE ANALYSIS
G-010 ACCESSIBILITY GUIDELINES

CIVIL

*FOR CIVIL SEE DZILTH-NA-O-DITH-HLE
COMMUNITY SCHOOL + SITE PACKAGE

LANDSCAPE

*FOR LANDSCAPE SEE DZILTH-NA-O-DITH-HLE
COMMUNITY SCHOOL + SITE PACKAGE

STRUCTURAL

ISSUED OCTOBER 5, 2020
INCLUDED HERE FOR REFERENCE
(REVISIONS TO DATE ARE CLOUDED)

S-001 GENERAL STRUCTURAL NOTES
S-002 STRUCTURAL QUALITY ASSURANCE INSPECTIONS
S-101 FOUNDATION PLAN
S-111 ROOF FRAMING PLAN
S-301 FOUNDATION SECTIONS
S-305 FRAMING SECTIONS
S-306 FRAMING SECTIONS
S-505 FRAMING DETAILS
S-601 BRACED FRAME ELEVATIONS & DETAILS

ARCHITECTURAL

A-101 FLOOR PLAN
A-111 DIMENSION PLAN
A-120 REFLECTED CEILING PLANS
A-131 ROOF PLAN
A-141 ROOF DETAILS
A-142 ROOF DETAILS
A-201 BUILDING ELEVATIONS
A-301 BUILDING SECTIONS
A-302 BUILDING SECTIONS
A-311 WALL SECTIONS
A-312 WALL SECTIONS
A-401 ENLARGED PLANS AND ELEVATIONS
A-402 ENLARGED PLANS AND ELEVATIONS
A-403 ENLARGED PLANS AND ELEVATIONS
A-501 PARTITION SCHEDULE
A-601 DOOR-WINDOW SCHEDULE
A-611 WINDOW / STOREFRONT DETAILS

INTERIORS

ID-101 FINISH LEGEND
ID-102 FLOOR FINISH PLAN

PLUMBING

P-001 PLUMBING LEGEND
PL-101 WASTE & VENT FLOOR PLAN
PL-131 PLUMBING ROOF PLAN
PP-101 PRESSURE PIPING FLOOR PLAN
P-401 ENLARGED PLUMBING PLANS
P-402 ENLARGED PLUMBING PLANS
P-501 PLUMBING DETAILS
P-502 PLUMBING DETAILS
P-701 PLUMBING SCHEDULES
P-702 PLUMBING SCHEDULES

FIRE PROTECTION

FX001 FIRE PROTECTION LEGEND
FX-101 FIRE PROTECTION FLOOR PLAN
FX-131 FIRE PROTECTION ROOF PLAN
FX501 FIRE PROTECTION DETAILS

MECHANICAL


M-001 MECHANICAL LEGEND
MH-101 HVAC FLOOR PLAN
MH-131 MECHANICAL ROOF PLAN
MP-101 MECHANICAL PIPING FLOOR PLAN
M-401 ENLARGED MECHANICAL PLANS
M-402 ENLARGED MECHANICAL PLANS
M-501 MECHANICAL DETAILS
M-502 MECHANICAL DETAILS
M-503 MECHANICAL DETAILS
M-601 MECHANICAL DIAGRAMS
M-602 MECHANICAL DIAGRAMS
M-701 MECHANICAL SCHEDULES
M-702 MECHANICAL SCHEDULES
MI001 MECHANICAL CONTROLS LEGEND
MI601 MECHANICAL CONTROLS DIAGRAM
MI602 MECHANICAL CONTROLS DIAGRAM
MI603 MECHANICAL CONTROLS DIAGRAM

ELECTRICAL

E-001 ELECTRICAL LEGEND
E-002 ADA MOUNTING DETAIL
ES-101 ELECTRICAL SITE PLAN
EL-101 LIGHTING FLOOR PLAN
EL-141 LIGHTING PENTHOUSE PLAN
EP-101 POWER FLOOR PLAN
EP-141 ELECTRICAL ROOF PLAN
LP-141 LIGHTNING PROTECTION ROOF PLAN
FA-101 FIRE ALARM FLOOR PLAN
E-401 ENLARGED PLANS
E-501 ELECTRICAL DETAIL SHEET
E-502 LIGHTNING PROTECTION DETAILS
E-601 ELECTRICAL DIAGRAMS
E-602 GROUNDING DIAGRAM
E-603 ELECTRICAL FIRE RISER DIAGRAM
E-701 ELECTRICAL SCHEDULES
E-702 ELECTRICAL PANEL SCHEDULES


TECHNOLOGY

T-101 TECHNOLOGY PLAN



VICINITY MAP

35 Road 7585 #5003 - Bloomfield, NM 87413



BIM MODEL REQUIREMENTS

BIM MODEL SUBMITTAL & COORDINATION REQUIREMENTS

All requirements noted in individual specification sections for submittal of coordination drawings and shop drawings shall be strictly followed. Item or Equipment fabrications and installations that occur prior to the approval of these drawings shall be subject to removal and replacement at no additional cost to the owner.

In addition to the required drawings noted above, contractor shall prepare BIM (Building Information Model) for the systems noted below. The intent of this BIM model is to determine conflicts and coordinate solutions that will resolve final system installation. The contractor may use the overall BIM model to generate the coordination drawings and vice-versa.

1. HVAC
2. Plumbing
3. Electrical
4. Fire Protection
5. Special Systems
6. Structural

REVISIONS

All clouded revisions within these drawings indicate material and/or quantity changes made from the Pricing Set issued on 11/10/2020.

OWNER

Dzilth-Na-O-Dith-Hle Community School
35 Road 7585 #5003
Bloomfield, NM 87413
p_505.960.8563

CONSULTANTS

CIVIL
Bohannon Huston
7500 Jefferson St NE,
Albuquerque, NM 87109
p_505.823.1000

STRUCTURAL
Walla Engineering Ltd
6501 Americas Pkwy NE Ste. 302
Albuquerque, NM 87110
p_505.243.9287

M/E/P/FP
Bridgers and Paxton
4600-C Montgomery Blvd. NE
Albuquerque, New Mexico 87109
p_505.883.4111


INTERIORS
Studio M
6501 Americas Pkwy NE Ste. 301
Albuquerque, NM 87110
p_505.243.9287

SITE
Groundwork Studio
6501 Americas Pkwy NE Ste. 350
Albuquerque, NM 87110
p_505.212.9126

FOOD SERVICE
Standard Kitchen Supply
2405 Candelaria Rd. NE,
Albuquerque, NM 87107
p_505.341.1054


AV & TECHNOLOGY
Network Cabling, INC
3100 La Plata HWY
Farmington, NM 87401
p_505.598.5054

fbt | architects
MAIL: 6501 Americas Pkwy NE Ste. 300
Albuquerque, NM 87110
PHO: 505.883.5200
FAX: 505.884.5390
WEB: www.fbtarch.com



ARCHITECT

SET NO.



PER SECTION 24.1.7 (NFPA 5000, 2018) OCCUPANCY OF SLEEPING ROOMS ARE CALCULATED AS FOLLOWS FOR EGRESS COMPONENTS -

4 BEDS + 1 GUEST EACH = 8 OCCUPANTS
(ROOMS 108.1, 108.2, 222, 224, 225, 226 & 227)

2 BEDS + 1 GUEST EACH = 4 OCCUPANTS
(ROOM 220 & 223)

PER SECTION 24.1.7 (NFPA 5000, 2018) OCCUPANCY OF SLEEPING ROOMS ARE CALCULATED AS FOLLOWS FOR EGRESS COMPONENTS -

4 BEDS + 1 GUEST EACH = 8 OCCUPANTS
(ROOMS 113.1, 113.2, 209, 210, 211, 212 & 213)

2 BEDS + 1 GUEST EACH = 4 OCCUPANTS
(ROOM 207 & 208)

CODE ANALYSIS

REFERENCES

BUILDING / LIFE SAFETY - NFPA 5000, (CURRENT EDITION).
MECHANICAL - UNIFORM MECHANICAL CODE (CURRENT EDITION), 2018 Ed.
PLUMBING - UNIFORM PLUMBING CODE (CURRENT EDITION), 2018 Ed.
ACCESSIBILITY - AMERICANS WITH DISABILITIES ACT (ADA), 2004 Ed.
ARCHITECTURAL BARRIERS ACT ACCESSIBILITY GUIDELINES (ABAAG), 2018 Ed.
FIRE PROTECTION - NATIONAL FIRE PROTECTION ASSOCIATION (NFPA 13), 2018 Ed.

ADDRESS

35 ROAD 7585
BLOOMFIELD, NM 87413

OCCUPANCY CLASSIFICATION

RESIDENTIAL - DORMITORY SECTION 6.1.8.1.4

CONSTRUCTION TYPE

NEW CONSTRUCTION: TYPE II (000), FULLY SPRINKLERED

ALLOWABLE BUILDING HEIGHT AND AREA

NUMBER OF STORIES: ALLOWABLE - 5
ACTUAL - 1

BUILDING HEIGHT: ALLOWABLE - 75'-0"
ACTUAL - 29'-0"

GROSS BUILDING AREA: ALLOWABLE - 16,000
ACTUAL - 13,889

FIRE RATED CONSTRUCTION

TYPE II (000) CONSTRUCTION:
EXTERIOR BEARING WALLS - 0 FLOOR/CEILING ASSEMBLIES - 0
INTERIOR BEARING WALLS - 0 ROOF/CEILING ASSEMBLIES - 0
COLUMNS - 0 INTERIOR NON BEARING WALLS - 0
BEAMS, GIRDERS, TRUSSES & ARCHES - 0 EXTERIOR NON BEARING WALLS - 0
*HEAVY TIMBER STRUCTURAL ELEMENTS ARE PERMITTED (7.2.3.2.10)

EXTERIOR WALLS

FIRE RESISTANCE RATING - 0

MEANS OF ESCAPE

SECONDARY MEANS OF ESCAPE IS NOT REQUIRED (SPRINKLERED) (22.2.1.2 (2))

COMMON PATH OF TRAVEL

50 FT. MAXIMUM EDUCATIONAL OCCUPANCY (SPRINKLERED)
- ROOMS NOT INCLUDED WHEN DETERMINING LENGTH (24.2.5.5)

DEAD-END CORRIDORS

50 FT. MAXIMUM EDUCATIONAL OCCUPANCY (SPRINKLERED)

TRAVEL DISTANCE TO EXITS

200 FT. MAXIMUM EDUCATIONAL OCCUPANCY (SPRINKLERED)

HAZEROUS AREA PROTECTION

1 HOUR SEPARATION + FIRE SPRINKLERS
- BOILER & HEATER ROOMS - SMOKE PARTITIONS + FIRE SPRINKLERS
- GUEST LAUNDRY ROOMS - SMOKE PARTITIONS + FIRE SPRINKLERS
- STORAGE ROOMS - SMOKE PARTITIONS + FIRE SPRINKLERS

EXTINGUISHMENT REQUIREMENTS

EQUIPPED THROUGHOUT WITH AN ELECTRICALLY SUPERVISED
AUTOMATIC SPRINKLER SYSTEM

COORIDOR FIRE RESISTANCE RATING

12 HOUR (SPRINKLERED) (24.3.6.2)
DOORS MINIMUM 20 MIN. RATED (24.3.6.3)

SUBDIVISION OF BUILDING SPACES

ALL DORM ROOMS SEPARATED BY 1/2 HOUR FIRE BARRIER WALL

FIRE EXTINGUISHERS (FE)

RESIDENTIAL OCCUPANCY
MINIMUM RATED EXTINGUISHER: 4-A
MAXIMUM FLOOR AREA PER UNIT OF A: 3,000 SF
MAXIMUM ALLOWABLE DISTANCE BETWEEN: 75 LF
NUMBER REQUIRED: 5
NUMBER PROVIDED: 8

UNIFORM PLUMBING CODE, TABLE 422.1, 2018 Ed TABLE R-2 DORMITORIES MINIMUM PLUMBING FACILITIES - UPC TABLE 422.1

Dormitories - School							
GSF / 200 = TOTAL NUMBER OF OCCUPANTS - 13,889 / 200 = 70							
MALE OCC. LOAD				FEMALE OCC. LOAD			DRINKING FOUNTAIN
70 / 2 = 35				70 / 2 = 35			
FACTOR	REQUIRED	PROVIDED		FACTOR	REQUIRED	PROVIDED	1 PER 150
1:25	1	1					
1:10	4	6	WC	1:8	5	7	
1:12	3	6	LAV	1:12	3	6	
				+1:15 over 12			1 REQ.
1:8	5	7	LAV	1:8	5	7	4 PROV.
Dormitories - Staff							
Assuming a maximum of 8 Staff							
MALE OCC. LOAD				FEMALE OCC. LOAD			ADULT SHOWER
8 / 2 = 4				8 / 2 = 4			
FACTOR	REQUIRED	PROVIDED		FACTOR	REQUIRED	PROVIDED	1 PER 8
1:50	1	1					
1-15	1	1	WC	1-15	1	1	1 REQ.
1:40	1	1	LAV	1:40	1	1	1 PROV.

CODE SYMBOL LEGEND

- 1/2 HOUR FIRE PARTITION
- AREA OCCUPANT LOAD
- F.E.C. SEMI RECESSED FIRE EXTINGUISHER CABINET
- EXIT TRAVEL DISTANCE
- EXIT OCCUPANT LOAD
(ARROW INDICATES DIRECTION TO EXIT)

A1 CODE FLOOR PLAN

1/8" = 1'-0"

CONSULTANT

CIVIL

Bohannon Huston
7500 Jefferson St NE,
Albuquerque, NM 87109
p_505.823.100

STRUCTURAL

Walla Engineering Ltd
6501 Americas Pkwy NE Ste. 302
Albuquerque, NM 87110
p_505.243.9287

M/E/P/FP

Bridgers and Paxton
4600-C Montgomery Blvd. NE
Albuquerque, New Mexico 87109
p_505.883.4111 f_505.888.1436

INTERIORS

Studio M
6501 Americas Pkwy NE Ste. 301
Albuquerque, NM 87110
p_505.243.9287

SITE

Groundwork Studio
6501 Americas Pkwy NE Ste. 350
Albuquerque, NM 87110
p_505.212.9126

FOOD SERVICE

Standard Kitchen Supply
2405 Candelaria Rd. NE,
Albuquerque, NM 87107
p_505.341.1054

ENVELOPE AND ROOF CONSULTANT

Armstrong Group INC.
2415 Princeton Ave, NE Suite E
Albuquerque, NM 87107
p_505.235.7596

AV & TECHNOLOGY

Network Cabling, INC
3100 La Plata HWY,
Farmington, NM 87401
p_505.598.5054



Dzilth-Na-O-Dith-Hle - New Dormitory Building

CONSTRUCTION DOCUMENTS


35 Road 7585, Bloomfield, NM
87413

DECEMBER 4TH, 2020


MARK	DATE	DESCRIPTION
ISSUE:		
DATE:		
PROJECT NO:		
CAD DWG FILE:		
DRAWN BY:		
CHECKED BY:		

SHEET TITLE


BUILDING CODE ANALYSIS




E1 ACCESSIBLE RESTROOM - 9-ADULT
1/2" = 1'-0"




D1 ACCESSIBLE RESTROOM - 5-8
1/2" = 1'-0"




C1 ACCESSIBLE URINAL - 12-ADULT
1/2" = 1'-0"




B1 ACCESSIBLE URINAL - 5-12
1/2" = 1'-0"




A1 FORWARD REACH - 5-ADULT
1/2" = 1'-0"




E2 ACCESSIBLE STALL - 9-ADULT
1/2" = 1'-0"




D2 ACCESSIBLE STALL - 5-8
1/2" = 1'-0"




C2 DRINKING FOUNTAIN - 12-ADULT
1/2" = 1'-0"




B2 DRINKING FOUNTAIN - 5-12
1/2" = 1'-0"




A2 OBSTRUCTED SIDE REACH - 5-ADULT
1/2" = 1'-0"




E3 W.C. ELEVATION - 9-ADULT
1/2" = 1'-0"




D3 W.C. ELEVATION - 5-8
1/2" = 1'-0"




C3 TRANSFER SHOWER - 5-ADULT
1/2" = 1'-0"




B3 DRINKING FOUNTAIN - 5-ADULT
1/2" = 1'-0"




A3 DOOR MINIMUM CLEARANCES
1/4" = 1'-0"




E4 ACCESSIBLE SINK - 12-ADULT
1/2" = 1'-0"




D4 ACCESSIBLE SINK - 5-12
1/2" = 1'-0"



C4 TRANSFER SHOWER ELEV. - 12-ADULT
1/2" = 1'-0"




B4 TRANSFER SHOWER ELEV. - 5-12
1/2" = 1'-0"



A5 SIGNAGE MOUNTING HEIGHT/ LOCATION
1/2" = 1'-0"

GENERAL NOTES

ALL FIXTURES AND ACCESSORIES SHALL COMPLY WITH ADA, ANSI, UFAS, AND LOCAL AND STATE BUILDING CODE REQUIREMENTS. ALL HEIGHTS, DIMENSIONS AND CLEARANCES FOR PLUMBING FIXTURES, CASEWORK, COUNTERTOPS, ACCESSORIES, SIGNAGE, ACCESSIBLE ROUTES, ETC. SHALL BE STRICTLY HELD TO ADA, ANSI, AND LOCAL AND STATE REQUIREMENTS. IN THE EVENT OF CONFLICTING REQUIREMENTS, THE MOST RESTRICTIVE REQUIREMENTS SHALL APPLY.



fbt | architects

MAL: 6501 Americas Pkwy NE, Ste. 300
Albuquerque, NM 87110

PHO: 505.883.6200
FAX: 505.884.6290
WEB: www.fbtarch.com

CONSULTANT

CIVIL
Bohannon Huston
7500 Jefferson St. NE,
Albuquerque, NM 87109
p_505.823.100

STRUCTURAL
Walla Engineering Ltd
6501 Americas Pkwy NE Ste. 302
Albuquerque, NM 87110
p_505.243.9287

M/E/P/FP
Bridgers and Paxton
4600-C Montgomery Blvd. NE
Albuquerque, New Mexico 87109
p_505.883.4111 f_505.888.1436

INTERIORS
Studio M
6501 Americas Pkwy NE Ste. 301
Albuquerque, NM 87110
p_505.243.9287

SITE
Groundwork Studio
6501 Americas Pkwy NE Ste. 350
Albuquerque, NM 87110
p_505.212.9126

FOOD SERVICE
Standard Kitchen Supply
2405 Candelaria Rd. NE,
Albuquerque, NM 87107
p_505.341.1054

ENVELOPE AND ROOF CONSULTANT
Armstrong Group INC.
2415 Princeton Ave, NE Suite E
Albuquerque, NM 87107
p_505.235.7596

AV & TECHNOLOGY
Network Cabling, INC
3100 La Plata HWY.
Farmington, NM 87401
p_505.598.5054

ARCHITECT

**Dzilth-Na-O-Dith-Hle -
New Dormitory
Building**

**CONSTRUCTION
DOCUMENTS**

35 Road 7585, Bloomfield, NM
87413

DECEMBER 4TH, 2020

MARK	DATE	DESCRIPTION

ISSUE:

DATE:

PROJECT NO:

CAD DWG FILE:

DRAWN BY:

CHECKED BY:

SHEET TITLE

ACCESSIBILITY GUIDELINES

G-010

Dzilth-Na-O-Dith-Hle Community School

SCHEDULE OF STRUCTURAL QUALITY ASSURANCE INSPECTIONS

1. QUALITY ASSURANCE INSPECTIONS / TESTING - "QUALITY ASSURANCE INSPECTION" SHALL NOT RELIEVE THE OWNER OR THEIR AGENT FROM REQUESTING THE JURISDICTION BUILDING DEPARTMENT INSPECTIONS REQUIRED BY SECTION 40 OF THE NFPA-5000.
2. REPORTING FOR QUALITY ASSURANCE INSPECTION -
 a. QUALITY ASSURANCE INSPECTION AND TESTING REPORTS SHALL BE COMPLETED AND DISTRIBUTED AT THE COMPLETION OF EACH TASK IF A TASK IS LONGER THAN (3) DAYS. PROVIDE REPORTS FOR EACH DAY. PROVIDE COPIES OF REPORTS TO: CONTRACTOR, OWNER, ARCHITECT AND STRUCTURAL ENGINEER OF RECORD. QUALITY ASSURANCE INSPECTOR TO KEEP A NON-COMPLIANCE LOG OF ALL DEFICIENCIES INSPECTED NOT MEETING APPROVED CONSTRUCTION DOCUMENTS AND WHEN / HOW RESOLVED.
3. SEE ARCHITECTURAL, MECHANICAL, ELECTRICAL, AND PLUMBING CONSTRUCTION DOCUMENTS FOR ADDITIONAL, NON-STRUCTURAL, QUALITY ASSURANCE INSPECTION ITEMS.

IN ACCORDANCE WITH NFPA 5000 CHAPTER 40, THE FOLLOWING TYPES OF WORK REQUIRE QUALITY ASSURANCE INSPECTIONS AND TESTING:

QUALITY ASSURANCE INSPECTION AND VERIFICATION OF SOILS				
SPECIAL INSPECTION REQUIRED Y/N	VERIFICATION AND INSPECTION TASK	CONTINUOUS DURING TASK LISTED	PERIODICALLY DURING TASK LISTED	NFPA 500
Y	1. VERIFY MATERIALS BELOW FOOTINGS ARE ADEQUATE TO ACHIEVE THE DESIGN BEARING CAPACITY.	-----	X	40.3.5.2
Y	2. VERIFY EXCAVATIONS ARE EXTENDED TO PROPER DEPTH AND HAVE REACHED PROPER MATERIAL.	-----	X	40.3.5.1
Y	3. PERFORM CLASSIFICATION AND TESTING OF CONTROLLED FILL MATERIALS.	-----	X	40.3.5.2
Y	4. VERIFY USE OF PROPER MATERIALS, DENSITIES AND LIFT THICKNESS DURING PLACEMENT AND COMPACTION OF CONTROLLED FILL.	X	-----	40.3.5.2
Y	5. PRIOR TO PLACEMENT OF CONTROLLED FILL, INSPECT SUBGRADE AND VERIFY THAT SITE HAS BEEN PREPARED PROPERLY.	-----	X	40.3.5.1

QUALITY ASSURANCE INSPECTION AND VERIFICATION OF CONCRETE CONSTRUCTION

SPECIAL INSPECTION REQUIRED Y/N	VERIFICATION AND INSPECTION	FREQUENCY OF INSPECTION		REFERENCE FOR CRITERIA	
		CONTINUOUS DURING TASK LISTED	PERIODICALLY DURING TASK LISTED	NFPA-5000	REFERENCE D STANDARD
Y	1. INSPECT REINFORCEMENT AND VERIFY PLACEMENT.	-----	X	40.3.7	ACI 318: CH. 20, 25.2, 25.3, 26.6.1-26.6.3
N	2. REINFORCING BAR WELDING: a. VERIFY WELDABILITY OF REINFORCING BARS OTHER THAN ASTM A706.	-----	X	40.3.7	AWS D1.4 ACI 318: 26.6.4
N	b. INSPECT SINGLE-PASS FILLET WELDS, MAXIMUM 1/4", AND		X		
N	c. INSPECT ALL OTHER WELDS.	X			
Y	3. INSPECT ANCHORS CAST IN CONCRETE.	-----	X	40.3.7	ACI 318: 17.8.2
	4. INSPECT ANCHORS POST-INSTALLED IN HARDENED CONCRETE MEMBERS				
Y	a. ADHESIVE ANCHORS INSTALLED IN HORIZONTALLY OR UPWARDLY INCLINED ORIENTATIONS TO RESIST SUSTAINED TENSION LOADS.	X		-----	ACI 318: 17.8.2.4
	b. MECHANICAL ANCHORS AND ADHESIVE ANCHORS NOT DEFINED IN 4.a.		X		ACI 318: 17.8.2
Y	5. VERIFYING USE OF REQUIRED DESIGN MIX.	-----	X	40.3.7	ACI 318: CH. 19, 26.4.3, 26.4.4
	6. PRIOR TO CONCRETE PLACEMENT, FABRICATE SPECIMENS FOR STRENGTH TESTS, PERFORM SLUMP AND AIR CONTENT TEST, AND DETERMINE THE TEMPERATURE OF THE CONCRETE.	X	-----	40.3.7	ASTM C172 ASTM C31 ACI 318: 26.4, 26.12
Y	7. INSPECT CONCRETE PLACEMENT FOR PROPER APPLICATION TECHNIQUES.	X	-----	40.3.7	ACI 318: 26.5
Y	8. VERIFY MAINTENANCE OF SPECIFIED CURING TEMPERATURES AND TECHNIQUES.	-----	X	40.3.7	ACI 318: 26.5.3 -26.5.5
N	9. INSPECT ERECTION OF PRECAST CONCRETE MEMBERS.	-----	X	-----	ACI 318: 26.8
N	10. VERIFY IN-SITU CONCRETE STRENGTH PRIOR TO REMOVAL OF SHORES AND FORMS FROM BEAMS AND STRUCTURAL SLABS.	-----	X	40.3.7	ACI 318: 26.11.2
Y	11. INSPECT FORMWORK FOR SHAPE, LOCATION AND DIMENSIONS OF THE CONCRETE MEMBER BEING FORMED.	-----	X	40.3.7	ACI 318: 26.11.1, 26(b)

QUALITY ASSURANCE INSPECTION AND VERIFICATION OF STEEL CONSTRUCTION

SPECIAL INSPECTION REQUIRED Y/N	VERIFICATION AND INSPECTION	FREQUENCY OF INSPECTION		REFERENCE FOR CRITERIA	
		CONTINUOUS DURING TASK LISTED	PERIODICALLY DURING TASK LISTED	NFPA-5000 SECTION 403.3.10	REFERENCED STANDARD
	1. MATERIAL VERIFICATION OF HIGH-STRENGTH BOLTS, NUTS AND WASHERS:				
Y	a. IDENTIFICATION MARKINGS TO CONFORM TO ASTM STANDARDS SPECIFIED IN THE APPROVED CONSTRUCTION DOCUMENTS.	----	X	----	APPLICABLE ASTM MATERIAL SPECIFICATIONS, AISC 360 SECTION A3.3
Y	b. MANUFACTURER'S CERTIFICATE OF COMPLIANCE REQUIRED.	----	X	----	----
	2. INSPECTION OF HIGH-STRENGTH BOLTING:				
Y	a. SNUG-TIGHT JOINTS	----	X		
Y	b. PRETENSIONED AND SLIP CRITICAL JOINTS USING TURN-OF-NUT WITH MATCHMARKING, TWIST-OFF BOLT OR DIRECT TENSION INDICATOR METHODS OF INSTALLATION	----	X	----	AISC 360, SECTION M2.5
Y	c. PRETENSIONED AND SLIP CRITICAL JOINTS USING TURN-OF-NUT WITHOUT MATCHMARKING OR CALIBRATED WRENCH METHODS OF INSTALLATION	X	----		
	3. MATERIAL VERIFICATION OF STRUCTURAL STEEL AND COLD-FORMED STEEL DECK:				
Y	a. FOR STRUCTURAL STEEL, IDENTIFICATION MARKINGS TO CONFORM TO AISC 360	----	X		AISC 360 SECTION M5.5
Y	b. FOR OTHER STEEL, IDENTIFICATION MARKINGS TO CONFORM TO ASTM STANDARDS SPECIFIED IN THE APPROVED CONSTRUCTION DOCUMENTS	----	X		APPLICABLE ASTM MATERIAL STANDARDS
Y	c. MANUFACTURERS CERTIFIED TEST REPORTS	----	X		
	4. MATERIAL VERIFICATION OF WELD FILLER MATERIALS:				
Y	a. IDENTIFICATION MARKINGS TO CONFORM TO AWS SPECIFICATION IN THE APPROVED CONSTRUCTION DOCUMENTS.	----	----	----	AISC 360, SECTION A3.5
Y	b. MANUFACTURER'S CERTIFICATE OF COMPLIANCE REQUIRED.	----	----	----	----
	5. INSPECTION OF WELDING:				
	a. STRUCTURAL STEEL:				
Y	1) COMPLETE AND PARTIAL PENETRATION GROOVE WELDS.	X	----		
N	2) MULTIPASS FILLET WELDS.	X	----		
N	3) SINGLE-PASS FILLET WELDS > 5/16"	X	----	----	AWS D1.1
Y	4) PLUG & SLOT WELDS	X	----		
Y	5) SINGLE-PASS FILLET WELDS < 5/16"	----	X		
N	6) ROOF DECK WELDS.	----	X	----	AWS D1.3
N	b. REINFORCING STEEL:	----	----		
N	1) VERIFICATION OF WELDABILITY OF REINFORCING STEEL OTHER THAN ASTM A 706.	----	X		
N	2) REINFORCING STEEL- RESISTING FLEXURAL AND AXIAL FORCES IN INTERMEDIATE AND SPECIAL MOMENT FRAMES, AND BOUNDARY ELEMENTS OF SPECIAL REINFORCED CONCRETE SHEAR WALLS AND SHEAR REINFORCEMENT.	X	----	----	AWS D1.4 ACI 318 3.5.2
Y	3) SHEAR REINFORCEMENT.	X	----		
Y	4) OTHER REINFORCING STEEL	----	X		
	6. INSPECTION OF STEEL FRAME JOINT DETAIL FOR COMPLIANCE WITH APPROVED CONSTRUCTION DOCUMENTS:				
N	a. DETAILS SUCH AS BRACING AND STIFFENING.	----	X		
Y	b. MEMBER LOCATIONS.	----	X	----	----
Y	c. APPLICATION OF JOINT DETAILS AT EACH CONNECTION.	----	X		

QUALITY ASSURANCE INSPECTION AND VERIFICATION OF STEEL DECK CONSTRUCTION

SPECIAL INSPECTION REQUIRED Y/N	VERIFICATION AND INSPECTION TASK	FREQUENCY OF INSPECTION		REFERENCE FOR CRITERIA
		CONTINUOUSLY DURING TASK LISTED	PERIODICALLY DURING TASK LISTED	NFPA-5000 SECTION 40.3.10
Y	VERIFY DECK MATERIALS AND MILL CERTIFICATIONS	----	X	SDI-QA/QC
Y	VERIFY FIELD WELDING OF DECK	----	X	AWS D13, SDI C, SDI NC, SDI RD
Y	VERIFY MECHANICAL FASTENERS	----		SDI C, SDI NC, SDI RD
Y	VERIFY STEEL DECK INSTALLATION IN ACCORDANCE WITH CONSTRUCTION DOCUMENTS			SDI C, SDI NC, SDI RD

REQUIRED QUALITY ASSURANCE INSPECTION OF OPEN-WEB STEEL JOISTS AND JOIST GIRDERS

SPECIAL INSPECTION REQUIRED Y/N	VERIFICATION AND INSPECTION TASK	FREQUENCY OF INSPECTION		REFERENCE FOR CRITERIA
		CONTINUOUS DURING TASK LISTED	PERIODICALLY DURING TASK LISTED	NFPA-5000 TABLE
	1. INSTALLATION OF OPEN-WEB STEEL JOISTS AND JOIST GIRDERS.			
Y	a. END CONNECTIONS - WELDED OR BOLTED.	-----	X	403.10
	b. BRIDGING - HORIZONTAL OR DIAGONAL.	-----		403.10
Y	1. VISUALLY INSPECT ALL FIELD WELDS OF A MINIMUM OF 5 PERCENT OF THE JOISTS, RANDOMLY SELECTED.	-----	X	403.10

QUALITY ASSURANCE INSPECTION OF SEISMIC FORCE RESISTING SYSTEMS
(REQUIRED WHEN SDC = C, D, E OR F) AND
DESIGNATED SEISMIC SYSTEMS (REQUIRED WHEN SDC=D,E OR F)

SPECIAL INSPECTION REQUIRED Y/N	VERIFICATION AND INSPECTION TASK	FREQUENCY OF INSPECTION		REFERENCE FOR CRITERIA
		CONTINUOUS DURING TASK LISTED	PERIODICALLY DURING TASK LISTED	
Y	1. STRUCTURAL STEEL: a. STRUCTURAL WELDING REQUIRED BY AISC 341	X	-----	44.2.2
Y	2. STRUCTURAL WOOD: a. FIELD GLUING OPERATIONS OF ELEMENTS IN THE SEISMIC-FORCE-RESISTING SYSTEM.	X	-----	40.3.11
Y	b. NAILING, BOLTING, ANCHORING, AND OTHER FASTENING OF COMPONENTS WITHIN THE SEISMIC-FORCE-RESISTING SYSTEM, INCLUDING WOOD SHEAR WALLS, WOOD DIAPHRAGMS, DRAG STRUTS, BRACES, AND HOLD DOWNS.	-----	X	40.3.11
	3. COLD - FORMED STEEL FRAMING:			
Y	a. WELDING OF ELEMENTS IN SEISMIC-FORCE RESISTANCE	-----	X	44.8.1
Y	b. SCREW ATTACHMENTS, BOLTING, ANCHORING, AND OTHER FASTENING OF COMPONENTS WITHIN THE SEISMIC-FORCE-RESISTING SYSTEM.	-----	X	44.8.1
Y	4. ANCHORAGE:	-----	X	41.4

QUALITY ASSURANCE INSPECTION AND VERIFICATION OF COLD FORMED METAL FRAMING

SPECIAL INSPECTION REQUIRED Y/N	VERIFICATION AND INSPECTION TASK	FREQUENCY OF INSPECTION		REFERENCE FOR CRITERIA
		CONTINUOUS DURING TASK LISTED	PERIODICALLY DURING TASK LISTED	AS/1240 SECTION
Y	1. SEATING OF STUDS IN TRACK.	-----	X	-----
Y	2. WELDING OF ELEMENTS.	-----	X	D6.6
Y	3. SCREW ATTACHMENTS, BOLTING, ANCHORING, AND OTHER FASTENING OF COMPONENTS.	-----	X	D6.7
Y	4. STEEL STUD BRIDGING SPACING AND END ATTACHMENT	-----	X	D6.5
Y	5. WELDED CONNECTIONS ARE TOUCHED UP WITH PAINT.	-----	X	D6.6
Y	6. VERIFY STRUCTURAL STUD SIZE, DEPTH, AND GAGE.	-----	X	D6.5

fbt | architects

MAIL: 6501 Americas Pkwy NE., Ste. 300
Albuquerque, NM 87110

PHO: 505.883.5200
FAX: 505.884.5390
WEB: www.fbtarch.com

CONSULTANT

CIVIL
Bohannon Huston
7500 Jefferson St NE,
Albuquerque, NM 87109
p_505.823.100

STRUCTURAL
Walla Engineering Ltd
6501 Americas Pkwy NE Ste. 302
Albuquerque, NM 87110
p 505.243.9287

M/E/P/FP
Bridgers and Paxton
 4600-C Montgomery Blvd. NE
 Albuquerque, New Mexico 87109
 p_505.883.4111 f_505.888.1436

INTERIORS
Studio M
 6501 Americas Pkwy NE Ste. 301
 Albuquerque, NM 87110
 p 505.243.9287

SITE
Groundwork Studio
6501 Americas Pkwy NE Ste. 350
Albuquerque, NM 87110
p_505.212.9126

FOOD SERVICE
Standard Kitchen Supply
 2405 Candelaria Rd. NE,
 Albuquerque, NM 87107
 p. 505.341.1054



**Dzilh-Na-O-Dith-Hle -
New Dormitory Building
Construction Documents**

35 Road 7585, Bloomfield, NM
87413

OCTOBER 5, 2020


MARK	DATE	DESCRIPTION
ISSUE:		
DATE:		
PROJECT NO:		751
CAD DWG FILE:		
DRAWN BY:		KV
CHECKED BY:		MJW

SHEET TITLE


STRUCTURAL QUALITY ASSURANCE INSPECTIONS

PREVIOUSLY ISSUED
SEE REVISION CLOUDS
FOR UPDATES

S-002



GENERAL NOTES


- A. ALL PERIMETER DIMENSIONS ARE TO FACE OF CONCRETE STEMWALL UNLESS NOTED OTHERWISE.
- B. C/J INDICATES CONCRETE SLAB CONTROL JOINT. SEE DETAIL E4/S-301.
- C. B/L EL = ###'-##" INDICATES BOTTOM OF FOOTING ELEVATION.
- D. BF-# INDICATES BRACED FRAME LOCATION. SEE SHEET S-601 FOR BRACED FRAME ELEVATIONS AND DETAILS.
- E. FD  INDICATES FLOOR DRAIN. SEE ARCHITECTURAL AND PLUMBING FOR LOCATION. SLOPE TOP OF SLAB TO DRAIN.

KEYED NOTES

- 1 5" THICK CONCRETE SLAB W/ #4 @ 18" OC (CENTERED IN SLAB) OVER 4" AGGREGATE BASE COURSE OVER VAPOR BARRIER PER ARCH - SEE CIVIL.
- 2 RECESS TOP OF SLAB 2". SEE ARCHITECTURAL FOR EXTENTS. MAINTAIN MINIMUM 5" THICK SLAB PER C2/S-301.
- 3 HSS3x3x1/4 PARTITION WALL POSTS @ 8'-0" OC MAX. AND AT EACH END OF WALL. COORDINATE WALL LOCATION WITH ARCHITECTURAL. SEE C4/S-301 FOR POST ATTACHMENT.


ISOLATED FOOTING SCHEDULE				
Mark	Length	Width	DEPTH	REINFORCING
F1	2' - 6"	2' - 6"	1' - 0"	(4) #4 EACH WAY
F2	3' - 0"	3' - 0"	1' - 0"	(4) #4 EACH WAY
F3	3' - 6"	3' - 6"	1' - 0"	(5) #4 EACH WAY
F4	4' - 0"	4' - 0"	1' - 0"	(6) #4 EACH WAY
F5	4' - 6"	4' - 6"	1' - 0"	(6) #5 EACH WAY
F6	5' - 0"	5' - 0"	1' - 0"	(5) #5 EACH WAY

PREVIOUSLY ISSUED
SEE REVISION CLOUDS
FOR UPDATES



GENERAL NOTES

- A. PROVIDE JOIST BRIDGING PER LATEST SJI REQUIREMENTS.
- B. DESIGN JOISTS FOR 10 PSF NET UPLIFT TYPICAL UNLESS NOTED OTHERWISE
- C. FRAME AROUND ROOF DECK OPENINGS PER DETAIL 83/S-505 UNO.
- D. SEE C1/S-505 FOR LIGHTGAGE STEEL LINTEL SCHEDULE AND DETAILS AT ALL EXTERIOR OPENINGS AND INTERIOR BEARING WALLS.
- E. DIMENSIONS ARE TO EXTERIOR FACE OF STUD WALL.
- F. F INDICATES BASE PLATE TYPE PER A1/S-301.
- G. GF INDICATES BRACED FRAME LOCATION. SEE SHEET S-601 FOR BRACED FRAME ELEVATIONS AND DETAILS.



KEYED NOTES

- 1 1 1/2" TYPE "B", 20 GA PAINTED METAL DECK WITH NESTABLE SIDELAPS. ATTACH DECK TO SUPPORTS PERPENDICULAR TO RISBS WITH (5) 5/8" DIA PUDDLE WELDS PER 24" ATTACH SIDELAPS WITH #10 T SCREWS @ 12" OC.
- 2 1.5x17x7/84 HORIZONTAL BRIDGING EQUIVALENT SPACED AS SHOWN WELD TO TOP AND BOTTOM CHORDS OF JOISTS.
- 3 3" CONCRETE SLAB W/ 6#xW-2, 1XW2, 1 WVF OVER 2" TYPE "VL" 20 GA GALVANIZED COMPOSITE DECK (5" TOTAL THICKNESS) - 2 SPAN MIN ATTACH DECK W/ (4) 5/8" DIA PUDDLE WELDS PER 36" WIDE SHEET TO EACH SUPPORT AND TO SUPPORTS PARALLEL TO RISBS W/ #10 T SCREWS @ 12" OC. FINISH FLOOR ATTACHMENT 11/4"X6" UNLESS NOTED OTHERWISE. MSLE = CEB. SILL SAWCUT 1/8" WIDE X 1 1/2" DEEP AT JOIST CHORDS.
- 4 3" TYPE "N", 20 GA PAINTED METAL DECK WITH NESTABLE SIDELAPS. ATTACH DECK TO SUPPORTS PERPENDICULAR TO RISBS WITH (4) 5/8" DIA PUDDLE WELDS PER 24" WIDE SHEET AND TO SUPPORTS PARALLEL TO RISBS WITH 5/8" DIA PUDDLE WELDS @ 12" OC ATTACH SIDELAPS WITH #10 T SCREWS @ 12" OC.
- 5 3" TYPE "N", 18 GA PAINTED METAL DECK WITH NESTABLE SIDELAPS. ATTACH DECK TO SUPPORTS PERPENDICULAR TO RISBS WITH (4) 5/8" DIA PUDDLE WELDS PER 24" WIDE SHEET AND TO SUPPORTS PARALLEL TO RISBS WITH 5/8" DIA PUDDLE WELDS @ 8" OC PER 24" WIDE SHEET AND TO SUPPORTS PARALLEL TO RISBS WITH 8x1 1/2" WOOD SCREWS AND WASHERS @ 8" OC ATTACH SIDELAPS WITH #10 T SCREWS @ 12" OC.
- 6 BRACED WALL LOCATION WITH 4"x4" 8A+STRAP EXTERIOR FACE OF WALL. SEE PENTHOUSE ROOF FRAMING PLAN FOR EXTENT OF BRACING. SEE A715-S/65 FOR DETAILS.
- 7 SUNSHADE. SEE ARCHITECTURAL.



Dzilth-Na-O-Dith-Hle - New Dormitory Building Construction Documents

35 Road 7585, Bloomfield, NM
87413

OCTOBER 5, 2020


MARK	DATE	DESCRIPTION
1	30 OCT 2020	CLARIFICATIONS
ISSUE:		
DATE:		
PROJECT NO:		751
CAD DWG FILE:		
DRAWN BY:		KV
CHECKED BY:		MJW

SHEET TITLE

ROOF FRAMING PLAN

PREVIOUSLY ISSUED
SEE REVISION CLOUDS
FOR UPDATES

11/17/2020 2:03:50 PM Dzilh-Na-O-Dith-Hle - New Dormitory Building



fbt

architects

MAIL: 6501 Americas Pkwy NE, Ste. 300
Albuquerque, NM 87110

PHO: 505.883.5200

FAX: 505.884.5290

WEB: www.fbtarch.com

CONSULTANT

CIVIL

Bohannon Huston

7500 Jefferson St. NE,
Albuquerque, NM 87109

p_505.823.100

STRUCTURAL

Walla Engineering Ltd

6501 Americas Pkwy NE Ste. 302
Albuquerque, NM 87110

p_505.243.9287

M/E/P/FP

Bridgers and Paxton

4600-C Montgomery Blvd. NE
Albuquerque, New Mexico 87109

p_505.883.4111 f_505.888.1436

INTERIORS

Studio M

6501 Americas Pkwy NE Ste. 301
Albuquerque, NM 87110

p_505.243.9287

SITE

Groundwork Studio

6501 Americas Pkwy NE Ste. 350
Albuquerque, NM 87110

p_505.212.9126

FOOD SERVICE

Standard Kitchen Supply

2405 Candelaria Rd. NE,
Albuquerque, NM 87107

p_505.341.1054

ENGINEER

11/17/2020

Dzilh-Na-O-Dith-Hle -
New Dormitory Building

Construction Documents

35 Road 7585, Bloomfield, NM
87413

OCTOBER 5, 2020

MARK	DATE	DESCRIPTION
1	30 OCT 2020	CLARIFICATIONS

ISSUE:

DATE:

PROJECT NO: 751

CAD DWG FILE:

DRAWN BY: KV

CHECKED BY: MJW

SHEET TITLE

FOUNDATION SECTIONS


S-301

School Information

PREVIOUSLY ISSUED
SEE REVISION CLOUDS
FOR UPDATES

Dzilth-Na-O-Dith-Hle - New Dormitory Building

11/17/2020 2:03:51 PM



fbt | architects

MAIL: 6501 Americas Pkwy NE, Ste. 300
Albuquerque, NM 87110

PHO: 505.883.5200
FAX: 505.884.5290
WEB: www.fbtarch.com

CONSULTANT

CIVIL
Bohannon Huston
7500 Jefferson St. NE,
Albuquerque, NM 87109
p_505.823.100

STRUCTURAL
Walla Engineering Ltd
6501 Americas Pkwy NE Ste. 302
Albuquerque, NM 87110
p_505.243.9287

M/E/P/FP
Bridgers and Paxton
4600-C Montgomery Blvd. NE
Albuquerque, New Mexico 87109
p_505.883.4111 f_505.888.1436

INTERIORS
Studio M
6501 Americas Pkwy NE Ste. 301
Albuquerque, NM 87110
p_505.212.9287

SITE
Groundwork Studio
6501 Americas Pkwy NE Ste. 350
Albuquerque, NM 87110
p_505.212.9126

FOOD SERVICE
Standard Kitchen Supply
2405 Candelaria Rd. NE,
Albuquerque, NM 87107
p_505.341.1054

ENGINEER

**Dzilth-Na-O-Dith-Hle -
New Dormitory Building**

Construction Documents

35 Road 7585, Bloomfield, NM
87413

OCTOBER 5, 2020

MARK	DATE	DESCRIPTION
1	30 OCT 2020	CLARIFICATIONS

ISSUE:
DATE:
PROJECT NO: 751
CAD DWG FILE:
DRAWN BY: KV
CHECKED BY: MJW

SHEET TITLE
FRAMING SECTIONS

S-305

School Information

11/17/2020 2:03:52 PM Dzilh-Na-O-Dith-Hle - New Dormitory Building

fbt

architects

MAIL: 6501 Americas Pkwy NE, Ste. 300
Albuquerque, NM 87110

PHO: 505.883.5200

FAX: 505.884.5290

WEB: www.fbtarch.com

CONSULTANT

CIVIL

Bohannon Huston

7500 Jefferson St. NE,
Albuquerque, NM 87109
p_505.823.100

STRUCTURAL

Walla Engineering Ltd

6501 Americas Pkwy NE Ste. 302
Albuquerque, NM 87110
p_505.243.9287

M/E/P/FP

Bridgers and Paxton

4600-C Montgomery Blvd. NE
Albuquerque, New Mexico 87109
p_505.883.4111 f_505.888.1436

INTERIORS

Studio M

6501 Americas Pkwy NE Ste. 301
Albuquerque, NM 87110
p_505.243.9287

SITE

Groundwork Studio

6501 Americas Pkwy NE Ste. 350
Albuquerque, NM 87110
p_505.212.9126

FOOD SERVICE

Standard Kitchen Supply

2405 Candelaria Rd. NE,
Albuquerque, NM 87107
p_505.341.1054

ENGINEER

Dzilh-Na-O-Dith-Hle -
New Dormitory Building

Construction Documents

35 Road 7585, Bloomfield, NM
87413

OCTOBER 5, 2020

MARK	DATE	DESCRIPTION
	30 OCT 2020	CLARIFICATIONS

ISSUE:

DATE:

PROJECT NO: 751

CAD DWG FILE:

DRAWN BY: KV


CHECKED BY: MJW

SHEET TITLE

FRAMING SECTIONS

S-306

School Information



fbt | architects

MAIL: 6501 Americas Pkwy NE, Ste. 300
Albuquerque, NM 87110

PHO: 505.883.5200
FAX: 505.884.5390
WEB: www.fbtarch.com

CONSULTANT

CIVIL
Bohannon Huston
7500 Jefferson St. NE,
Albuquerque, NM 87109
p_505.823.100

STRUCTURAL
Walla Engineering Ltd
6501 Americas Pkwy NE Ste. 302
Albuquerque, NM 87110
p_505.243.9287

M/E/P/FP
Bridgers and Paxton
4600-C Montgomery Blvd. NE
Albuquerque, New Mexico 87109
p_505.883.4111 f_505.888.1436

INTERIORS
Studio M
6501 Americas Pkwy NE Ste. 301
Albuquerque, NM 87110
p_505.212.9126

SITE
Groundwork Studio
6501 Americas Pkwy NE Ste. 350
Albuquerque, NM 87110
p_505.212.9126

FOOD SERVICE
Standard Kitchen Supply
2405 Candelaria Rd. NE,
Albuquerque, NM 87107
p_505.341.1054

ENGINEER

Dzilth-Na-O-Dith-Hle - New Dormitory Building

Construction Documents

35 Road 7585, Bloomfield, NM 87413

OCTOBER 5, 2020

MARK	DATE	DESCRIPTION
	30 OCT 2020	CLARIFICATIONS

ISSUE:

DATE:

PROJECT NO: 751

CAD DWG FILE:

DRAWN BY: KV

CHECKED BY: MJW

SHEET TITLE

FRAMING DETAILS

S-505

School Information



- A. CONTRACTOR SHALL PERFORM DAILY CLEANUP WHEN FINISH GRAD WORK IS BEING PERFORMED.
- B. SEE ENLARGED PLANS FOR CLASSROOM LAYOUTS, CASEWORK, ETC.
- C. SEE ROOM MATERIALS LEGEND ON ID SHEETS FOR FLOOR BASE, WALL AND CEILING MATERIAL INFORMATION.
- D. PROVIDE WOOD BLOCKING IN ALL WALLS FOR SUPPORT OF PARTITIONS, SIGNAGE, ACCESSORIES, AND OTHER WALL SUPPORTED ITEMS AS REQUIRED.
- E. SEE ANSI GUIDELINES FOR INFORMATION REGARDING ACCESSIBILITY REQUIREMENTS
- F. PROVIDE SEALANT AT INTERSECTIONS OF ALL DISSIMILAR MATERIALS.
- G. COORDINATE ALL PLUMBING FIXTURES WITH THE PLUMBING DRAWINGS. IN CASE OF ANY DISCREPANCY NOTIFY ARCHITECT AND ENGINEER PRIOR TO BEGINNING OF INSTALLATION.
- H. PROVIDE WATER RESISTANT GYPSUM BOARD AT ALL WET LOCATIONS.
- I. FURNISH AND INSTALL 5/8" ARBUSE RESISTANT GYP. BOARD TO 6'-0" AFF AT ALL CORRIDOR AND VESTIBULE WALL LOCATIONS.

	<p>DOOR TYPE (FOR INFORMATION SEE SHEET A-601)</p>
	<p>BUILDING ELEVATION</p>
	<p>INTERIOR ELEVATION</p>
	<p>BUILDING/ WALL SECTION</p>
	<p>STRUCTURAL GRID</p>
	<p>WINDOW TYPE (FOR INFORMATION SEE SHEET A-603)</p>
	<p>PARTITION TYPE (FOR INFORMATION SEE SHEET A-601)</p>
	<p>FIRE EXTINGUISHER</p>

001 EXPOSED STEEL COLUMN, PAINT SEE STRUCTURAL.

002 AIR DISTRIBUTION SYSTEM ENCLOSED IN PLASTIC LAMINATE CASEWORK. SEE

003 ENLARGED PLANS AND ELEVATIONS. SEE MECHANICAL.

004 CASEWORK, UPPER AND LOWER CABINETS WHERE SHOWN. SEE ENLARGED

005 PLANS AND ELEVATIONS. PROVIDE 1/2" CHECKING IN WALL AS REQUIRED.

006 DASHED FURNISHINGS NOT IN CONTRACT.

007 DASHED LINE INDICATES CANOPY / SUNSHADE ABOVE. SEE BUILDING AND WALL

008 SECTIONS.

009 54" HIGH WALL, 8" STEEL STUDS AT 48" OC WITH 6" STEEL GYPSUM BOARD ON

010 BOTH SIDES. TAPE, TEXTURE AND PAINT. 1/4" HARKWOOD WOOD. SAND FOUR

011 SIDES AND RADIIUS ALL EXPD EDGES 1/4". FINISH WOOD SPECIES TO

012 MATCH WOOD CEILING. SEE ROP FOR INFORMATION.

013 POWER ACTUATED DOOR OPENER SWITCH BUTTON, COORDINATE WIRING RUN

014 THROUGH ROOF FRAME. SEE MECHANICAL DRAWINGS AND COORDINATE.

015 ELECTRICAL REQUIREMENTS WITH ELECTRICAL DRAWINGS. INSTALL PNEUMATIC

016 ACTUATOR, BOX FOR DOOR OPERATOR ABOVE CEILING. MOUNT SWITCH PER AS

017 STIPPLED.

018

019 ROOF ACCESS LADDER AND HATCH. SEE ROOF DETAILS S-A-141.

020 RECYCLE PLASTIC BIN, OWNER PROVIDED. OWNER PROVIDED.

021 RECYCLE PAPER BIN, OWNER PROVIDED. OWNER PROVIDED.


022 RECYCLE/TRASH COMBO CONTAINER. OWNER PROVIDED.

023 WALL, MOUNTED, SEE PLUMBING.

024 OWNER FURNISHED REFRIGERATOR. SEE PLUMBING AND ELECTRICAL FOR


025 ROUGH IN REQUIREMENTS.

026 VIDEO DOOR PHONE. SEE ELECTRICAL AND TECHNOLOGY DRAWINGS.




A5 NO SMOKING SIGN
3/4" = 1'-0"

TN PN
A1 FLOOR PLAN
1/8" = 1'-0"



- ### GENERAL NOTES
- A. ALL DIMENSIONS ARE TO FACE OF STEEL STUDS OR MASONRY, UNLESS NOTED OTHERWISE.
 - B. REFER TO ENLARGED PLAN FOR ADDITIONAL DIMENSIONS & DETAILED SPACE LAYOUTS.
 - C. SEE SITE PLAN FOR BUILDING LOCATION LAYOUT.
 - D. SEE PARTITION DETAILS SHEET A-501 FOR PARTITION INFORMATION.
 - E. SEE ANSI GUIDELINES FOR INFORMATION REGARDING ACCESSIBILITY REQUIREMENTS.
 - F. SEE FLOOR PLANS, REFLECTED CEILING PLANS, AND ID SHEETS FOR FLOOR, WALL AND CEILING INFORMATION.
 - H. COLUMN GRIDS "I" AND "O" ARE NOT USED.
 - I. FURNISH AND INSTALL 5/8" FIBERROCK VHI TYPE "X" GYP. BOARD TO 6'-0" F.F. AT ALL HALLWAY AND VESTIBULE WALL LOCATIONS.

- ### SYMBOL LEGEND
- (XX) DOOR TYPE (FOR INFORMATION SEE SHEET A-601)
 - Ref 1 A101 1 Ref BUILDING ELEVATION
 - 1Ref 1 A101 1Ref INTERIOR ELEVATION
 - 1Ref 1 A101 1Ref BUILDING/WALL SECTION
 - (X) STRUCTURAL GRID
 - (x) WINDOW TYPE (FOR INFORMATION SEE SHEET A-603)
 - (X) PARTITION TYPE (FOR INFORMATION SEE SHEET A-501)
 - F.E.C FIRE EXTINGUISHER



A1 DIMENSION PLAN
1/8" = 1'-0"

A5 DIMENSION PLAN - CLERESTORY
1/8" = 1'-0"

fbt | architects

MAIL: 6501 Americas Pkwy NE, Ste. 300
Albuquerque, NM 87110

PHO: 505.883.5200
FAX: 505.884.5290
WEB: www.fbtarch.com

CONSULTANT

ARCHITECT

Dzilth-Na-O-Dith-Hle - New Dormitory Building

CONSTRUCTION

35 Road 7585, Bloomfield, NM 87413

DECEMBER 4TH, 2020


MARK	DATE	DESCRIPTION

ISSUE:
DATE: PROJECT 1751
CAD DWG FILE:
DRAWN BY Author
CHECKED BY Checker

SHEET TITLE
DIMENSION PLAN

A-111

School Information



GENERAL NOTES

- ALL CEILING ELEVATIONS ARE ABOVE FINISH FLOOR UNLESS NOTED OTHERWISE.
- CONTROL DRYWALL TEXTURE OVER SPRAY AT ALL LOCATIONS OF EXPOSED CEILING. ENSURE NO OVER SPRAY ON STRUCTURE AND/OR BATT INSULATION.
- CONTRACTOR SHALL COORDINATE WITH MECHANICAL, ELECTRICAL, AND FIRE PROTECTION WORK TO ACCOMPLISH CEILING HEIGHTS. NOTIFY ARCHITECTS OF ANY CONFLICTS PRIOR TO INSTALLATION.
- EXACT LOCATION OF SPRINKLER HEADS AND ALL SPECIAL SYSTEMS EQUIPMENT SHALL BE COORDINATED WITH ARCHITECT PRIOR TO SYSTEM INSTALLATION. SPRINKLER HEADS SHALL BE INSTALLED IN CENTER OF CEILING TILE.
- SEE ID SHEETS FOR WALL ACCENT PAINT COLORS.
- ALL PAINT COLORS TO BE SELECTED BY ARCHITECT UNLESS NOTED OTHERWISE.
- COORDINATE LOCATIONS OF CEILING ACCESS PANELS WITH MECHANICAL AND PLUMBING.
- ALL DIMENSIONS ARE TO FACE OF FINISH.

REFLECTED CEILING LEGEND

- 1 SIM BUILDING / WALL SECTION
- SPOT ELEVATION
- GYPSUM BOARD CEILING, TAPE, TEXTURE AND PAINT.
- EXPOSED TONGUE AND GROOVE WOOD DECKING AND GLULAM BEAMS.
- 2' X 2' ACOUSTIC, LAY-IN CEILING TILE.
- 2' X 4' ACOUSTIC, LAY-IN CEILING TILE.
- SUPPLY AIR DIFFUSER. SEE MECHANICAL.
- RETURN AIR DIFFUSER. SEE MECHANICAL.
- LIGHT FIXTURES. NOT ALL TYPES SHOWN IN THIS LEGEND. SEE ELECTRICAL FOR COMPLETE FIXTURE SCHEDULE

NOTE: REFER ALSO TO ELECTRICAL AND MECHANICAL DRAWINGS FOR REFLECTED CEILING PLAN ITEMS NOT SHOWN OR NOTED ON ARCHITECTURAL REFLECTED CEILING PLANS

KEYED NOTES

- 030 ROOF ACCESS LADDER AND HATCH. SEE ROOF DETAILS A-141.
- 080 EXPOSED TO STRUCTURE. PAINT ALL STRUCTURAL ELEMENTS INCLUDING DECK AND ELECTRICAL, MECHANICAL AND FIRE PROTECTION ITEMS. COLOR TO BE SELECTED BY ARCHITECT.
- 081 PREFINISHED ALUMINUM SUNSHADE. SEE BUILDING AND WALL SECTIONS.
- 082 GYP BOARD BULKHEAD. PAINT.
- 083 STUCCO SOFFIT
- 102 EXPOSED TONGUE AND GROOVE WOOD DECKING AND GLULAM BEAMS. STAINED. COLOR TO BE SELECTED BY ARCHITECT. SEE WALL SECTIONS AND DETAILS.
- 104 EXTERIOR CANOPY. PAINT ALL EXPOSED STEEL. SEE BUILDING AND WALL SECTIONS. SEE STRUCTURAL.

A4 BULKHEAD DETAIL

1 1/2" = 1'-0"

A5 SOFFIT DETAIL

1 1/2" = 1'-0"

CONSULTANT

CIVIL
Bohannon Huston
7500 Jefferson St. NE,
Albuquerque, NM 87109
p_505.823.100

STRUCTURAL
Walla Engineering Ltd
6501 Americas Pkwy NE Ste. 302
Albuquerque, NM 87110
p_505.243.9287

M/E/P/FP
Bridgers and Paxton
4600-C Montgomery Blvd. NE
Albuquerque, New Mexico 87109
p_505.883.4111 f_505.888.1436

INTERIORS
Studio M
6501 Americas Pkwy NE Ste. 301
Albuquerque, NM 87110
p_505.243.9287

SITE
Groundwork Studio
6501 Americas Pkwy NE Ste. 350
Albuquerque, NM 87110
p_505.212.9126

FOOD SERVICE
Standard Kitchen Supply
2405 Candelaria Rd. NE,
Albuquerque, NM 87107
p_505.341.1054

ENVELOPE AND ROOF CONSULTANT
Armstrong Group INC.
2415 Princeton Ave, NE Suite E
Albuquerque, NM 87107
p_505.235.7596

AV & TECHNOLOGY
Network Cabling, INC
3100 La Plata HWY.
Farmington, NM 87401
p_505.598.5054



Dzilth-Na-O-Dith-Hle - New Dormitory Building

CONSTRUCTION DOCUMENTS

35 Road 7585, Bloomfield, NM
87413

DECEMBER 4TH, 2020

MARK	DATE	DESCRIPTION
------	------	-------------


ISSUE:	
DATE:	
PROJECT NO:	751
CAD DWG FILE:	
DRAWN BY:	Author
CHECKED BY:	Checker

SHEET TITLE

REFLECTED CEILING PLANS

Dzilth-Na-O-Dith-Hle - New Dormitory Building

12/6/2020 9:04:15 PM



ROOF COMPOSITION LEGEND	
(A)	ROOF TYPE A • PVC ROOFING MEMBRANE SYSTEM
(B)	ROOF TYPE B • STANDING SEAM METAL ROOFING

- ### GENERAL NOTES

A. THE ROOFING SYSTEM SHALL BE INSTALLED PER MANUFACTURER'S REQUIREMENTS FOR A 20 YEAR WARRANTY. INSTALL PER MOST STRINGENT REQUIREMENT BETWEEN PLANS, SPECIFICATIONS, MANUFACTURER'S REQUIREMENTS, AND IN ACCORDANCE WITH THE NRCA ROOFING & WATERPROOFING MANUAL, CURRENT EDITION.

B. ROOFING AND FLASHING SYSTEM REQUIRED TO CONFORM TO ES-1 WIND DESIGN STANDARD FOR EDGE SYSTEMS USED WITH LOW SLOPE ROOFING SYSTEMS.

C. FABRICATE AND INSTALL ALL METAL FLASHING AND ACCESSORIES PER RECOMMENDATIONS OF SMACNA ARCHITECTURAL SHEET METAL MANUAL, CURRENT EDITION, AND NRCA ROOFING AND WATERPROOFING MANUAL, CURRENT EDITION.

D. PROVIDE SHOP DRAWINGS FOR ALL ROOF ACCESSORIES, SHEET METAL, TAPERED INSULATION LAYOUT, ETC.

E. PROVIDE CRICKETS ON THE UPHILL SIDE OF ALL EQUIPMENT, OPENINGS, CURBS, ETC. GREATER THAN 12" IN WIDTH.

F. SLOPE ALL CRICKETS 1/4" MINIMUM GREATER THAN THE SLOPE OF THE DECK, WITH A MINIMUM 3 TO 1 LENGTH TO WIDTH RATIO. MAINTAIN POSITIVE DRAINAGE UNLESS NOTED OTHERWISE.

G. PRE-DRILL ALL METAL FLASHING / COUNTER FLASHING MATERIAL PRIOR TO INSTALLING FASTENERS.

H. ALL PLUMBING VENTS MUST MAINTAIN AN 18" MINIMUM DISTANCE ABOVE ROOF, TYPICAL.

I. PROVIDE A MINIMUM 12" HIGH VERTICAL DISTANCE BETWEEN TOP OF ROOFING FIELD MEMBRANES AND TERMINATION OF ALL FLASHINGS / COUNTER FLASHINGS AND FLASHING MEMBRANES. SEE DETAILS AND ROOFING MANUFACTURERS REQUIREMENTS.

J. PRIME AND PAINT ALL EXPOSED FERROUS METAL UNLESS OTHERWISE NOTED.

K. PROVIDE PRE-MANUFACTURED STANDS, MIRO INDUSTRIES, OR APPROVED EQUIVALENT, FOR ALL ROOF TOP PIPING AND CONDUITS ACROSS ROOF. DO NOT EXCEED MAXIMUM LOAD WEIGHT. INSTALL PER MANUFACTURERS REQUIREMENTS. PIPES 1-1/2" AND SMALLER SHALL BE SUPPORTED AT 8'-0" O.C. MAX. AND PIPES 2" AND LARGER SHALL BE SUPPORTED AT 10'-0" O.C. MAX. SEE ROOF DETAILS A-141/A-142.

L. LOCATIONS OF ROOF TOP EQUIPMENT, DUCTWORK, ROOF PENETRATIONS, FLASHINGS, CURBS, ETC. THAT ARE INDICATED ON THE ROOF PLAN DRAWINGS NEED TO BE COORDINATED IN THE FIELD.

M. IMMEDIATELY NOTIFY ARCHITECT OF ANY CONFLICT BETWEEN ROOFING MANUFACTURERS RECOMMENDATION FOR ANY GIVEN CONDITION AND ARCHITECT'S DETAILS.

N. SLOPE DIRECTION INDICATED BY ARROW ON ROOF PLAN. MAINTAIN DRAINAGE AND SLOPES LISTED.

O. EXTEND GAS LINES, CONDUITS, VENTS ETC. PENETRATING THRU ROOF PER DETAILS ON SHEETS A-141/A-142. SLEEVE WIRE AND CABLE PENETRATIONS THRU ROOF WITH GOOSE NECK PIPE OR CONDUIT.

P. FURNISH AND INSTALL TREATED 1/2" OR THICKNESS AS DETAILED CDX PLYWOOD ON INSIDE FACE OF ALL PARAPETS.

Q. FURNISH AND INSTALL TREATED WOOD BLOCKING AT ROOF MEMBRANE TERMINATION FASTENING LOCATIONS.

R. FURNISH AND INSTALL INSULATION AT ALL MECHANICAL CURBS IF NOT PROVIDED BY MANUFACTURER.

S. TURN FLASHING 90 DEGREES VERTICALLY INTO FASCIA WITH MITERED CORNER AT ALL EXPOSED FLASHING CORNERS.

T. PRIOR TO INSTALLATION OF INTERIOR DRYWALL FINISH CONTRACTOR SHALL TEST ROOF DRAINS FOR LEAKS AS FOLLOWS:
a. FIRST FILL DRAIN BOWL ONLY TO CHECK PLUMBING SEAL
b. THEN PLUG ROOF DRAIN AND FLOOD AREA OF ROOF AROUND DRAIN WITH 2" OF WATER
c. TEST ROOF DRAIN CONNECTION TO VERTICAL AND HORIZONTAL PLUMBING LEADERS SEAL ALL LEAK AREAS.
d. CHECK ROOFING SECUREMENT TO DRAIN
e. INSTALL RUBBERIZED BOOT AROUND CONNECTIONS OF ROOF DRAIN TO VERTICAL LEADER. CLAMP TIGHTLY TO PROVIDE SUPPORT AND WEATHER TIGHT SEAL.

U. THE ROOFING CONTRACTOR SHALL PROVIDE FASTENERS AS REQUIRED FOR CORROSIVE AGENTS ADDED TO TREATED WOOD NAILERS AND AS RECOMMENDED BY THE ROOFING MANUFACTURER REQUIRED FOR THE WARRANTY.

V. FURNISH AND INSTALL MANUFACTURERS WALK PAD, INSTALL AT THE FOLLOWING LOCATIONS: (1) AT ALL POINTS OF ROOF LANDING AT ACCESS LADDERS, DOORWAYS, HATCHES ETC. (2) ALONG DIRECT PATH TO ROOF TOP UNITS FROM POINTS OF LANDING, (3) TWO ROW WIDTH AROUND ROOF TOP UNITS. DO NOT COVER WELDED TPO SEAMS WITH WALK PAD. PROVIDE FOR A GAP OVER SEAM SPACED AS RECOMMENDED BY MANUFACTURER BUT IT NOT LESS THAN 6". MAXIMUM LENGTH OF ANY SINGLE RUN OF WALK PAD TO BE NO MORE THAN 10'-0". PROVIDE 3" GAP BETWEEN ROWS OF WALK PADS FOR POSITIVE DRAINAGE.

W. COORDINATE ALL ROOF PENETRATIONS BETWEEN ARCHITECTURAL PLUMBING, AND MECHANICAL WORK. NOTIFY ARCHITECT OF ANY CONFLICTS PRIOR TO PERFORMING WORK.

X. PAINT ALL EXPOSED DUCTS, ELECTRICAL CONDUITS, GAS LINES ETC. RUNNING VERTICAL ON WALLS AND HORIZONTALLY ON ROOF. COORDINATE WITH MECHANICAL, ELECTRICAL AND PLUMBING. PAINT COLOR TO BE SELECTED BY ARCHITECT.

Y. FURNISH AND INSTALL PRECAST CONCRETE SPLASHBLOCK AT TERMINATION OF ALL DOWNSPOUTS AND OR SCUPPER OVERFLOWS THAT DO NOT TERMINATE INTO CATCHBASINS. PROVIDE AT BOTH AT GRADE TERMINATIONS, AND ON DOWNSPOUTS & SCUPPERS THAT TERMINATE ONTO A LOWER ROOF.

Z. CONTRACTOR SHALL FIELD VERIFY ALL DIMENSIONS AND LAYOUT OF BOTH THE SITE AND BUILDING ELEMENTS. COORDINATE FIELD INFORMATION WITH THE ARCHITECT PRIOR TO ANY CONSTRUCTION ACTIVITY.
- ### KEYED NOTES

125 24 GA. METAL COPING CAP. SEE ROOF DETAILS A-141
129 22 GA. METAL LEADER HEAD AND DOWNSPOUT. TERMINATE AT SPLASH BLOCK. SEE ROOF DETAILS.
130 OVERFLOW SCUPPER. SEE ROOF DETAILS.
137 MECHANICAL EQUIPMENT. MOUNT PER ARCHITECTURAL DETAILS. COORDINATE WITH MECHANICAL REQUIREMENTS. SEE MECHANICAL.
138 WALL MOUNTED SUN SHADES. SEE ELEVATIONS, BUILDING AND WALL SECTIONS.
139 PREMANUFACTURED ROOF ACCESS LADDER AND HATCH. COORDINATE ROOF PENETRATIONS WITH STRUCTURAL. SEE DETAIL C1A-141.
141 PRIMARY ROOF DRAIN. SEE ROOF DETAILS AND PLUMBING DRAWINGS.
142 WALK PAD. SEE GENERAL NOTES FOR ADDITIONAL INFORMATION.
143 SNOW RETENTION SYSTEM.
144 TAPERED INSULATION ROOF CRICKET. SEE GENERAL NOTES FOR ADDITIONAL INFORMATION.
156 6" DIVIDING WALL. SEE DETAIL A5A-142.

fbt | architects

MAIL: 6501 Americas Pkwy NE, Ste. 300 Albuquerque, NM 87110
PHO: 505.883.5200 FAX: 505.884.5290
WEB: www.fbtarch.com

CONSULTANT

CIVIL
Bohannon Huston
7500 Jefferson St. NE,
Albuquerque, NM 87109
p_505.823.100

STRUCTURAL
Walla Engineering Ltd
6501 Americas Pkwy NE Ste. 302
Albuquerque, NM 87110
p_505.243.9287

M/E/P/FP
Bridgers and Paxton
4600-C Montgomery Blvd. NE
Albuquerque, New Mexico 87109
p_505.883.4111 f_505.888.1436

INTERIORS
Studio M
6501 Americas Pkwy NE Ste. 301
Albuquerque, NM 87110
p_505.243.9287

SITE
Groundwork Studio
6501 Americas Pkwy NE Ste. 350
Albuquerque, NM 87110
p_505.212.9126

FOOD SERVICE
Standard Kitchen Supply
2405 Candelaria Rd. NE,
Albuquerque, NM 87107
p_505.341.1054

ENVELOPE AND ROOF CONSULTANT
Armstrong Group INC.
2415 Princeton Ave, NE Suite E
Albuquerque, NM 87107
p_505.235.7596

AV & TECHNOLOGY
Network Cabling, INC
3100 La Plata HWY.
Farmington, NM 87401
p_505.598.5054

ARCHITECT

Dzilth-Na-O-Dith-Hle - New Dormitory Building

CONSTRUCTION DOCUMENTS

35 Road 7585, Bloomfield, NM 87413

DECEMBER 4TH, 2020

MARK	DATE	DESCRIPTION
1	12/12/12	THIS IS A TEST

ISSUE:

DATE:

PROJECT NO: 751

CAD DWG FILE:

DRAWN BY: Author


CHECKED BY: Checker

SHEET TITLE


ROOF PLAN

A-131


Dzilth-Na-O-Dith-Hle Community School




D1 COPING CAP BUTT JOINT
1 1/2" = 1'-0"




D2 COPING CAP CORNER JOINT




D3 PENETRATION SPACING
1" = 1'-0"




B1 SCUPPER DETAIL
1" = 1'-0"




B2 COPING CAP WALL ABUTEMENT
1 1/2" = 1'-0"




STEP 2



A1 PARAPET DETAIL
1" = 1'-0"



A2 PARAPET CAP DETAIL
3" = 1'-0"



A3 PRIMARY ROOF DRAIN
1 1/2" = 1'-0"



**Dzilh-Na-O-Dith-Hle -
New Dormitory
Building**

CONSTRUCTION DOCUMENTS

35 Road 7585, Bloomfield, NM
87413


DECEMBER 4TH, 2020

MARK	DATE	DESCRIPTION
1	12/12/12	THIS IS A TEST
ISSUE:		
DATE:		
PROJECT NO:		751
CAD DWG FILE:		
DRAWN BY:		Author
CHECKED BY:		Checker


SHEET TITLE

ROOF DETAILS


A-142




C1 LEADERHEAD AND DOWNSPOUT
1" = 1'-0"




C3 RIDGE DETIAL - METAL ROOF




C5 PIPE FLASHING




B1 PENTHOUSE/ROOF DETAIL
1" = 1'-0"




B2 FASCIA DETAIL
12" = 1'-0"




B3 HOGON ROOF DETAIL
1 1/2" = 1'-0"




B4 NTS **GUTTER DETIAL - METAL ROOF**




A1 HIGH WALL FLASHING DETAIL @ STUCCO




A2 ROOF HATCH & LADDER







A4 CURB DETAIL
NTS



A5 DIVIDING WALL DETAIL



EXTERIOR FINISH LEGEND	
	3 COAT STUCCO SYSTEM WITH ANTI-GRAFFITI COATING. FIELD COLOR, COLOR TO BE SELECTED BY ARCHITECT.
	3 COAT STUCCO SYSTEM WITH ANTI-GRAFFITI COATING. ACCENT COLOR. COLOR TO BE SELECTED BY ARCHITECT.
	3 1/2" HIGH MASONRY VENEER WITH ANTI-GRAFFITI COATING. FIELD COLOR, COLOR TO BE SELECTED BY ARCHITECT.



f b t | architects

MAL: 6501 Americas Pkwy NE, Ste. 300 Albuquerque, NM 87110	PHO: 505.883.5200 FAX: 505.884.5390 WEB: www.fbtarch.com
---	---

CONSULTANT

CIVIL
Bohannon Huston
7500 Jefferson St NE,
Albuquerque, NM 87109
p_505.823.100

STRUCTURAL
Walla Engineering Ltd
6501 Americas Pkwy NE Ste. 302
Albuquerque, NM 87110
p_505.243.9287

M/E/P/FP
Bridgers and Paxton
4650-C Monticorty Blvd. NE
Albuquerque, New Mexico 87109
p_505.883.4111 f_505.888.1436

INTERIORS
Studio M
6501 Americas Pkwy NE Ste. 301
Albuquerque, NM 87110
p_505.243.9287

SITE
Groundwork Studio
6501 Americas Pkwy NE Ste. 350
Albuquerque, NM 87110
p_505.212.9126




**Dzilh-Na-O-Dith-Hle -
New Dormitory
Building**

**CONSTRUCTION
DOCUMENTS**

35 Road 7585, Bloomfield, NM
87413

DECEMBER 4TH, 2020



SHEET TITLE
BUILDING ELEVATIONS
A-201



301 ALUMINUM STOREFRONT SYSTEM. SEE WINDOW FRAME ELEVATIONS.
316 CONCRETE SLAB ON GRADE OVER VAPOR BARRIER AND 4" AGGREGATE
BASE COURSE ON PREPARED SUBGRADE. SEE STRUCTURAL AND
GEOTECHNICAL REPORT.
321 FINISH CEILING. SEE RCP.
325 EXPOSED MECHANICAL EQUIPMENT OR DUCTWORK. PAINT ALL EXPOSED
ELEMENTS. COLOR TO BE SELECTED BY ARCHITECT. DO NOT PAINT
PREFINISHED ELEMENTS.
326 MEMBRANE ROOFING SYSTEM. SEE ROOF PLAN AND DETAILS.
381 STANDING SEAM METAL ROOFING SYSTEM. SEE ROOF PLAN AND DETAILS.

AV & TECHNOLOGY
Network Cabling, INC
 3100 La Plata HWY.
 Farmington, NM 87401
 p_505.598.5054





301 ALUMINUM STOREFRONT SYSTEM. SEE WINDOW FRAME ELEVATIONS.
302 CONCRETE SLAB ON GRADE OVER VAPOR BARRIER AND 4" AGGREGATE
303 BASE COURSE ON PREPARED SUBGRADE. SEE STRUCTURAL AND
304 MECHANICAL REPORT.
305 CONCRETE SLAB OVER METAL DECK. SEE STRUCTURAL
306 CONCRETE STEM WALL AND FOOTING. SEE STRUCTURAL
307 DOOR AND FRAME. SEE FLOOR PLAN AND DOOR SCHEDULE.
308 FINISH CEILING. SEE RCP.
309 MEMBER ROOFING SYSTEM. SEE ROOF PLAN AND DETAILS.
310 PREFINISHED METAL COPING CAP. SEE ROOF DETAILS A-141A-142.
311 ROOF ACCESS LADDER AND HATCH. SEE ROOF DETAILS.
312 STEEL STRUCTURE. SEE STRUCTURAL. PAINT ALL EXPOSED SECTIONS,
313 INCLUDING STRUCTURAL DECK, COLOR TO BE SELECTED BY
314 ARCHITECT.
315 STEEL STUD PARTITION. SEE PARTITION SCHEDULE.
316 3 COAT STUCCO SYSTEM.
317 STANDING SEAM METAL ROOFING SYSTEM. SEE ROOF PLAN AND
318 DETAILS.

STATE OF NEW MEXICO
SANJAY I.
ENGINEER
No. 3088
REGISTERED ARCHITECT
12/20
ARCHITECT

A-302

- A. CIVIL ELEVATIONS OF 6754.50 (SHOW IN SCHOOL BUILDING & SITE PACKAGE) = 100' - 0" ON ARCHITECTURAL SECTIONS. BEARING HEIGHTS ARE SHOWN FOR REFERENCE TO 100'-0" AND NOT INDIVIDUAL HEIGHTS ABOVE FINISHED FLOOR COORDINATED WITH FLOOR PLAN DRAWINGS AND STRUCTURAL.
- B. ANY EXPOSED PENETRATIONS, FLASHINGS, VENTS, MECHANICAL EQUIPMENT, UTILITY LINES, ETC. SHALL BE INTEGRATED TO GO-OR-AS SELECTED BY THE ARCHITECT. DO NOT PAINT PRE FINISHED ITEMS.
- C. FURNISH AND INSTALL SEALANT AT INTERSECTION OF ALL DISSIMILAR MATERIALS.
- D. MASONRY JOINTS IN MASONRY WALL SHALL BE COORDINATED WITH STRUCTURAL REQUIREMENTS.
- E. REFER TO CIVIL DRAWINGS IN SCHOOL BUILDING & SITE PACKAGE FOR ALL GRADING INFORMATION AROUND THE BUILDING.

301 ALUMINUM STOREFRONT SYSTEM. SEE WINDOW FRAME ELEVATIONS.
302 1-1/2" CONTINUOUS EXTERIOR INSULATION, THERMAL, WATER AND AIR
303 BARRIER SYSTEM.
304 10" EXPANSION JOINT MATERIAL WITH JOINT SEALANT.
305 5/8" TYPE "X" GYPSUM BOARD, TAPE, TEXTURE & PAINT.
306 1/2" METAL FRAMING, FOR EXTERIOR WALLS SEE STRUCTURAL
307 6-1/2" PERMITTER INSULATION.
308 CONCRETE SIDEWALK OR MOVISITP. SEE SITE PLAN.
309 CONCRETE SLAB ON GRADE OVER VAPOR BARRIER AND 4" AGGREGATE
310 BASE COURSE ON PREPARED SUBGRADE. SEE STRUCTURAL AND
311 GEOTECHNICAL REPORT.
312 CONCRETE STEM WALL. SEE DETAIL.
313 DOOR AND FRAME. SEE FLOOR PLAN AND DOOR SCHEDULE.
314 FINISH CEILING. SEE RCP.
315 MEMBRANE ROOFING SYSTEM. SEE ROOF PLAN AND DETAILS.
316 R-13 BATT INSULATION. TYPICAL AT ALL EXTERIOR STUD WALLS UNLESS
317 NOTED OTHERWISE.
318 1/2" MASONRY VENER WITH "A" AIR SPACE. SEE ELEVATIONS AND
319 STRUCTURAL FOR ADDITIONAL INFORMATION.
320 VENEER BASE. SEE DETAIL.
321 6" STEEL STUDS AT 16" OC FOR BUMP OUT. SEE PLAN DETAILS AND
322 ELEVATIONS FOR EXTENTS.
323 STEEL STRUCTURE. SEE STRUCTURAL. PAINT ALL EXPOSED SECTIONS,
324 INCLUDING STRUCTURAL STEEL, COLOR TO BE SPECIFIED BY ARCHITECT.
325 4" STEEL STUDS AT 16" OC.
326 3 COAT STUCCO SYSTEM.
327 MASONRY VENER BY CAP. SEE WINDOW AND DOOR DETAILS.
328 ALUMINUM SUNSHADE BY WINDOW MANUFACTURER. SEE DETAIL.

5"

2X TREATED WOOD BLOCKING

STUCCO STOP AND SEALANT AT EACH BRACKET

25" AIRFOIL OUTRIGGER

SQUARE FACIA

AIRFOIL BLADE (TYPICAL OF 4)

DIALECTIC BOLT KIT WITH NYLON BUSHINGS

3X5X1/4" STEEL ANGLE WELDED OR BOLTED TO STEEL STUDS. PRIME AND PAINT TO MATCH AIRFOIL OUTRIGGER

16"

STOREFRONT HEAD DETAIL. SEE WINDOW AND DOOR DETAILS.

[illegible]

T.O.W.
115' - 0"

A1
A-141
SIM.

TYP.

1'-0"

326

344

321

311

307

357

302

331

334

D3
A-311

316

313

FINISH FLOOR
100' - 0"

Architectural section drawing of a building facade, showing a 1-3 SLEEPING ROOM and a FINISH FLOOR. The drawing includes various callouts for structural elements and dimensions.

1-3 SLEEPING ROOM
113.2

FINISH FLOOR
100' - 0"

Dimensions and Callouts:

- GRID
- 1178" TYP.
- A1 A-141
- B3 A-611
- A3 A-611
- 326
- 344
- 302
- 357
- 366
- 321
- 331
- 311
- 307
- 301
- 359
- 332
- 316
- 303
- 315
- 313
- 333
- 307
- 311
- 331

Other Labels:

- T.O.W. 115' - 0"
- 5' - 0"

CONSTRUCTION DOCUMENTS


35 Road 7585, Bloomfield, NM
87413

DECEMBER 4TH, 2020

MARK	DATE	DESCRIPTION
	12/12/12	THIS IS A TEST
ISSUE:		
DATE:		
PROJECT NO:		751
CAD DWG FILE:		
DRAWN BY:		Author
CHECKED BY:		Checker

SHEET TITLE

WALL SECTIONS



fbt | architects

MAIL: 6501 Americas Pkwy NE, Ste. 300
Albuquerque, NM 87110

PHO: 505.883.6200
FAX: 505.884.6290
WEB: www.fbtarch.com

CONSULTANT

CIVIL
Bohannon Huston
7500 Jefferson St NE,
Albuquerque, NM 87109
p_505.823.100

STRUCTURAL
Walla Engineering Ltd
6501 Americas Pkwy NE Ste. 302
Albuquerque, NM 87110
p_505.243.9287

M/E/P/FP
Bridgers and Paxton
4600-C Montgomery Blvd. NE
Albuquerque, New Mexico 87109
p_505.883.4111 f_505.888.1436

INTERIORS
Studio M
6501 Americas Pkwy NE Ste. 301
Albuquerque, NM 87110
p_505.243.9287

SITE
Groundwork Studio
6501 Americas Pkwy NE Ste. 350
Albuquerque, NM 87110
p_505.212.9126

FOOD SERVICE
Standard Kitchen Supply
2405 Candelaria Rd. NE,
Albuquerque, NM 87107
p_505.341.1054

ENVELOPE AND ROOF CONSULTANT
Armstrong Group INC.
2415 Princeton Ave, NE Suite E
Albuquerque, NM 87107
p_505.235.7596

AV & TECHNOLOGY
Network Cabling, INC
3100 La Plata HWY.
Farmington, NM 87401
p_505.598.5054

STATE OF NEW MEXICO

SAMAY L. ENGINEER

No. 3088

12/1/20

REGISTERED ARCHITECT

Dzilth-Na-O-Dith-Hle - New Dormitory Building

CONSTRUCTION DOCUMENTS

35 Road 7585, Bloomfield, NM 87413

DECEMBER 4TH, 2020

MARK	DATE	DESCRIPTION
1	12/12/12	THIS IS A TEST

ISSUE:

DATE:

PROJECT NO: 751

CAD DWG FILE:

DRAWN BY: Author


CHECKED BY: Checker

SHEET TITLE


WALL SECTIONS

A-312


Dzilth-Na-O-Dith-Hle Community School




E1 HONORS RR
1/4" = 1'-0"
ADULT RR (AGE 12+) ROOMS 208A & 232A




E2 HONORS RR LAVATORY
1/4" = 1'-0"




E3 HONORS RR SIDE
1/4" = 1'-0"




E4 HONORS RR FIXTURE
1/4" = 1'-0"




E5 HONORS RR END
1/4" = 1'-0"




C1 BOYS RR - ISOLATION RR
1/4" = 1'-0"
CHILDREN RR (AGES 9-12) ROOMS 221 & 218




D2 ISO RR - FIXTURE
1/4" = 1'-0"




D3 ISO RR - SIDE
1/4" = 1'-0"




D4 ISO RR - ENTRANCE
1/4" = 1'-0"




D5 ISO RR - END
1/4" = 1'-0"




C2 BOYS RR - FIXTURE
1/4" = 1'-0"




C3 BOYS RR - SIDE
1/4" = 1'-0"




C4 BOYS RR - SHOWERS
1/4" = 1'-0"




A1 GIRLS RR - ISOLATION RR
1/4" = 1'-0"
CHILDREN RR (AGES 9-12) ROOMS 204 & 207A




B2 ISOLATION - FIXTURE
1/4" = 1'-0"




B3 ISO - END WALL
1/4" = 1'-0"




B4 ISO - ENTRANCE
1/4" = 1'-0"




B5 ISOLATION - SIDE
1/4" = 1'-0"




A2 GIRLS RR - FIXTURE
1/4" = 1'-0"



A3 GIRLS RR - SHOWERS
1/4" = 1'-0"



A4 GIRLS RR - SIDE
1/4" = 1'-0"



A6 STORAGE ROOM 112
1/4" = 1'-0"

GENERAL NOTES

- CONTRACTOR SHALL PERFORM DAILY CLEANUP WHEN FINISH TRADE WORK IS BEING PERFORMED.
- PROVIDE WOOD BLOCKING IN ALL WALLS FOR SUPPORT OF PARTITIONS, SIGNAGE, ACCESSORIES, AND OTHER WALL SUPPORTED ITEMS AS REQUIRED.
- PROVIDE SEALANT AT INTERSECTIONS OF ALL DISSIMILAR MATERIALS.
- COORDINATE ALL PLUMBING FIXTURES WITH THE PLUMBING DRAWINGS. IN CASE OF ANY DISCREPANCY, NOTIFY ARCHITECT AND ENGINEER PRIOR TO ROUGH-IN OF INSTALLATION.
- PROVIDE WATER RESISTANT GYPSUM BOARD AT ALL WET LOCATIONS.
- ALL DIMENSIONS ARE TO FACE OF STUD UNLESS NOTED OTHERWISE.
- ALL FIXTURES AND ACCESSORIES SHALL COMPLY WITH ADA, ANSI, AND LOCAL AND STATE BUILDING CODE REQUIREMENTS. ALL HEIGHTS, DIMENSIONS AND CLEARANCES FOR PLUMBING FIXTURES, CASEWORK, COUNTERTOPS, ACCESSORIES, SIGNAGE, ACCESSIBLE ROUTES, ECT. SHALL BE STRICTLY HELD TO ADA, ANSI, AND LOCAL AND STATE REQUIREMENTS. IN THE EVENT OF CONFLICTING REQUIREMENTS, THE MOST RESTRICTIVE SHALL APPLY. REFER TO ACCESSIBILITY GUIDELINES SHEET.

TOILET ACCESSORY LEGEND

MARK	ACCESSORIES
1	30" X 36" (UNLESS OTHERWISE NOTED) MIRROR.
2	LIQUID SOAP DISPENSER, MOUNT 5" ABOVE SINK. CONTRACTOR FURNISHED, CONTRACTOR INSTALLED.
3	TOILET PAPER DISPENSER, CONTRACTOR FURNISHED, CONTRACTOR INSTALLED.
4	MANUAL PAPER TOWEL DISPENSER, CONTRACTOR FURNISHED, CONTRACTOR INSTALLED.
5	GRAB BAR 1-1/2" DIA. (SEE ACCESSIBILITY GUIDELINES FOR MOUNTING HEIGHT). INSTALL DUAL HEIGHT GRAB BARS IN AGES 9-12+ ACCESSIBLE RESTROOMS.
6	SANITARY NAPKIN DISPOSAL. MOUNT 28" A.F.F.
7	FOLDING SHOWER SEAT. MOUNT TOP OF SEAT AT 15" HIGH IN CHILD SHOWER AND 17" IN ADULT SHOWER.
8	SHOWER CURTAIN ROD AND SHOWER CURTAIN.
9	ADA SHOWER GRAB BAR 1-1/2" DIA. (SEE ACCESSIBILITY GUIDELINES FOR MOUNTING HEIGHT).
11	24" TOWEL SHELF AND BAR. MOUNT TOP OF SHELF AT 44" A.F.F. UNLESS NOTED OTHERWISE.

PLASTIC LAMINATE LEGEND

PL1	COLOR: TBD	MAUFACTURER: TBD
PL2	COLOR: TBD	MAUFACTURER: TBD
PL3	COLOR: TBD	MAUFACTURER: TBD
PL4	COLOR: TBD	MAUFACTURER: TBD
SS1	COLOR: TBD	MAUFACTURER: TBD

KEYED NOTES

- 030 ROOF ACCESS LADDER AND HATCH. SEE ROOF DETAILS A-141.
- 064 WALL MOUNTED SINK. SEE PLUMBING.
- 065 OWNER FURNISHED REFRIGERATOR. SEE PLUMBING AND ELECTRICAL FOR ROUGH IN REQUIREMENTS.
- 416 DOOR AND FRAME. SEE FLOOR PLAN AND DOOR SCHEDULE.
- 421 EXPOSED STEEL STRUCTURE. PAINT. COLOR TO BE SELECTED BY ARCHITECT.
- 423 FINISH CEILING. SEE RCP.
- 428 GYPSUM BOARD FINISH. TAPE, TEXTURE, AND PAINT.
- 429 5'-0" ADA WHEEL CHAIR TURNING SPACE.
- 432 MOP SINK AND MOP RACK. SEE PLUMBING.
- 436 PLASTIC LAMINATE CASEWORK.
- 449 VINYL WALL BASE. SEE FINISH SCHEDULE ID-100.
- 451 TRANSITION STRIP. SEE ID FINISH LEGEND, ID-100.
- 460 WALL MOUNTED LAVATORY.
- 476 ELECTRIC WATER COOLER. SEE PLUMBING.
- 478 SHOWER FIXTURE. SEE PLUMBING.
- 479 ACCESSIBLE SINK IN SOLID SURFACE COUNTERTOP. SEE PLUMBING.
- 480 WALL TILE. DASHED LINE ON DOOR PLAN INDICATES EXTENT OF WALL TILE. SEE ELEVATIONS FOR TILE HEIGHT AND ID SHEETS FOR PATTERN.
- 481 WALL MOUNTED LIGHT FIXTURE. SEE ELECTRICAL.
- 483 TOILET PARTITION.
- 484 WATER CLOSET. SEE PLUMBING.
- 486 WALL MOUNTED URINAL. SEE PLUMBING.
- 489 2" LONG TRENCH DRAIN. CENTER IN SHOWER OPENING FOR BARRIER FREE ACCESS.
- 490 INSTALL SHOWER FLOOR TILE OVER 2" MORTAR BED IN RECESSED SLAB. SLOPE SHOWER FLOOR TO DRAIN.

CONSULTANT

CIVIL
Bohannon Huston
7500 Jefferson St. NE,
Albuquerque, NM 87109
p_505.823.100

STRUCTURAL
Walla Engineering Ltd
6501 Americas Pkwy NE Ste. 302
Albuquerque, NM 87110
p_505.243.9287

M/E/P/FP
Bridgers and Paxton
4600-C Montgomery Blvd. NE
Albuquerque, New Mexico 87109
p_505.883.4111 f_505.888.1436

INTERIORS
Studio M
6501 Americas Pkwy NE Ste. 301
Albuquerque, NM 87110
p_505.243.9287

SITE
Groundwork Studio
6501 Americas Pkwy NE Ste. 350
Albuquerque, NM 87110
p_505.212.9126

FOOD SERVICE
Standard Kitchen Supply
2405 Candelaria Rd. NE,
Albuquerque, NM 87107
p_505.341.1054

ENVELOPE AND ROOF CONSULTANT
Armstrong Group INC.
2415 Princeton Ave, NE Suite E
Albuquerque, NM 87107
p_505.235.7596

AV & TECHNOLOGY
Network Cabling, INC
3100 La Plata HWY.
Farmington, NM 87401
p_505.598.5054



Dzilth-Na-O-Dith-Hle - New Dormitory Building

CONSTRUCTION DOCUMENTS

35 Road 7585, Bloomfield, NM 87413

DECEMBER 4TH, 2020


MARK	DATE	DESCRIPTION
1	12/12/12	THIS IS A TEST

ISSUE:	
DATE:	
PROJECT NO:	751
CAD DWG FILE:	
DRAWN BY:	Author
CHECKED BY:	Checker


SHEET TITLE
ENLARGED PLANS AND ELEVATIONS

Dzilth-Na-O-Dith-Hle - New Dormitory Building


12/6/2020 8:43:24 PM




E1 KITCHENETTE PLAN
1/4" = 1'-0"






E2 KITCHEN - STOVE
1/4" = 1'-0"



E3 KITCHEN - BAR
1/4" = 1'-0"







A	WALL TYPE AS SHOWN IN DETAIL ABOVE	B	WALL TYPE AS SHOWN IN DETAIL ABOVE	C	WALL TYPE AS SHOWN IN DETAIL ABOVE
A1	AS SHOWN IN DETAIL ABOVE WITH THE FOLLOWING EXCEPTIONS: • EXTEND ASSEMBLY TO 6" ABOVE FINISH CEILING	B1	AS SHOWN IN DETAIL ABOVE WITH THE FOLLOWING EXCEPTIONS: • EXTEND ASSEMBLY TO 6" ABOVE FINISH CEILING	C1	AS SHOWN IN DETAIL ABOVE WITH THE FOLLOWING EXCEPTIONS: • EXTEND ASSEMBLY TO 6" ABOVE FINISH CEILING
A2	AS SHOWN IN DETAIL ABOVE WITH THE FOLLOWING EXCEPTIONS: • 30 MINUTE FIRE BARRIER WALL (UL U407) • ACOUSTICAL PARTITION - STC RATING 45 • PROTECT ALL OPENINGS, SEAL ALL PENETRATIONS & JOINTS TO MAINTAIN RATING	B2	AS SHOWN IN DETAIL ABOVE WITH THE FOLLOWING EXCEPTIONS: • 30 MINUTE FIRE BARRIER WALL (UL U407) • ACOUSTICAL PARTITION - STC RATING 45 • PROTECT ALL OPENINGS, SEAL ALL PENETRATIONS & JOINTS TO MAINTAIN RATING	C2	AS SHOWN IN DETAIL ABOVE WITH THE FOLLOWING EXCEPTIONS: • 30 MINUTE FIRE BARRIER WALL (UL U407) • ACOUSTICAL PARTITION - STC RATING 45 • PROTECT ALL OPENINGS, SEAL ALL PENETRATIONS & JOINTS TO MAINTAIN RATING
A2A	AS SHOWN IN DETAIL ABOVE WITH THE FOLLOWING EXCEPTIONS: • 30 MINUTE FIRE BARRIER WALL (UL U407) • ACOUSTICAL PARTITION - STC RATING 45 • PROTECT ALL OPENINGS, SEAL ALL PENETRATIONS & JOINTS TO MAINTAIN RATING • 5/8" TYPE "X" CEMENTITIOUS BACKER BOARD AT WALL TILE. SEE INTERIOR ELEVATIONS AND FINISH SCHEDULE FOR HEIGHT AND EXTENT.	B2A	AS SHOWN IN DETAIL ABOVE WITH THE FOLLOWING EXCEPTIONS: • 30 MINUTE FIRE BARRIER WALL (UL U407) • ACOUSTICAL PARTITION - STC RATING 45 • PROTECT ALL OPENINGS, SEAL ALL PENETRATIONS & JOINTS TO MAINTAIN RATING • 5/8" TYPE "X" CEMENTITIOUS BACKER BOARD AT WALL TILE. SEE INTERIOR ELEVATIONS AND FINISH SCHEDULE FOR HEIGHT AND EXTENT.	C2A	AS SHOWN IN DETAIL ABOVE WITH THE FOLLOWING EXCEPTIONS: • 30 MINUTE FIRE BARRIER WALL (UL U407) • ACOUSTICAL PARTITION - STC RATING 45 • PROTECT ALL OPENINGS, SEAL ALL PENETRATIONS & JOINTS TO MAINTAIN RATING • 5/8" TYPE "X" CEMENTITIOUS BACKER BOARD AT WALL TILE. SEE INTERIOR ELEVATIONS AND FINISH SCHEDULE FOR HEIGHT AND EXTENT.
A3	AS SHOWN IN DETAIL ABOVE WITH THE FOLLOWING EXCEPTIONS: • 5/8" TYPE "X" CEMENTITIOUS BACKER BOARD AT WALL TILE. SEE INTERIOR ELEVATIONS AND FINISH SCHEDULE FOR HEIGHT AND EXTENT • 5/8" TYPE "X" WATER RESISTANT GYPSUM BOARD ABOVE WALL TILE. TAPE, TEXTURE, PAINT.	B3	AS SHOWN IN DETAIL ABOVE WITH THE FOLLOWING EXCEPTIONS: • 5/8" TYPE "X" CEMENTITIOUS BACKER BOARD AT WALL TILE. SEE INTERIOR ELEVATIONS AND FINISH SCHEDULE FOR HEIGHT AND EXTENT • 5/8" TYPE "X" WATER RESISTANT GYPSUM BOARD ABOVE WALL TILE. TAPE, TEXTURE, PAINT.	C3	AS SHOWN IN DETAIL ABOVE WITH THE FOLLOWING EXCEPTIONS: • 5/8" TYPE "X" CEMENTITIOUS BACKER BOARD AT WALL TILE. SEE INTERIOR ELEVATIONS AND FINISH SCHEDULE FOR HEIGHT AND EXTENT • 5/8" TYPE "X" WATER RESISTANT GYPSUM BOARD ABOVE WALL TILE. TAPE, TEXTURE, PAINT.
A4	AS SHOWN IN DETAIL ABOVE WITH THE FOLLOWING EXCEPTIONS: • 5/8" TYPE "X" GYPSUM BOARD ON EXPOSED SIDE TAPE, TEXTURE, PAINT. • EXTEND STUDS & GYPSUM BOARD TO 6" ABOVE FINISH CEILING.	B4	AS SHOWN IN DETAIL ABOVE WITH THE FOLLOWING EXCEPTIONS: • 5/8" TYPE "X" GYPSUM BOARD ON EXPOSED SIDE TAPE, TEXTURE, PAINT. • EXTEND STUDS & GYPSUM BOARD TO 6" ABOVE FINISH CEILING.	C4	AS SHOWN IN DETAIL ABOVE WITH THE FOLLOWING EXCEPTIONS: • 5/8" TYPE "X" GYPSUM BOARD ON EXPOSED SIDE TAPE, TEXTURE, PAINT. • EXTEND STUDS & GYPSUM BOARD TO 6" ABOVE FINISH CEILING.
A5	AS SHOWN IN DETAIL ABOVE WITH THE FOLLOWING EXCEPTIONS: (SLEEPING ROOM TO ADJACENT OCCUPIED SPACE) • 1 HOUR FIRE BARRIER WALL (UL U419) • ACOUSTICAL PARTITION - STC RATING 45 • PROTECT ALL OPENINGS, SEAL ALL PENETRATIONS & JOINTS TO MAINTAIN RATING	B5	AS SHOWN IN DETAIL ABOVE WITH THE FOLLOWING EXCEPTIONS: (SLEEPING ROOM TO ADJACENT OCCUPIED SPACE) • 1 HOUR FIRE BARRIER WALL (UL U419) • ACOUSTICAL PARTITION - STC RATING 45 • PROTECT ALL OPENINGS, SEAL ALL PENETRATIONS & JOINTS TO MAINTAIN RATING	C5	AS SHOWN IN DETAIL ABOVE WITH THE FOLLOWING EXCEPTIONS: (SLEEPING ROOM TO ADJACENT OCCUPIED SPACE) • 1 HOUR FIRE BARRIER WALL (UL U419) • ACOUSTICAL PARTITION - STC RATING 45 • PROTECT ALL OPENINGS, SEAL ALL PENETRATIONS & JOINTS TO MAINTAIN RATING
A6	AS SHOWN IN DETAIL ABOVE WITH THE FOLLOWING EXCEPTIONS: (TYPICAL SLEEPING ROOM TO ADJACENT RESTROOM) • 1 HOUR FIRE BARRIER WALL (UL U419) • 5/8" TYPE "X" CEMENTITIOUS BACKER BOARD AT WALL TILE. SEE INTERIOR ELEVATIONS AND FINISH SCHEDULE FOR HEIGHT AND EXTENT • 5/8" TYPE "X" WATER RESISTANT GYPSUM BOARD ABOVE WALL TILE. TAPE, TEXTURE AND PAINT. • PROTECT ALL OPENINGS, SEAL ALL PENETRATIONS & JOINTS TO MAINTAIN RATING	B6	AS SHOWN IN DETAIL ABOVE WITH THE FOLLOWING EXCEPTIONS: (TYPICAL SLEEPING ROOM TO ADJACENT RESTROOM) • 1 HOUR FIRE BARRIER WALL (UL U419) • 5/8" TYPE "X" CEMENTITIOUS BACKER BOARD AT WALL TILE. SEE INTERIOR ELEVATIONS AND FINISH SCHEDULE FOR HEIGHT AND EXTENT • 5/8" TYPE "X" WATER RESISTANT GYPSUM BOARD ABOVE WALL TILE. TAPE, TEXTURE AND PAINT. • PROTECT ALL OPENINGS, SEAL ALL PENETRATIONS & JOINTS TO MAINTAIN RATING	C6	AS SHOWN IN DETAIL ABOVE WITH THE FOLLOWING EXCEPTIONS: (TYPICAL SLEEPING ROOM TO ADJACENT RESTROOM) • 1 HOUR FIRE BARRIER WALL (UL U419) • 5/8" TYPE "X" CEMENTITIOUS BACKER BOARD AT WALL TILE. SEE INTERIOR ELEVATIONS AND FINISH SCHEDULE FOR HEIGHT AND EXTENT • 5/8" TYPE "X" WATER RESISTANT GYPSUM BOARD ABOVE WALL TILE. TAPE, TEXTURE AND PAINT. • PROTECT ALL OPENINGS, SEAL ALL PENETRATIONS & JOINTS TO MAINTAIN RATING

NOTE: NOT ALL PARTITION TYPES ARE USED IN THIS PROJECT

ACOUSTICAL PARTITION NOTES

- A. BACK TO BACK OUTLETS WILL NOT BE ALLOWED.
- B. FURNISH AND INSTALL ACOUSTIC SEALANT AT FLOOR TO PARTITION CONNECTIONS.
- C. FURNISH AND INSTALL ACOUSTIC SEALANT AT ALL PENETRATIONS FOR UTILITIES, HVAC, SPRINKLERS, CONDUITS, ETC. AS THEY PENETRATE STC RATED PARTITIONS. SUPPORT PENETRATIONS ON EACH SIDE OF PARTITION TO AVOID MECHANICAL CONTACT WITH STUDS OR GYPSUM BOARD.
- D. SPACES BETWEEN ITEMS PENETRATING STC RATED PARTITIONS AND THE PARTITION ITSELF SHALL BE SEALED USING ACOUSTIC SEALANT AND BACKER MATERIAL (GLASS FIBER INSULATION OR ROCK WOOL).

GENERAL NOTES

- A. FURNISH AND INSTALL SEALANT AT INTERSECTION OF ALL DISJUNCTIONAL MATERIALS.
- B. FURNISH AND INSTALL WOOD BLOCKING IN ALL WALLS FOR SUPPORT OF TOILET PARTITIONS, SINKS, ACCESSORIES OR OTHER WALL SUPPORTED ITEMS AS REQUIRED.
- C. FURNISH AND INSTALL WATER RESISTANT GYPSUM BOARD IN KITCHENS, RESTROOMS, CUSTODIAL ROOMS AND ALL WET AREAS.
- D. SEE FLOOR PLANS FOR EXTENT OF RAISED ASSEMBLIES.
- E. SEE BUILDING AND WALL SECTIONS FOR ADDITIONAL INFORMATION OF INTERIOR WALLS THAT EXTEND ABOVE THE ROOF PLANE AND EXTERIOR WALLS. COORDINATE WITH STRUCTURAL.
- F. SEE REFLECTED CEILING PLAN FOR ALL CEILING INFORMATION.
- G. AT ALL LOCATIONS OF EXPOSED CEILING STRUCTURE ALL CMU WALLS SHALL BE PAINTED TO ROOF DECK AND ALL STEEL STUD WALLS SHALL BE TAPED, TEXTURED AND PAINTED TO UNDERSIDE OF ROOF DECK. CONTROL ALL PAINT AND TEXTURE OVERSPRAY AT THESE LOCATIONS. OVERSPRAY ON EXPOSED ROOF DECK WILL NOT BE ACCEPTED.
- H. SEE STRUCTURAL DRAWINGS FOR LOCATIONS AND DETAIL OF LOAD BEARING STEEL STUDS OR CMU WALLS.
- I. PARTITION GAUGE SHALL COMPLY WITH DEFLECTION AND LOADING CRITERIA INDICATED IN THE SPECIFICATIONS.
- J. FURNISH AND INSTALL WALL TILE ON 58" TYPE X CEMENTATION BACKBOARD TO 48" HEIGHT ON INTERIOR ELEVATIONS IN ALL RESTROOMS AT ALL DRINKING FOUNTAINS.
- K. SEE FLOOR PLANS AND ID SHEETS FOR INTERIOR FINISH INFORMATION.
- L. NO RIGID INSULATION SHALL BE EXPOSED INSIDE THE BUILDING ENVELOPE. COVER ALL INSULATION WITH GYPSUM BOARD, TAPE BED AND SEAL ALL GAPS AT DECK WITH FIRE/SMOKE SEALANT.
- M. FURNISH AND INSTALL SLIP TYPE HEAD JOINTS AT ALL STEEL STUD PARTITIONS THAT EXTEND TO DECK.
- N. FURNISH AND INSTALL FIRE STOP TRACKS AT ALL FIRE RATED STEEL STUD PARTITIONS.
- O. PARTITIONS THAT HAVE MULTIPLE LAYERS OF GYP BOARD SHALL BE CONTINUOUS WALL SURFACE. STAGGERED OR STEPPED WALL SURFACES WILL NOT BE ACCEPTED.



CONSULTANT

CIVIL
Bohannon Huston
7500 Jefferson St NE,
Albuquerque, NM 87109
p_505.823.100

STRUCTURAL
Walla Engineering Ltd
6501 Americas Pkwy NE Ste. 302
Albuquerque, NM 87110
p_505.243.9287

M/E/P/FP
Bridgers and Paxton
4600-C Montgomery Blvd. NE
Albuquerque, New Mexico 87109
p_505.883.4111 f_505.888.1436

INTERIORS
Studio M
 6501 Americas Pkwy NE Ste. 301
 Albuquerque, NM 87110
 p 505.243.9287

SITE
Groundwork Studio
6501 Americas Pkwy NE Ste. 350
Albuquerque, NM 87110
p_505.212.9126

FOOD SERVICE
Standard Kitchen Supply
 2405 Candelaria Rd. NE,
 Albuquerque, NM 87107
 p_505.341.1054

ENVELOPE AND ROOF CONSULTANT
Armstrong Group INC.
 2415 Princeton Ave, NE Suite E
 Albuquerque, NM 87107
 p_505.235.7596

AV & TECHNOLOGY
Network Cabling, INC
 3100 La Plata HWY.
 Farmington, NM 87401
 p_505.598.5054



Dzilh-Na-O-Dith-Hle - New Dormitory Building

CONSTRUCTION DOCUMENTS

35 Road 7585, Bloomfield, NM
87413

DECEMBER 4TH, 2020

MARK	DATE	DESCRIPTION
ISSUE:		
DATE:		
PROJECT NO:		751
CAD DWG FILE:		
DRAWN BY:		Author
CHECKED BY:		Checker

SHEET TITLE
PARTITION SCHEDULE

A-501

Door & Frame Schedule													
DOOR				DOOR TYPE	FACING/FINISH	FRAME TYPE	GLAZING	FIRE RATING	DETAIL REFERENCE HEAD	DETAIL REFERENCE JAMB	DETAIL REFERENCE SILL	SIGNAGE	REMARKS
DOOR NUMBER	WIDTH	SIZE HEIGHT	HEIGHT										
001	6'-4"	6'-10"	1	PAIR	ALUM	F	1" ISG	-	C3/A-611	B3/A-611	C2/A-611	EXIT	ACCESS CONTROL / ADA ACTUATOR /
002	4'-0"	7'-0"	2		HMP	D		-	A3/A-611	A4/A-611	-	MECHANICAL	
003	3'-0"	7'-0"	1		ALUM	D	1" ISG	-	COORDINATE	-	-	EXIT	ACCESS CONTROL
004	3'-1"	7'-0"	1	PAIR	ALUM	G	1" ISG	-	C3/A-611	B3/A-611	C2/A-611	EXIT	
005	3'-0"	7'-0"	1		ALUM	B	1" ISG	-	COORDINATE	-	-	EXIT	ACCESS CONTROL
006	3'-0"	7'-0"	2		HMP	D		-	COORDINATE	-	-	ELECTRICAL	
007	6'-0"	7'-0"	2	PAIR	HMP	E	-	-	-	-	-	PENTHOUSE	
100	6'-4"	7'-0"	1	PAIR	ALUM	A	1/4" SG	-	A2/A-611	B2/A-611	-	-	
100A	3'-0"	7'-0"	3		W/5V	C	1/4" SG	-	A1/A-611	A1/A-611	-	-	BUZZER CONTROL
101B	3'-0"	7'-0"	3		W/5V	C	1/4" SG	-	A1/A-611	A1/A-611	-	-	BUZZER CONTROL
103	3'-0"	7'-0"	3		W/5V	D	1/4" SG	-	A1/A-611	A1/A-611	-	-	HOME LIVING SPECIALIST
105	3'-0"	7'-0"	3		W/5V	C	1/4" SG	-	A1/A-611	A1/A-611	-	-	BOYS LAUNDRY
107	3'-0"	7'-0"	3		W/5V	C	1/4" SG	-	A1/A-611	A1/A-611	-	-	GIRLS LAUNDRY
108	3'-0"	7'-0"	3		W/5V	D	1/4" SG	20 MIN	A1/A-611	A1/A-611	-	-	SLEEPING ROOM
108.1	3'-0"	7'-0"	3		W/5V	D	1/4" SG	-	A1/A-611	A1/A-611	-	-	
110	3'-0"	7'-0"	3		W/5V	D	1/4" SG	-	A1/A-611	A1/A-611	-	-	COUNSELOR
111	3'-0"	7'-0"	4		W/5V	D		-	A1/A-611	A1/A-611	-	-	JANITOR
112	3'-0"	7'-0"	4		W/5V	D		-	A1/A-611	A1/A-611	-	-	STORAGE
113	3'-0"	7'-0"	3		W/5V	D		-	A1/A-611	A1/A-611	-	-	SLEEPING ROOM
114.1	3'-0"	7'-0"	4		W/5V	D	1/4" FG	20 MIN	A1/A-611	A1/A-611	-	-	STORAGE
120	3'-0"	7'-0"	4		W/5V	D	-	-	A1/A-611	A1/A-611	-	-	MENS RESTROOM
120.1	3'-0"	7'-0"	4		W/5V	D	-	-	A1/A-611	A1/A-611	-	-	STORAGE
121	3'-0"	7'-0"	4		W/5V	D	-	-	A1/A-611	A1/A-611	-	-	WOMENS RESTROOM
200	6'-4"	7'-0"	1	PAIR	ALUM	G	1/4" SG	-	A2/A-611	B2/A-611	C2/A-611	-	ACCESS CONTROL / ADA ACTUATOR / REMOVABLE CENTER MULLION
201B	6'-6"	5'-4"	-	-	-	-	-	-	-	-	-	-	KITCHEN: COILING GRILLE DOOR
202	3'-0"	7'-0"	3		W/5V	D	1/4" FG	20 MIN	A1/A-611	A1/A-611	-	-	GIRLS DORMITORY
203	3'-0"	7'-0"	4		W/5V	D	-	-	A1/A-611	A1/A-611	-	-	STORAGE
204	3'-0"	7'-0"	4		W/5V	D	-	-	A1/A-611	A1/A-611	-	-	GIRLS RESTROOM
205	3'-0"	7'-0"	4		W/5V	D	-	20 MIN	A1/A-611	A1/A-611	-	-	IT
206	3'-0"	7'-0"	4		W/5V	D	-	-	A1/A-611	A1/A-611	-	-	JANITOR
207	3'-0"	7'-0"	3		W/5V	D	1/4" FG	20 MIN	A1/A-611	A1/A-611	-	-	ISOLATION
207A	3'-0"	7'-0"	4		W/5V	D		-	A1/A-611	A1/A-611	-	-	RESTROOM
208	3'-0"	7'-0"	3		W/5V	D	1/4" FG	20 MIN	A1/A-611	A1/A-611	-	-	HONORS SLEEPING ROOM
208A	3'-0"	7'-0"	4		W/5V	D	-	-	A1/A-611	A1/A-611	-	-	RESTROOM
209	3'-0"	7'-0"	3		W/5V	D	1/4" FG	20 MIN	A1/A-611	A1/A-611	-	-	SLEEPING ROOM
210	3'-0"	7'-0"	3		W/5V	D	1/4" FG	20 MIN	A1/A-611	A1/A-611	-	-	SLEEPING ROOM
211	3'-0"	7'-0"	3		W/5V	D	1/4" FG	20 MIN	A1/A-611	A1/A-611	-	-	SLEEPING ROOM
212	3'-0"	7'-0"	3		W/5V	D	1/4" FG	20 MIN	A1/A-611	A1/A-611	-	-	SLEEPING ROOM
213	3'-0"	7'-0"	3		W/5V	D	1/4" FG	20 MIN	A1/A-611	A1/A-611	-	-	SLEEPING ROOM
215	3'-0"	7'-0"	3		W/5V	D		-	A1/A-611	A1/A-611	-	-	KITCHEN
216	3'-0"	7'-0"	3		W/5V	D	1/4" FG	20 MIN	A1/A-611	A1/A-611	-	-	BOYS DORMITORY
217	3'-0"	7'-0"	3		W/5V	D		20 MIN	A1/A-611	A1/A-611	-	-	STORAGE
218	3'-0"	7'-0"	4		W/5V	D	-	-	A1/A-611	A1/A-611	-	-	BOYS RESTROOM
219	3'-0"	7'-0"	4		W/5V	D	-	-	A1/A-611	A1/A-611	-	-	JANITOR
220	3'-0"	7'-0"	3		W/5V	D	1/4" FG	20 MIN	A1/A-611	A1/A-611	-	-	ISOLATION
221	3'-0"	7'-0"	3		W/5V	D		-	A1/A-611	A1/A-611	-	-	RESTROOM
222	3'-0"	7'-0"	3		W/5V	D	1/4" FG	20 MIN	A1/A-611	A1/A-611	-	-	SLEEPING ROOM
223	3'-0"	7'-0"	3		W/5V	D	1/4" FG	20 MIN	A1/A-611	A1/A-611	-	-	HONORS SLEEPING ROOM
223A	3'-0"	7'-0"	4		W/5V	D	-	-	A1/A-611	A1/A-611	-	-	RESTROOM
224	3'-0"	7'-0"	3		W/5V	D	1/4" FG	20 MIN	A1/A-611	A1/A-611	-	-	SLEEPING ROOM
225	3'-0"	7'-0"	3		W/5V	D	1/4" FG	20 MIN	A1/A-611	A1/A-611	-	-	SLEEPING ROOM
226	3'-0"	7'-0"	3		W/5V	D	1/4" FG	20 MIN	A1/A-611	A1/A-611	-	-	SLEEPING ROOM
227	3'-0"	7'-0"	3		W/5V	D	1/4" FG	20 MIN	A1/A-611	A1/A-611	-	-	SLEEPING ROOM

WINDOW SHADE LEGEND			
WINDOW TYPES	SIZE		SHADE TYPE
	WIDTH	HEIGHT	
H	12" - 0"		MANUAL ROLLER SHADE
I			MANUAL ROLLER SHADE
J			MANUAL ROLLER SHADE
K			MANUAL ROLLER SHADE
M			MANUAL ROLLER SHADE

GENERAL NOTES

- A. GROUT ALL HOLLOW METAL DOOR FRAMES SOLID.
- B. FINISH AND INSTALL PAINTABLE SEALANT AT INTERSECTION OF ALL METAL FRAMES AND WALLS.
- C. PAINT ALL VISIBLE SURFACES OF HOLLOW METAL GLASS TOPS.
- D. ALL FRAME DIMENSIONS AND PROFILES ARE TO BE FIELD VERIFIED.
- E. METAL INSERTS FOR GLASS SHALL BE 1-1/4" MAX. PAINT ALL VISIBLE SURFACES OF INSERTS.
- F. FINISH ALL METAL DOORS AND FRAMES. COLOR TO BE SELECTED BY ARCHITECT.
- G. LOCATE ROOM IDENTIFICATION SIGNS AT ALL DOORS AS INDICATED ON SHEET 4-A601 DOOR SCHEDULES.
- H. LOCATE EGRESS SIGNS (SEE SPECIFICATIONS FOR SIZE AND TYPE OF SIGN) AT EACH EGRESS EXIT AT EACH END OF ALL CORRIDORS. LOCATE EXIT SIGNS AT ALL VESTIBULE DOORS.
- I. COORDINATE FINAL LOCATION OF ALL BUILDING SIGNS WITH OWNER.
- J. LOCATE ALL EGRESS EXIT SIGNS AT ALL EGRESS EXITS.
- K. GLASS IN ALL EXTERIOR DOORS AND/OR DOOR FRAMES SHALL BE INSULATED GLAZING.
- L. SUBMIT SHOP DRAWINGS FOR HARDWARE SCHEDULE AND INFORMATION TO ARCHITECT FOR REVIEW.
- M. CENTER MULLION TYPING ON ALL DOUBLE-LEAF DOORS UNLESS NOTED ON SHEET 4-A601 DOOR SCHEDULES.
- N. FINISH AND INSTALL ALL EGRESS EXIT SIGNS AT ALL EGRESS EXITS AT ALL RESTROOMS THAT DO NOT HAVE DOORS.

LEGEND

- | | | |
|---------|---|--|
| HMP/ | - | HOLLOW METAL/PAINT |
| ALUM | - | ALUMINUM SYSTEM FINISH TO BE SELECTED BY ARCHITECT |
| W/SV | - | WOOD SOLID CORE / STAIN & VARNISH |
| 1" ISG | - | 1" INSULATED SAFETY GLASS |
| 1/4" SG | - | 1/4" SAFETY GLASS |
| 1/4" FG | - | 1/4" FIRE GLASS |
| SS | - | STAINLESS STEEL |
| SGG | - | SCHOOL GUARD GLASS |



CONSULTANT

CIVIL
Bohannon Huston
7500 Jefferson St NE,
Albuquerque, NM 87109
p_505.823.100

STRUCTURAL
Walla Engineering Ltd
6501 Americas Pkwy NE Ste. 302
Albuquerque, NM 87110
p_505.243.9287

M/E/P/FP
Bridgers and Paxton
4600-C Montgomery Blvd. NE
Albuquerque, New Mexico 87109
p 505.883.4111 f 505.888.1431

INTERIORS
Studio M
6501 Americas Pkwy NE Ste. 301
Albuquerque, NM 87110
p_505.243.9287

SITE
Groundwork Studio
6501 Americas Pkwy NE Ste. 350
Albuquerque, NM 87110
p_505.212.9126

FOOD SERVICE
Standard Kitchen Supply
 2405 Candelaria Rd. NE,
 Albuquerque, NM 87107
 p_505.341.1054

ENVELOPE AND ROOF CONSULTANT
Armstrong Group INC.
 2415 Princeton Ave, NE Suite E
 Albuquerque, NM 87107
 p 505.235.7596

AV & TECHNOLOGY
Network Cabling, INC
 3100 La Plata HWY.
 Farmington, NM 87401
 p 505.598.5054



**Dzilth-Na-O-Dith-Hle -
New Dormitory
Building**

CONSTRUCTION DOCUMENTS

35 Road 7585, Bloomfield, NM
87413

DECEMBER 4TH, 2020

MARK	DATE	DESCRIPTION
1	12/12/12	THIS IS A TEST
ISSUE:		
DATE:		
PROJECT NO:		751
CAD DWG FILE:		
DRAWN BY:		Author
CHECKED BY:		Checker

SHEET TITLE

DOOR-WINDOW SCHEDULE

A-601

CONSULTANT

CIVIL
Bohannon Huston
7500 Jefferson St. NE,
Albuquerque, NM 87109
p_505.823.100

STRUCTURAL
Walla Engineering Ltd
6501 Americas Pkwy NE Ste. 302
Albuquerque, NM 87110
p_505.243.9287

M/E/P/FP
Bridgers and Paxton
4600-C Montgomery Blvd. NE
Albuquerque, New Mexico 87109
p_505.883.4111 f_505.888.1436

INTERIORS
Studio M
6501 Americas Pkwy NE Ste. 301
Albuquerque, NM 87110
p_505.243.9287

SITE
Groundwork Studio
6501 Americas Pkwy NE Ste. 350
Albuquerque, NM 87110
p_505.212.9126

FOOD SERVICE
Standard Kitchen Supply
2405 Candelaria Rd. NE,
Albuquerque, NM 87107
p_505.341.1054

ENVELOPE AND ROOF CONSULTANT
Armstrong Group INC.
2415 Princeton Ave, NE Suite E
Albuquerque, NM 87107
p_505.235.7596

AV & TECHNOLOGY
Network Cabling, INC
3100 La Plata HWY.
Farmington, NM 87401
p_505.598.5054



Dzilth-Na-O-Dith-Hle -
New Dormitory
Building

CONSTRUCTION
DOCUMENTS


35 Road 7585, Bloomfield, NM
87413

DECEMBER 4TH, 2020


MARK	DATE	DESCRIPTION
ISSUE:		
DATE:		
PROJECT NO:		751
CAD DWG FILE:		
DRAWN BY:		Author
CHECKED BY:		Checker

SHEET TITLE
WINDOW / STOREFRONT
DETAILS


A-611




C1 STOREFRONT INTERIOR - HEAD
3" = 1'-0"



HEAD




JAMB




SIDELITE SILL


A1 HOLLOW METAL INTERIOR
3" = 1'-0"




B2 STOREFRONT - SILL
3" = 1'-0"



A2 DOOR THRESHOLD
3" = 1'-0"




C3 STOREFRONT HEAD - STUCCO SOFFIT
3" = 1'-0"




B3 STOREFRONT HEAD - STUCCO
3" = 1'-0"

NOTE: JAMB SIMILAR



A3 STOREFRONT SILL - MASONRY VENEER
3" = 1'-0"



A4 STOREFRONT SILL - STUCCO
3" = 1'-0"

CONSULTANT

CIVIL
Bohannon Huston
7500 Jefferson St. NE,
Albuquerque, NM 87109
p_505.823.100

STRUCTURAL
Walla Engineering Ltd
6501 Americas Pkwy NE Ste. 302
Albuquerque, NM 87110
p_505.243.9287

M/E/P/FP
Bridgers and Paxton
4600-C Montgomery Blvd. NE
Albuquerque, New Mexico 87109
p_505.883.4111 f_505.888.1436

INTERIORS
Studio M
6501 Americas Pkwy NE Ste. 301
Albuquerque, NM 87110
p_505.243.9287

SITE
Groundwork Studio
6501 Americas Pkwy NE Ste. 350
Albuquerque, NM 87110
p_505.212.9126

FOOD SERVICE
Standard Kitchen Supply
2405 Candelaria Rd. NE,
Albuquerque, NM 87107
p_505.341.1054

ENVELOPE AND ROOF CONSULTANT
Armstrong Group INC.
2415 Princeton Ave, NE Suite E
Albuquerque, NM 87107
p_505.235.7596

AV & TECHNOLOGY
Network Cabling, INC
3100 La Plata HWY.
Farmington, NM 87401
p_505.598.5054



Dzilth-Na-O-Dith-Hle -
New Dormitory
Building

CONSTRUCTION
DOCUMENTS

35 Road 7585, Bloomfield, NM
87413

DECEMBER 4TH, 2020


MARK	DATE	DESCRIPTION
ISSUE:		
DATE:		
PROJECT NO:		751
CAD DWG FILE:		
DRAWN BY:	Author	
CHECKED BY:	Checker	

SHEET TITLE
INTERIOR FINISH LEGEND

ID-101

ROOM FINISH LEGEND				DZ - DORMATORY & SCHOOL			
CARPET TILES - 12" X 24"							
		CPT1	MANUFACTURER:		SHAW CONTRACT FLOORING		
			STYLE/ COLLECTION:		THINK/ MINDFUL PLAY		
			COLOR:		TBD		
NOTE:				INSTALLATION METHOD: (CONFIRM @ TIME OF INSTALL.)			
CARPET TILES - 18" X 36"							
		CPT2	MANUFACTURER:		SHAW CONTRACT FLOORING		
			STYLE/ COLLECTION:		ENCLAVE / SHIFTING FIELDS		
			COLOR:		TBD		
NOTE:				INSTALLATION METHOD: (CONFIRM @ TIME OF INSTALL.)			
WALK-OFF MODULAR TILE - 24" X 24" - 10'-0" IN THE DIRECTION OF TRAVEL							
		CPT3	MANUFACTURER:		INTERFACE COMMERCIAL		
			STYLE:		SUPER FLOR		
			COLOR:		TBD		
NOTE:				INSTALLATION METHOD: $\frac{1}{4}$ TURNED INSTALLATION			
VINYL COMPOSITION TILE 12" X 12"							
BASE BID			MANUFACTURER:		ARMSTRONG COMMERICAL TILE		
			STYLE/ COLLECTION:		PREMIUM EXCELON/ CROWN TEXTURE		
FIELD 40%	VCT1			COLOR:	TBD		
FIELD 30%	VCT2			COLOR:	TBD		
ACCENT 10%	VCT3			COLOR:	TBD		
ACCENT 10%	VCT4			COLOR:	TBD		
ACCENT 10%	VCT5			COLOR:	TBD		
LUXURY VINYL TILE - 12" X 24"							
ADD ALT. #1			MANUFACTURER:		MANNINGTON COMMERICAL		
			STYLE/ COLLECTION:		STRIDE & GROOVE/ COLOR ANCHOR		
FIELD 40%	LVT1			COLOR:	TBD		
FIELD 30%	LVT2			COLOR:	TBD		
ACCENT 10%	LVT3			COLOR:	TBD		
ACCENT 10%	LVT4			COLOR:	TBD		
ACCENT 10%	LVT5			COLOR:	TBD		
PORCELAIN FLOOR TILE - 24" X 24"							
RESTROOMS				MANUFACTURER:	DAL TILE		
	FT1			SERIES:	TBD		
				COLOR:	TBD		
NOTE:				INSTALLATION METHOD: RUNNING BOND			
PORCELAIN WALL TILE BASE - 12" X 24" (CUT IN FIELD FOR 6" APPLICATION							
		PWB	MANUFACTURER:		DAL TILE		
			SERIES:				
			COLOR:				
NOTE:				EPOXY FLOOR GROUT: MFG: LATICRETE - COLOR: TBD			
PORCELAIN STONE TILE - 6" X 6" (PTG) & WALL BASE (PTGB)							
KITCHEN				MANUFACTURER:	DAL TILE		
	PTG/ PTGB			SERIES:	SURETREAD		
				COLOR:	TBD		
NOTE:				EPOXY FLOOR GROUT: MFG: LATICRETE - COLOR: TBD			
SPORTS FLOORING - MULTI-USE GYM							
				MANUFACTURER:	TARKETT SPORTS FLOORING		
		SPF			SERIES:	OMNISPORTS - CLASS 2	
					COLOR:	TBD	
SEALED CONCRETE							
				MANUFACTURER:	REFER TO PROJECT SPECIFICATION MANUAL		
4" VINYL WALL COVE BASE							
		VB1	MANUFACTURER:		JOHNSONITE		
			COLOR:		TBD		

WOOD ATHLETIC FLOORING			
		MANUFACTURER:	AACER SPORTS FLOORING
		SERIES:	AACER CRUSH II
		WOOD SPECIES:	TBD
FLOOR TRANSITION			
		MANUFACTURER:	SCHLUTER SYSTEMS
LVT/ CARPET		SERIES:	CONTRACTOR TO PROVIDE
LVT/ PORCELAIN TILE		FINISH:	SATIN ANODIZED ALUMINUM
WALLS			
WALL TILE - GLAZED TILE - 8" X 24"			
		MANUFACTURER:	DAL TILE
		COLLECTION:	COLOR WHEEL - LINEAR
FIELD 50%	WT 1	COLOR:	TBD
ACCENT 30%	WT 2	COLOR:	TBD
ACCENT 10%	WT 3	COLOR:	TBD
ACCENT 10%	WT 3	COLOR:	TBD
NOTE: WALL GROUT: MFG: LATICRETE - COLOR: TBD			
CORNER BEAD - EDGE PROTECTION AT 90 DEGREE OUTSIDE CORNER			
		MANUFACTURER:	SCHLUTER SYSTEMS
		SERIES:	ED/RO 100E
		FINISH:	SATIN ANODIZED ALUMINUM
		SIZE:	$\frac{3}{8}$ " X 10'-0" CUT TO LENGTH
PAINT			
		MANUFACTURER:	DUNN EDWARDS
FIELD	PT1	COLOR:	
H MDF	PT2	COLOR:	
ACCENT	PT3	COLOR:	
ACCENT	PT4	COLOR:	
ACCENT	PT5	COLOR:	
FRP PANEL			
		MANUFACTURER:	MARLITE PANEL SYSTEMS
JANITOR	FRP1	FINISH:	PEBBLED SURFACE
		COLOR :	# P100 WHITE
PLASTIC LAMINATE			
		MANUFACTURER:	TBD
		COLOR:	TBD
LOCATION:	HORIZONTAL/ UPPER CASEWORK IN BREAKROOM		
		MANUFACTURER:	TBD
		COLOR:	TBD
LOCATION:	LOWER CASEWORK IN BREAKROOM		
		MANUFACTURER:	TBD
		COLOR:	TBD
		MANUFACTURER:	TBD
		COLOR:	TBD



A1 INTERIOR FINISH FLOOR PLAN
1/8" = 1'-0"

CONSULTANT

CIVIL
Bohannon Huston
7500 Jefferson St NE,
Albuquerque, NM 87109
p_505.823.100

STRUCTURAL
Walla Engineering Ltd
6501 Americas Pkwy NE Ste. 302
Albuquerque, NM 87110
p_505.243.9287

M/E/P/FP
Bridgers and Paxton
4600-C Montgomery Blvd. NE
Albuquerque, New Mexico 87109
p_505.883.4111 f_505.888.1436

INTERIORS
Studio M
 6501 Americas Pkwy NE Ste. 301
 Albuquerque, NM 87110
 p_505.243.9287

SITE
Groundwork Studio
6501 Americas Pkwy NE Ste. 350
Albuquerque, NM 87110
p_505.212.9126

FOOD SERVICE
Standard Kitchen Supply
 2405 Candelaria Rd. NE,
 Albuquerque, NM 87107
 p_505.341.1054

ENVELOPE AND ROOF CONSULTANT
Armstrong Group INC.
 2415 Princeton Ave, NE Suite E
 Albuquerque, NM 87107
 p_505.235.7596

AV & TECHNOLOGY
Network Cabling, INC
 3100 La Plata HWY.
 Farmington, NM 87401
 p_505.598.5054



**Dzilth-Na-O-Dith-Hle -
New Dormitory
Building**

**CONSTRUCTION
DOCUMENTS**

35 Road 7585, Bloomfield, NM
87413

DECEMBER 4TH, 2020


MARK	DATE	DESCRIPTION
ISSUE:		
DATE:		
PROJECT NO:		751
CAD DWG FILE:		
DRAWN BY:		Author
CHECKED BY:		Checker

SHEET TITLE
INTERIOR FINISH PLANS


CONSULTANT

PLUMBING SYMBOL LEGEND


PLUMBING FIXTURE & EQUIPMENT SYMBOL




SECTION SYMBOL



DETAIL SYMBOL




SECTION, ELEVATION, AND DETAIL TITLES




PIPING SYMBOLS

SYMBOL	ABBREVIATION	DESCRIPTION
AV	AV	ACID VENT
AW	AW	ACID WASTE
CA	CA	COMPRESSED AIR
CD	CD	CONDENSATE DRAIN
DCW	DCW	DOMESTIC COLD WATER
DHW	DHW	DOMESTIC HOT WATER
DHWR	DHWR	DOMESTIC HOT WATER RETURN
DHW 140°F	DHW 140°F	140° DOMESTIC HOT WATER
DHWR 140°F	DHWR 140°F	140° DOMESTIC HOT WATER RETURN
ROS	ROS	REVERSE OSMOSIS SUPPLY
ROR	ROR	REVERSE OSMOSIS RETURN
MU	MU	MAKE-UP WATER
NPW	NPW	NON-POTABLE WATER
V	V	VENT
DIS	DIS	DEIONIZED WATER SUPPLY
DIR	DIR	DEIONIZED WATER RETURN
SAN	SAN	SANITARY SEWER
GW	GW	GREASE WASTE
GV	GV	GREASE VENT
RD	RD	STORM/ROOF DRAIN
ORD	ORD	OVERFLOW ROOF DRAIN
LPG	LPG	LIQUEFIED PETROLEUM GAS
G	G	NATURAL GAS-LOW PRESSURE
NGM	NGM	NATURAL GAS-MEDIUM PRESSURE
NGH	NGH	NATURAL GAS-HIGH PRESSURE
IRR	IRR	IRRIGATION
SCW	SCW	SOFT COLD WATER
SHW	SHW	SOFT HOT WATER
TWR (L...)	TWR	TEMPERED WATER RETURN (TEMP °F)
TW (L...)	TW	TEMPERED WATER (TEMP °F)
PD	PD	PUMPED DISCHARGE LINE
ICW	ICW	INDUSTRIAL COLD WATER
IHW	IHW	INDUSTRIAL HOT WATER
IHW	IHW	INDUSTRIAL HOT WATER RETURN
INW	INW	INDUSTRIAL WASTE
IA	IA	INSTRUMENT COMPRESSED AIR
IW	IW	INDIRECT WASTE
LA	LA	LAB COMPRESSED AIR

SITE UTILITY SYMBOLS



VALVE SYMBOLS





ABBREVIATIONS

AFF	ABOVE FINISHED FLOOR
AFG	ABOVE FINISHED GRADE
ANT	ACID NEUTRALIZING TANK
AVTR	ACID RESISTANT VENT THROUGH ROOF
B.C.	BALANCING COCK
BOP	BOTTOM OF PIPE
BTU	BRITISH THERMAL UNIT
BTUH	BTU PER HOUR
CWB	CLOTHES WASHER BOX
CFH	CUBIC FEET PER HOUR
CO	CLEANOUT
COTG	CLEANOUT TO GRADE
CP	CIRCULATION PUMP
CVW	COMBINATION WASTE AND VENT
DCO	DOUBLE CLEANOUT
DCOTG	DOUBLE CLEANOUT TO GRADE
DF	DOWN
DN	DOWNSPOUT
DS	DOWNSPOUT NOZZLE
EL	ELEVATION
ELW	ELECTRIC WATER HEATER
EW	ELECTRIC WATER COOLER
EEW	EMERGENCY EYEWASH
ES	EMERGENCY SHOWER
ESEW	EMERGENCY SHOWER EYE WASH
F	DEGREES FAHRENHEIT
FCO	FLOOR CLEANOUT
FFE	FINISHED FLOOR ELEVATION
FEET	FEET
FOS	FUEL OIL SUPPLY
FOR	FUEL OIL RETURN
FOV	FUEL OIL VENT
FV	FLUSH VALVE
GD	GUTTER DRAIN
GI	GREASE INTERCEPTOR
GPH	GALLONS PER HOUR
GPM	GALLONS PER MINUTE
GWH	GAS WATER HEATER
HB	HOSE BIBB
HD	HEAD
HP	HORSEPOWER
IN	INCHES
INV	INVERT
KW	KILOWATT
MBh	1,000 BTUH
MV	MIXING VALVE
NA	NOT APPLICABLE
NIC	NOT IN CONTRACT
No. #	NUMBER
N.C.	NORMALLY CLOSED
N.O.	NORMALLY OPEN
OS&Y	OUTSIDE SCREW AND YOKE
PH	PHASE
PH	POWERS OF HARDNESS
PSIG	POUNDS PER SQUARE INCH GAUGE
SP	STATIC PRESSURE
TD	TRENCH DRAIN
TYP	TYPICAL
YB	YARD BOX
YH	YARD HYDRANT
WCO	WALL CLEANOUT
WCO	WATER CLOSET

NOTE: NOT ALL ABBREVIATIONS OR SYMBOLS APPLY TO THIS PROJECT

SCHEMATIC SYMBOLS





A1 WASTE & VENT FLOOR PLAN
1/8" = 1'-0"

0' 4' 8' 16'

GENERAL NOTES

- REFER TO ARCHITECTURAL FLOOR PLANS FOR EXACT LOCATION AND HEIGHTS OF ALL PLUMBING FIXTURES BEFORE ROUGH-IN OR INSTALLATION OF PIPE. PLUMBING FIXTURES SHALL BE MOUNTED AT HEIGHTS SHOWN ON ARCHITECTURAL ELEVATION DRAWINGS.
- ALL PIPING IN FINISHED ROOMS SHALL BE CONCEALED IN FURRED CHASES UNLESS OTHERWISE NOTED ON THIS DRAWING.
- PROVIDE HINGED ACCESS DOORS FOR VALVES, WATER HAMMER ARRESTERS, ISOLATION BALL VALVES LOCATED IN NONACCESSIBLE CEILINGS AND CHASES. DOORS FURNISHED PER ARCHITECTURAL SPECIFICATIONS AND PURCHASED AND INSTALLED PER DIVISION 22. ACCESS DOOR RATING SHALL MATCH THE CLASSIFICATION OF WALLS AND CEILING FIRE RATING. COORDINATE COLOR AND TYPE OF ACCESS DOOR WITH ARCHITECTURAL PRIOR TO PERFORMING WORK.
- REFER TO ARCHITECTURAL DRAWINGS FOR EXACT LOCATION OF ALL FIRE RATED AND OR SMOKE RATED WALLS AND ASSEMBLIES. PIPING PENETRATIONS OF FIRE AND SMOKE RATED WALLS AND LISTED ASSEMBLIES SHALL BE CAULKED AIRTIGHT TO THE ADJACENT STRUCTURE BY MEANS OF U.L. LISTED FIRE PROOF CAULKING MATERIAL.
- COORDINATE ALL PLUMBING PIPING WITH ALL OTHER TRADES AND PROVIDE NECESSARY OFFSETS TO AVOID CONFLICTS AND TO MAINTAIN REQUIRED EQUIPMENT ACCESS AND SERVICEABILITY.
- PIPING LOCATIONS HAVE BEEN SHOWN FOR CLARITY AND DO NOT NECESSARILY REFLECT THE EXACT LOCATION OF PIPE. COORDINATE ROUTING WITH ALL OTHER TRADES BEFORE INSTALLATION OR MAKEUP OF PIPE. PROVIDE COORDINATION DRAWINGS PER SPECIFICATIONS.
- PLUMBING FLOOR AND ROOF PENETRATIONS ARE SUBJECT TO CHANGE. COORDINATE WITH ARCHITECTURAL DRAWINGS FOR FINAL PLUMBING AND EQUIPMENT LOCATIONS.
- ALL PLUMBING FIXTURES SHALL HAVE WALL CLEANOUTS.
- ALL P-TRAPS TO FLOOR SINKS AND FLOOR DRAINS SHALL BE SUPPLIED WITH A TRAP SEAL GUARD.
- REFER TO DRAWING P-701 FOR PLUMBING ROUGH IN REQUIREMENTS.
- ALL STORM, SANITARY AND WASTE PIPING IS BELOW THIS SLAB UNLESS OTHERWISE NOTED.
- REFER TO SITE PLAN PS101 IN CLASSROOM SET FOR SANITARY, STORM EXITS ALONG WITH DOMESTIC COLD WATER AND GAS ENTRY. COORDINATE WITH CIVIL DRAWINGS.

KEYNOTES

- ROOF DRAIN LEADER DOWN FROM ABOVE.
- COORDINATE WITH OTHER TRADES.
- OFFSET BELOW WIDE FLANGE BEAM.
- 6" ROOF DRAIN LEADER DOWN IN CHASES, PROVIDE WALL CLEANOUT AT BASE, THEN THROUGH STEM WALL (PIPING ON TOP OF FOOTING TO MAINTAIN HIGHER EXITING INVERT), COORDINATE WITH OTHER TRADES.
- STRUCTURAL FOOTING, TYPICAL.
- 3/4" CONDENSATE FROM HVAC UNIT, ROUTE TO SERVICE SINK, INDIRECT DISCHARGE.

CONSULTANT


Dzilth-Na-O-Dith-Hle - New Dormitory Building CONSTRUCTION DOCUMENTS

35 Road 7585, Bloomfield, NM 87413

DECEMBER 4, 2020

MARK	DATE	DESCRIPTION
	11/17/20	Addendum Changes
ISSUE:		
DATE:		
PROJECT NO:		751
CAD DWG FILE:		
DRAWN BY:		AJM/SNB
CHECKED BY:		NZ

SHEET TITLE
WASTE & VENT FLOOR PLAN



A1 PLUMBING ROOF PLAN
1/8" = 1'-0"



GENERAL NOTES

- REFER TO ARCHITECTURAL FLOOR PLANS FOR EXACT LOCATION AND HEIGHTS OF ALL PLUMBING FIXTURES BEFORE ROUGH-IN OR INSTALLATION OF PIPE. PLUMBING FIXTURES SHALL BE MOUNTED AT HEIGHTS SHOWN ON ARCHITECTURAL ELEVATION DRAWINGS.
- ALL PIPING IN FINISHED ROOMS SHALL BE CONCEALED IN FURRED CHASES UNLESS OTHERWISE NOTED ON THIS DRAWING.
- PROVIDE HINGED ACCESS DOORS FOR VALVES, WATER HAMMER ARRESTERS, ISOLATION BALL VALVES LOCATED IN NONACCESSIBLE CEILINGS AND CHASES. DOORS FURNISHED PER ARCHITECTURAL SPECIFICATIONS AND PURCHASED AND INSTALLED PER DIVISION 22. ACCESS DOOR RATING SHALL MATCH THE CLASSIFICATION OF WALLS AND CEILING FIRE RATING. COORDINATE COLOR AND TYPE OF ACCESS DOOR WITH ARCHITECTURAL PRIOR TO PERFORMING WORK.
- REFER TO ARCHITECTURAL DRAWINGS FOR EXACT LOCATION OF ALL FIRE RATED AND OR SMOKE RATED WALLS AND ASSEMBLIES. PIPING PENETRATIONS OF FIRE AND SMOKE RATED WALLS AND LISTED ASSEMBLIES SHALL BE CAULKED AIRTIGHT TO THE ADJACENT STRUCTURE BY MEANS OF U.L. LISTED FIRE PROOF CAULKING MATERIAL.
- COORDINATE ALL PLUMBING PIPING WITH ALL OTHER TRADES AND PROVIDE NECESSARY OFFSETS TO AVOID CONFLICTS AND TO MAINTAIN REQUIRED EQUIPMENT ACCESS AND SERVICEABILITY.
- PIPING LOCATIONS HAVE BEEN SHOWN FOR CLARITY AND DO NOT NECESSARILY REFLECT THE EXACT LOCATION OF PIPE. COORDINATE ROUTING WITH ALL OTHER TRADES BEFORE INSTALLATION OR MAKEUP OF PIPE. PROVIDE COORDINATION DRAWINGS PER SPECIFICATIONS.
- PLUMBING FLOOR AND ROOF PENETRATIONS ARE SUBJECT TO CHANGE. COORDINATE WITH ARCHITECTURAL DRAWINGS FOR FINAL PLUMBING AND EQUIPMENT LOCATIONS.
- ALL PLUMBING FIXTURES SHALL HAVE WALL CLEANOUTS.
- ALL P-TRAPS TO FLOOR SINKS AND FLOOR DRAINS SHALL BE SUPPLIED WITH A TRAP SEAL GUARD.
- REFER TO DRAWING P-701 FOR PLUMBING ROUGH IN REQUIREMENTS.
- ALL STORM, SANITARY AND WASTE PIPING IS BELOW THIS SLAB UNLESS OTHERWISE NOTED.

KEYNOTES

- COORDINATE ROOF DRAIN LOCATION WITH ARCHITECTURAL ROOF PLANS AND STRUCTURAL PLANS.
- REDUCED PRESSURE ZONE BACKFLOW PREVENTER SERVING AHU, SEE DETAIL A1/P-502.
- ROUTE ROOF DRAINS TIGHT TO STRUCTURE.
- WATER METER FOR MAKE UP MEASUREMENT. COORDINATE WITH CONTROLS DRAWING M602 FOR WATER EFFICIENCY.


Dzilth-Na-O-Dith-Hle - New Dormitory Building
CONSTRUCTION DOCUMENTS

35 Road 7585, Bloomfield, NM 87413

DECEMBER 4, 2020

MARK	DATE	DESCRIPTION
	11/17/20	Addendum Changes
ISSUE:		
DATE:		
PROJECT NO:		751
CAD DWG FILE:		
DRAWN BY:		AJM/SNB
CHECKED BY:		NZ

SHEET TITLE
PLUMBING ROOF PLAN



1. 3/4" DOMESTIC COLD WATER UP TO RPZ SERVING AHU AND WATER METER IN PENTHOUSE.
2. REFER TO CIRCUIT SOLVER DETAIL C2/P-502.

CONSULTANT

PP-101



1. 4" ROOF DRAIN DROP FROM ABOVE. REFER TO DRAWING P-701 FOR ROOF DRAIN FIXTURE.
2. STRUCTURAL FOOTING, TYPICAL.
3. 4" VENT UP, 4" VENT UP THROUGH ROOF. REFER TO DRAWING PL-131 FOR CONTINUATION.
4. 3/4" CONDENSATE FROM HVAC UNIT, INDIRECT DISCHARGE TO SERVICE SINK.
5. LINT INTERCEPTOR BELOW FINISHED FLOOR, PROVIDE EXTENSION AS REQUIRED, INSTALL PER MANUFACTURERS RECOMMENDATIONS.

CONSULTANT


B **BRIDGERS
& PAXTON**

4600 C Montgomery Blvd. NE
Albuquerque, NM 87109 | 505.883.4111 | www.bpce.com


DAVID ZHIANI
NEW MEXICO
REGISTERED PROFESSIONAL ENGINEER
24274
Date: 08/20/2003
15:35:48-0700
ENGINEER

SHEET TITLE
ENLARGED PLUMBING PLANS


P-401




D1 ENLARGED PRESSURE PIPING PLAN - MECH ROOM
1/4" = 1'-0"




D3 ENLARGED PRESSURE PIPING PLAN - BOYS RR / LAUNDRY
1/4" = 1'-0"



D5 ENLARGED PRESSURE PIPING PLAN - BOYS RR 109
1/4" = 1'-0"



A1 ENLARGED PRESSURE PIPING PLAN - GIRLS RR 114
1/4" = 1'-0"



A3 ENLARGED PRESSURE PIPING PLAN - GIRLS RR 204 / STOR.
1/4" = 1'-0"

GENERAL NOTES

- REFER TO ARCHITECTURAL FLOOR PLANS FOR EXACT LOCATION AND HEIGHTS OF ALL PLUMBING FIXTURES BEFORE ROUGH-IN OR INSTALLATION OF PIPE. PLUMBING FIXTURES SHALL BE MOUNTED AT HEIGHTS SHOWN ON ARCHITECTURAL ELEVATION DRAWINGS.
- ALL PIPING IN FINISHED ROOMS SHALL BE CONCEALED IN FURNISHED CHASES UNLESS OTHERWISE NOTED ON THIS DRAWING.
- PROVIDE HINGED ACCESS DOORS FOR VALVES, WATER HAMMER ARRESTERS, ISOLATION BALL VALVES LOCATED IN INACCESSIBLE CEILINGS AND CHASES. DOORS FURNISHED PER ARCHITECTURAL SPECIFICATIONS AND PURCHASED AND INSTALLED PER DIVISION 22. ACCESS DOOR RATING SHALL MATCH THE CLASSIFICATION OF WALLS AND CEILING FIRE RATING. COORDINATE COLOR AND TYPE OF ACCESS DOOR WITH ARCHITECTURAL PRIOR TO PERFORMING WORK.
- REFER TO ARCHITECTURAL DRAWINGS FOR EXACT LOCATION OF ALL FIRE RATED AND OR SMOKE RATED WALLS AND ASSEMBLIES. PIPING PENETRATIONS OF FIRE AND SMOKE RATED WALLS AND LISTED ASSEMBLIES SHALL BE CAULKED AIRTIGHT TO THE ADJACENT STRUCTURE BY MEANS OF U.L. LISTED FIRE PROOF CAULKING MATERIAL.
- COORDINATE ALL PLUMBING PIPING WITH ALL OTHER TRADES AND PROVIDE NECESSARY OFFSETS TO AVOID CONFLICTS AND TO MAINTAIN REQUIRED EQUIPMENT ACCESS AND SERVICEABILITY.
- PIPING LOCATIONS HAVE BEEN SHOWN FOR CLARITY AND DO NOT NECESSARILY REFLECT THE EXACT LOCATION OF PIPE. COORDINATE ROUTING WITH ALL OTHER TRADES BEFORE INSTALLATION OR MAKEUP OF PIPE. PROVIDE COORDINATION DRAWINGS PER SPECIFICATIONS.
- PLUMBING FLOOR AND ROOF PENETRATIONS ARE SUBJECT TO CHANGE. COORDINATE WITH ARCHITECTURAL DRAWINGS FOR FINAL PLUMBING AND EQUIPMENT LOCATIONS.
- ALL PLUMBING FIXTURES SHALL HAVE WALL CLEANOUTS.
- ALL P-TRAPS TO FLOOR SINKS AND FLOOR DRAINS SHALL BE SUPPLIED WITH A TRAP SEAL GUARD.
- REFER TO DRAWING P-701 FOR PLUMBING ROUGH IN REQUIREMENTS.
- REFER TO DRAWING P-702 FOR PLUMBING EQUIPMENT SCHEDULES.
- DUE TO THE SMALL SCALE OF THE DRAWINGS IT IS IMPOSSIBLE TO SHOW ALL VALVES AND APPURTENANCES ON THE PLANS. THE PLUMBING CONTRACTOR SHALL PROVIDE A FULL PORT LINE-SIZED ISOLATION BALL VALVE ON EACH DOMESTIC HOT AND COLD WATER LINE TO A PLUMBING FIXTURE WHETHER SHOWN OR NOT. THE DOMESTIC HOT WATER SYSTEM AS INSTALLED SHALL NOT HAVE ANY DEAD LEGS IN EXCESS OF 1.5 X THE DIAMETER OF THE PIPE IN QUESTION.
- ALL 4" AND LARGER HORIZONTAL SANITARY LINES SHALL SLOPE 1/8" / FT. ALL HORIZONTAL SANITARY LINES LESS THAN 4" SHALL SLOPE 1/4" / FT.

KEYNOTES

- 3/4" DOMESTIC COLD WATER UP TO RPZ SERVING AHU AND WATER METER IN PENTHOUSE, SEE DETAIL A1/P-502.
- 24"X24"ACCESS PANEL, TYPICAL. COORDINATE LOCATION WITH ARCHITECT.
- WATER METER FOR DOMESTIC WATER MEASUREMENT. COORDINATE WITH CONTROLS DRAWING M602 FOR WATER EFFICIENCY.
- WATER METER FOR DOMESTIC HOT WATER MEASUREMENT. COORDINATE WITH CONTROLS DRAWING M602 FOR WATER EFFICIENCY.
- WATER METER FOR IRRIGATION WATER MEASUREMENT. COORDINATE WITH CONTROLS DRAWING M602 FOR WATER EFFICIENCY AND COORDINATE WITH IRRIGATION PLANS FOR CONTINUATION TO SITE.
- SEE CIVIL EARLY WORK PACKAGE DRAWING C205 FOR PIPING.
- REGULATOR, SET TO 14"wc, ROUTE 3/4" GAS VENT TO ATMOSPHERE IN A CODE COMPLIANT MANNER.

CONSULTANT


Dzilth-Na-O-Dith-Hle - New Dormitory Building CONSTRUCTION DOCUMENTS


35 Road 7585, Bloomfield, NM 87413

DECEMBER 4, 2020

MARK	DATE	DESCRIPTION
	11/17/20	Addendum Changes
ISSUE:		
DATE:		
PROJECT NO:		751
CAD DWG FILE:		
DRAWN BY:		AJM/SNB
CHECKED BY:		NZ

SHEET TITLE
ENLARGED PLUMBING PLANS





1

2

3

4

5

6

PLUMBING FIXTURE SCHEDULE						
REFER TO DIVISION 22 4000 FOR ADDITIONAL INFORMATION						
SYMBOL	FIXTURE			TRIM/FAUCET		REMARKS:
	TYPE	MANUFACTURER	MODEL	MANUFACTURER	MODEL	
P1	WATER CLOSET - WALL MTD. - FLUSH VALVE MANUAL - WATERSENSE	AMERICAN STANDARD	3351.101	SLOAN	ROYAL 111-1.28	1.28 GPF EXPOSED, CHROME PLATED, LOW FLOW, SEAT: HEAVY DUTY, OPEN FRONT LESS COVER, SOLID PLASTIC, WHITE, MFG: CHURCH 950SSC OR EQUAL
P1a	WATER CLOSET (BARRIER FREE) - WALL MTD. - FLUSH VALVE MANUAL - WATERSENSE	AMERICAN STANDARD	3461.001 "MADERA"	SLOAN	ROYAL 111-1.28	1.28 GPF MANUAL, EXPOSED, CHROME PLATED, LOW FLOW, SEAT: HEAVY DUTY, OPEN FRONT LESS COVER, SOLID PLASTIC, WHITE, MFG: CHURCH 950SSC OR EQUAL
P1e	WATER CLOSET - FLOOR MTD. - FLUSH TANK	AMERICAN STANDARD	2315.228	-	-	1.28 GPF CHROME LEVER TRIP, LOW FLOW, SEAT: #5001G-055 BABY DEVORO SEAT OPEN FRONT, LESS COVER
P2a	URINAL (BARRIER FREE) - WALL MTD. - FLUSH VALVE MANUAL - WATERSENSE	AMERICAN STANDARD	6590.001 "WASHBROOK"	SLOAN	ROYAL 186-0.5	0.125 GPF MANUAL, EXPOSED, CHROME PLATED, LOW FLOW, WHITE VITREOUS CHINA, 3/4" TOP SPUD
P3	LAVATORY - WALL MOUNT - MANUAL	AMERICAN STANDARD	0355.012	CHICAGO FAUCETS	802-VE39VPABCP	0.35 GPM DECK MOUNT, CHROME, LEVER HANDLES, VANDAL PROOF, 4" CENTERS, PROVIDE ANGLE STOPS, FLEXIBLE RISERS, ADJUSTABLE P-TRAP, AERATOR: CHICAGO FAUCET E39VPJKAACP, MIXING VALVE: WATTS MODEL LFUSG-B UNDER SINK
P3a	LAVATORY (BARRIER FREE) - WALL MOUNT - MANUAL	AMERICAN STANDARD	0355.012	CHICAGO FAUCETS	802-VE39VPABCP	0.35 GPM DECK MOUNT, CHROME, LEVER HANDLES, VANDAL PROOF, 4" CENTERS, PROVIDE ANGLE STOPS, FLEXIBLE RISERS, ADJUSTABLE P-TRAP, AERATOR: CHICAGO FAUCET E39VPJKAACP, MIXING VALVE: WATTS MODEL LFUSG-B UNDER SINK
P3e	LAVATORY (BARRIER FREE) COUNTER TOP - ROUND - MANUAL	AMERICAN STANDARD	0491.019	CHICAGO FAUCETS	802-VE39VPABCP	0.35 GPM DECK MOUNT, CHROME, LEVER HANDLES, VANDAL PROOF, 4" CENTERS, PROVIDE ANGLE STOPS, FLEXIBLE RISERS, ADJUSTABLE P-TRAP, AERATOR: CHICAGO FAUCET E39VPJKAACP, MIXING VALVE: WATTS MODEL LFUSG-B UNDER SINK
P4	SINK	ELKAY	LRAD191865	CHICAGO FAUCETS	895-317GN2AE72ABCP	0.5 GPM DOUBLE COMPARTMENT, 22" X 19-1/2" X 6"DEEP, 3-HOLE, 18 GA. TYPE 304 STAINLESS STEEL FAUCET, 8"CENTERS, CONVERTIBLE RIGID/SWING SPOUT, POLISHED CHROME, LAMINAR FLOW CONTROL, ANTIMICROBIAL METAL WRIST BLADE HANDLES, AERATOR: ELKAY E7JKAACP
P5	SERVICE SINK	FIAT PRODUCTS	TSB3012	CHICAGO FAUCETS	897-CCP	8 GPM WALL MOUNTED SERVICE FAUCET 42" ABOVE FLOOR, CHROME PLATED WITH VACUUM BREAKER, INTEGRAL STOPS, ADJUSTABLE WALL BRACE, TAIL HOOK AND 3/4" HOSE THREAD ON SPOUT, PROVIDE: INTEGRAL STAINLESS STEEL STRAINER DRAIN, 3" CAST IRON P-TRAP, HOSE AND BRACKET, 30" LONG FLEXIBLE HEAVY DUTY 5/8" RUBBER HOSE, MFG: FIAT No. 852 AA, MOP BRACKET, 24" LONG x 3" WIDE, STAINLESS STEEL WITH THREE RUBBER GRIPS, MFG: FIAT No. 889 CC
P6	DRINKING FOUNTAIN W/BOTTLE FILLER (BARRIER FREE)	HALSEY TAYLOR	HTHB-HRFSEBP-I	-	-	8 GPH WALL MOUNT, ADA COMPLIANT, HYDRO-BOOST BOTTLE FILLING STATION WITH TWO FACE MOUNTED FOUNTAINS, ONE PIECE, STAINLESS STEEL, BRUSHED SATIN FINISHED, SENSOR ACTIVATED BOTTLE FILLING STATION, AUTOMATIC 20 SECOND SHUT OFF TIMER, INTERFACE GRAPHICS.
P7	SHOWER	BUILT-UP ENCLOSURE PER ARCHITECT'S SPECIFICATIONS, SHOWER TRIM AS SPECIFIED	-	DELTA	8375EP15	1.5 GPM NON-ADA
P7a	SHOWER (BARRIER FREE)	BUILT-UP ENCLOSURE PER ARCHITECT'S SPECIFICATIONS, SHOWER TRIM AS SPECIFIED	-	DELTA	8342EP15	1.5 GPM ADA WITH GRAB BARS
P8	WATER HAMMER ARRESTOR	PRECISION PLUMBING PRODUCTS	-	-	-	- 0 TO 200 PSIG MAX. OPERATING PRESSURE, 1-11 FXTURE UNITS
P10	WALL HYDRANT	ZURN	Z1320-EZ	-	-	- FREEZE-PROOF, INTEGRAL VACUUM BREAKER, WITH LOOSE-KEY, LOCKABLE DOOR, 3/4" INLET AND 3/4" GARDEN HOSE OUTLET
P11	SUPPLY BOX	GUY GRAY	MIB1AB	-	-	- VALVE: COMPRESSION ANGLE VALVE 1/2" FIP INLETx1/4" OUTLET
P12	WASHER ROUGH-IN BOX	IPS MODEL	W4700HA	-	-	- CENTER DRAIN, BRASS 1/4 TURN VALVES WITH WATER HAMMER ARRESTERS, FRAME ACCOMMODATES UP TO 1" DRYWALL, BOTTOM OUTLET

PLUMBING ROUGH-IN SCHEDULE						
REFER TO DIVISION 22 4000 FOR ADDITIONAL INFORMATION						
SYMBOL	FIXTURE	ROUGH-IN SIZE			VENT	TRAP
		CW	HW	SAN / WASTE		
P1	WATER CLOSET - WALL MTD. - FLUSH VALVE MANUAL - WATERSENSE	1"	-	4"	2"	INTEGRAL
P1a	WATER CLOSET (BARRIER FREE) - WALL MTD. - FLUSH VALVE MANUAL - WATERSENSE	1"	-	4"	2"	INTEGRAL
P1e	WATER CLOSET - FLOOR MTD. - FLUSH TANK	1/2"	-	4"	2"	INTEGRAL
P2a	URINAL (BARRIER FREE) - WALL MTD. - FLUSH VALVE MANUAL - WATERSENSE	3/4"	-	2"	2"	INTEGRAL
P3	LAVATORY - WALL MOUNT - MANUAL	1/2"	1/2"	2"	2"	1-1/4" X 1-1/2"
P3a	LAVATORY (BARRIER FREE) - WALL MOUNT - MANUAL	1/2"	1/2"	2"	2"	1-1/4" X 1-1/2"
P3e	LAVATORY (BARRIER FREE) COUNTER TOP - ROUND - MANUAL	1/2"	1/2"	2"	1-1/2"	1-1/4" X 1-1/2"
P4	SINK	1/2"	1/2"	2"	2"	1-1/4" X 1-1/2"
P5	SERVICE SINK	1/2"	1/2"	3"	2"	3"
P6	DRINKING FOUNTAIN W/BOTTLE FILLER (BARRIER FREE)	1/2"	-	2"	2"	1-1/4" X 1-1/2"
P7	SHOWER	1/2"	1/2"	2"	2"	2"
P7a	SHOWER (BARRIER FREE)	1/2"	1/2"	2"	2"	2"
P8	WATER HAMMER ARRESTOR	1/2"	-	-	-	-
P10	WALL HYDRANT	3/4"	-	-	-	-
P11	SUPPLY BOX	1/2"	-	-	-	-
P12	WASHER ROUGH-IN BOX	1/2"	1/2"	2"	2"	2"

FLOOR/ROOF DRAIN SCHEDULE				
REFER TO DIVISION 22 4000 FOR ADDITIONAL INFORMATION				
SYMBOL	MANUFACTURER	MODEL	VENT	REMARKS:
FD1	ZURN	Z-415-B-VP-Z1000.	2"	7" DIAMETER, ROUND TYPE "B" STRAINER, POLISHED BRONZE, CAST IRON BODY WITH BOTTOM OUTLET, COMBINATION INVERTABLE MEMBRANE CLAMP, DEEP SEAL P-TRAP, VANDAL-PROOF SECURED TOP, DIAMETER OF OUTLET AS SHOWN ON DRAWINGS, PROVIDE WITH SURE SEAL IN-LINE TRAP SEAL, SIZE AND TYPE TO FIT DRAIN
2"FD2	JAY. R. SMITH	2015	2"	SHOWER DRAIN, ROUND TOP, 5" DIAMETER, DUCO CAST IRON BODY WITH FLASHING COLLAR, VANDAL-PROOF SECURED TOP, DIAMETER OF OUTLET AS SHOWN ON DRAWINGS, PROVIDE WITH SURE SEAL IN-LINE TRAP SEAL, SIZE AND TYPE TO FIT DRAIN, CAST IRON BODY WITH WHITE ACID RESISTING ENAMEL BODY INTERIOR, SLOTTED 3/4 LOOSE SET GRATE, ALUMINUM ANTI-SPASH DOME STRAINER, (DEEP SEAL P-TRAP MFG: ZURN Z1000), DIAMETER OF OUTLET AS SHOWN ON DRAWINGS, PROVIDE WITH SURE SEAL IN-LINE TRAP SEAL, SIZE AND TYPE TO FIT DRAIN, NO-HUB OUTLETS, SIZE AS INDICATED ON PLANS
FS1	ZURN	Z-1900	2"	
RD1	ZURN	Z100	-	

fbt

architects

MAIL: 6501 Americas Play NE, Ste. 300
Albuquerque, NM 87110

PHO: 505.883.6200

FAX: 505.884.6290

WEB: www.fbtarch.com

CONSULTANT

B

BRIDGERS & PAXTON

4600 C Montgomery Blvd. NE
Albuquerque, NM 87109 | 505.883.4111 | www.bpcce.com

NAVID ZHIAN

REGISTERED PROFESSIONAL ENGINEER

24274

Seal of the State of New Mexico

Dzilth-Na-O-Dith-Hle - New Dormitory Building

CONSTRUCTION DOCUMENTS

35 Road 7585, Bloomfield, NM 87413

DECEMBER 4, 2020

MARK	DATE	DESCRIPTION
ISSUE:		
DATE:		
PROJECT NO:		
CAD DWG FILE:		
DRAWN BY:		
CHECKED BY:		
SHEET TITLE		
PLUMBING SCHEDULES		
P-701		

WATER HEATER SCHEDULE																			
SYMBOL	MANUFACTURER	MODEL NO.	LOCATION	SERVICE	TYPE	SET POINT (DEGREES)	FUEL	EFFICIENCY	STORAGE VOLUME (GAL.)	INPUT (BTUH)	ELEVATION	OPERATION WEIGHT	ELECTRICAL				HOT WATER RECOVERY		REMARKS:
													V	PH	HZ	FLA	RATE (GPH)	Δ T °F	
DWH-3	LOCHINVAR	AWN200PM	MECH 228	DORM DHW	CONDENSING/ DIRECT VENT	140°F	NATURAL GAS	96%	1.8	199,900	5,463	196 LBS.	120	1	60	4.7	232	100	STAINLESS STEEL HEAT EXCHANGER, 5:1 TURN DOWN RATIO, PROVIDE CONDENSATE NEUTRALIZATION KIT, DISCHARGE FULL SIZE RELIEF VALVE TO FLOOR SINK, DIRECT VENT.
DWH-4	LOCHINVAR	AWN200PM	MECH 228	DORM DHW	CONDENSING/ DIRECT VENT	140°F	NATURAL GAS	96%	1.8	199,900	5,463	196 LBS.	120	1	60	4.7	232	100	STAINLESS STEEL HEAT EXCHANGER, 5:1 TURN DOWN RATIO, PROVIDE CONDENSATE NEUTRALIZATION KIT, DISCHARGE FULL SIZE RELIEF VALVE TO FLOOR SINK, DIRECT VENT.

HOT WATER GPH COUNT ASHRAE 2018 HVAC Applications - 50.20 - Table 10			
DEMAND = APARTMENT			
FIXTURE	# OF FIXTURES	GPH	TOTAL (# OF FIXTURES X GPH)
CLOTHES WASHER	5	40	200
LAVATORY	15	4	60
SERVICE SINK	3	20	60
SHOWER (# X GPM X MINS)	15	0	0
SINK	3	10	30
TOTAL GPH:			350

NATURAL GAS - WATER HEATER SIZING - ASHRAE 2015 HVAC Applications - Chapter 50.20 - APARTMENT																			
Apt. Probable Max Demand (PMD) x TOTAL GPH = Apt. Recovery Rate (GPH)			NOTE: showers calculated separate (Amount x GPM Per Shower Head x Minutes) = Shower Demand GPH				Apt. Recovery Rate + SHW (GPH)	EMERGENCY SHOWER DEMAND (GALS) 20 gpm x 15 mins = 300 gph x 50% ratio	<u>Apt. Recovery Rate + Shower GPH = TOTAL RECOVERY RATE (GPH)</u>	Storage Factor X TOTAL RECOVERY RATE		TOTAL RECOVERY RATE (GPH) x Δ T x (H2O/Eff) = btuh Recovery Rate (no elevation)				EQUIPMENT DERATED OVER 4000 FT.			<u>Recovery Rate (BTUH) + ELEVATION (BTUH) = TOTAL BTUH REQUIRED</u>
Apt. DEMAND	TOTAL GPH	<u>Apt. Recovery Rate (GPH)</u>	AMOUNT OF SHOWERS	GPM PER SHOWER HEAD	MINUTES	SHOWER DEMAND (GPH)				Apartment STORAGE FACTOR	<u>STORAGE (GALS.)</u>	<u>Δ T Rise (°F)</u>	H2O Weight (lb.)	Water Heater Efficiency (Eff)	Recovery Rate (BTUH)	<u>ELEV (°F)</u>	DERATION (Elev/1000) x 0.04%	ELEVATION (BTUH)	
0.30	350	105	15	1.5	10	225	330	0	330	1.25	413	8.3	0.95	289,358	5,312	0.212	61,483	350,841	

SYMBOL	MANUFACTURER	MODEL NO.	LOCATION	SERVICE	TYPE	CAPACITY		PUMP (RPM)	MOTOR (HP)	ELECTRICAL				REMARKS:
						GPM	TOTAL FT. HD.			V	PH	HZ	FLA	
RCP-5	BELL & GOSSETT	ecocirc XL N 20-35	MECH 137	DHW	IN-LINE	5	10	2650	1/12	120	1	60	1.4	LEAD FREE
RCP-6	LOCHINVAR	WA125	MECH 137	DHW	IN-LINE	5	8	-	1/6	120	1	60	2	RECIRCULATION PUMP BETWEEN WATER HEATER AND STORAGE TANK, REFER TO MANUFACTURER FOR ADDITIONAL PUMP INFORMATION.
RCP-7	LOCHINVAR	WA125	MECH 137	DHW	IN-LINE	5	8	-	1/6	120	1	60	2	RECIRCULATION PUMP BETWEEN WATER HEATER AND STORAGE TANK, REFER TO MANUFACTURER FOR ADDITIONAL PUMP INFORMATION.

THERMOSTATIC MIXING VALVE SCHEDULE														
SYMBOL	MANUFACTURER	MODEL NO.	LOCATION	SERVICE	OUTLET TEMPERATURE	INLET PIPE SIZE	OUTLET PIPE SIZE	RETURN PIPE SIZE	SYSTEM FLOW & PRESSURE DROP	ELECTRICAL				REMARKS:
										V	PH	HZ	FLA	
TMV-3 DORM	LEONARD	PNV-125-LF-IF-RTS	MECH 228	DORM DHW	110	1-1/2"	1-1/2"	3/4"	31 GPM @ 4 PSI	120	1	60	2	LEAD FREE, DIGITAL MIXING VALVE, 6 FOOT POWER CORD UL LISTED

EXPANSION TANK SCHEDULE									
SYMBOL	MANUFACTURER	MODEL NO.	SERVICE	DESIGN DEG °F	TANK VOLUME (GAL.)	TANK ACCEPTANCE (GAL.)	PSIG	WEIGHT (LBS.)	REMARKS:
EXP-2	LOCHINVAR	LTCPA5	DORM DHW	140	3.5	2.3	150	22	IN-LINE, COORDINATE LOCATION WITH MANUFACTURER RECOMMENDATIONS AND WITH WATER HEATERS AND STORAGE TANK, 3/4" CONNECTION

WATER HEATER STORAGE TANK SCHEDULE							
SYMBOL	MANUFACTURER	MODEL NO.	SERVICE	PSI	TANK VOLUME (GAL.)	TANK DIMENSIONS	REMARKS:
ST-2	LOCHINVAR	RGAD0318	DORM DHW	150	318	40" DIAMETER X 80" HIGH	JACKED ASME, VERTICAL, 5 YEAR WARRANTY, 3" NPT, 2" OUTLET, 1-1/4" T&P CONNECTION.

LINT INTERCEPTOR SCHEDULE									
SYMBOL	MANUFACTURER	MODEL NO.	LOCATION	SERVICE	TYPE	PDI RATING (GPM)	DIMENSIONS	REMARKS:	
LI-1	JAY, R. SMITH	8910-100	LNEN CLOSET 105A	WASHING MACHINES	IN-LINE	100	48"L X 30"W X 32"H	FABRICATED STEEL WITH GRAY DUCO COATING AND STAINLESS STEEL PRIMARY AND SECONDARY LINT SCREENS, 3/16" DIAMOND PLATE COVER AND THREADED 4"INLET AND 4"OUTLET.	

DOMESTIC HW BALANCING VALVES SCHEDULE													
SYMBOL	MANUFACTURER	MODEL	BLDG	FLOOR	AREA SERVED	ASSOCIATED TMV	DESIGN FLOW (GPM)	CIRCUIT SOLVER			BALANCE VALVE SIZE (in)	PIPE AND OTHER COMPONENTS (in)	SET POINT TEMP (°F)
								CV		SIZE (in)			
OPEN	CLOSED	SIZE (in)											
CS-1(DORM)	THERM-OMEGA-TECH	CSUA-3/4-110-CV1	DORM	1ST	WHOLE DORM	TMV-3 DORM	5	1.8	0.2	2.0	8.9	3/4" CHECK VALVE	110

PLUMBING BACKFLOW SCHEDULE									
SYMBOL	MANUFACTURER	MODEL	LOCATION	SERVICE	TYPE	PIPE SIZE (INCHES)	FLOW (GPM)	PSI LOSS	REMARKS:
RPZ-4	FEBCO	LF860	DORM PENTHOUSE	MECH MAKE-UP	HORIZONTAL IN-LINE	3/4	5	10	LEAD FREE, REDUCED PRESSURE ZONE ASSEMBLIES
RPZ-5	FEBCO	LF860	MECH 228	IRRIGATION	HORIZONTAL IN-LINE	1-1/2	10	10	LEAD FREE, REDUCED PRESSURE ZONE ASSEMBLIES

PLUMBING MISC. EQUIPMENT SCHEDULE							
SYMBOL	MANUFACTURER	MODEL NO.	LOCATION	SERVICE	PIPE SIZE	PSI	REMARKS:
GM-2	-	-	SITE	NAT GAS BLDG	-	HIGH	GAS METER PROVIDED BY UTILITY COMPANY. PROVIDE REGULATORS AND REGULATE INCOMING HIGH PRESSURE GAS DOWN TO 2 PSI. REFER TO NATURAL GAS SIZING CRITERIA ON DORM DRAWING P-702 FOR NEW CLASSROOM BUILDING CFH LOAD
REG-7	-	-	SITE	NAT GAS BLDG	-	HIGH	GAS REGULATOR PROVIDED BY UTILITY COMPANY. PROVIDE REGULATORS AND REGULATE INCOMING HIGH PRESSURE GAS DOWN TO 2 PSI. REFER TO NATURAL GAS SIZING CRITERIA ON DORM DRAWING P-702 FOR NEW CLASSROOM BUILDING CFH LOAD
REG-8	AMERICAN METER	2" #1813B	SITE	NAT GAS BLDG	1"	2 PSI	2,047 CFH
REG-9	AMERICAN METER	1" #1813B	MECH 228	DWHS NAT GAS	2"	14"wc	512 CFH
REG-10	AMERICAN METER	2" #1813B	MECH 228	BOILERS NAT GAS	2"	14"wc	1,536 CFH

ROOF DRAIN CALCULATION										
Instance Name	SYMBOL	Rain Fall Rate Per Hr (INCHES)	SLOPE	Roof Sq. Ft.	PARAPET/ VERTICAL WALL	Parapet Or Vertical Wall Sq. Ft. divided by 2	UPPER ROOF Sq. Ft.	TOTAL ROOF Sq. Ft.	GPM	LEADER OUTLET SIZE (INCHES)
ROOF DRAIN A	RD1	2	1/8" / 12"	2656	335	167.5	0	2823.5	59	4
ROOF DRAIN C	RD1	2	1/8" / 12"	1394	455	227.5	846	2467.5	51	4
ROOF DRAIN D	RD1	2	1/8" / 12"	1600	93	46.5	180	1826.5	38	4
ROOF DRAIN F	RD1	2	1/8" / 12"	1600	70	35	180	1815	38	4
ROOF DRAIN G	RD1	2	1/8" / 12"	1002	56	28	175	1205	25	3
ROOF DRAIN H	RD1	2	1/8" / 12"	3670	55	27.5	139	3836.5	80	6

NATURAL GAS SIZING CRITERIA						
TOTAL LENGTH = 43 FEET X 1.3 (FOR MISC. FITTINGS) = "TDL" TOTAL DEVELOPED LENGTH (TDL) = 50 FEET				PIPING SIZED PER CHAPTER 4 OF THE 2015 INTERNATIONAL FUEL GAS CODE		
GAS PRESSURE LEAVING REGULATOR = 2 psi (Note Equipment Regulators leaving at 14" wc)						
NATURAL GAS DEMAND LOAD						
SYMBOL	QUANTITY	INPUT BTU/H	ELEVATION	MBH	MBH PER CFH	CFH
DWH-3	1	199,900	5,463	200	0.781	256
DWH-4	1	199,900	5,463	200	0.781	256
B-1	1	600,000	5,463	600	0.781	768
B-2	1	600,000	5,463	600	0.781	768
Total DESIGN LOAD:		1,599,800		1,600		2,047

SANITARY PIPE SIZE (2015 UPC)		DHW PIPE SIZE (UPC @ 4 FPS)		
TOTAL DFU	PIPE SIZE @ 1/8" SLOPE (INCH)	TOTAL DHWFU	GPM	PIPE SIZE (INCH)
246	6	55.53	32	1.5

ENTIRE DORMITORY FIXTURE UNITS (2015 UPC)									
Note: SEE SEPARATE SANITARY EXITS, DOMESTIC COLD WATER ENTRY AND HOT WATER DEMAND SCHEDULE IF BUILDING REQUIRES SEPARATE DEMANDS									
FIXTURE	QUANTITY	SANITARY		DOMESTIC COLD WATER		TOTAL WATER SUPPLY		DOMESTIC HOT WATER	
		DFU	TOTAL DFU	DCWFU	TOTAL DCWFU	WSFU	TOTAL WSFU	DHWFU	TOTAL DHWFU
WATER CLOSET	11	4	44	5	55	5	55	0	0
WATER CLOSET - TANK TYPE	4	4	16	2.5	10	2.5	10	0	0
URINAL	2	2	4	4	8	4	8	0	0
LAVATORY	15	1	15	0.75	11.25	1	15	0.75	11.25
SINK	3	2	6	1.13	3.39	1.5	4.5	1.13	3.39
SERVICE SINK	3	3	9	2.25	6.75	3	9	1.13	3.39
DRINKING FOUNTAIN	2	1	1	0.5	1	0.5	1	0	0
SHOWER	15	0	0	1.5	22.5	2	30	1.5	22.5
WALL HYDRANT	7	0	0	0.5	3.5	0.75	5.25	0	0
SUPPLY BOX	1	0	0	0.5	0.5	0.5	0.5	0	0
WASHER ROUGH-IN BOX	5	3	15	3	15	4	20	3	15
FLOOR DRAIN (3" TRAP)	6	6	36	0	0	0	0	0	0
FLOOR DRAIN (4" TRAP)	1	8	8	0	0	0	0	0	0
SHOWER DRAIN (2" TRAP)	15	4	60	0	0	0	0	0	0
FLOOR SINK (4" TRAP)	4	8	32	0	0	0	0	0	0
Fixture Unit Totals:			246		136.89		158.25		55.53

ENTIRE DCW FLUSH VALVE DEMAND (UPC @ 5 FPS)					
DCWFU	DCWFU TO (GPM)	DCW PIPE SIZE (INCH)	WSFU TOTAL	WSFU TO (GPM)	ENTRY PIPE SIZE (INCH)
126.89	77	2.5	148.25	81	2.5

MARK	DATE	DESCRIPTION
	11/17/20	Addendum Changes
ISSUE:		
DATE:		
PROJECT NO:		751
CAD DWG FILE:		
DRAWN BY:		AJM/SNB
CHECKED BY:		NZ


TEST DATE:	04/28/2020
TEST LOCATION:	Residential at Main Entrance
WATER PRESSURE ZONE:	XX - XXXX
TEST ELEVATION:	5463' MSL
REQUESTED LOADING:	500 GPM
(IF MODELED BY THE MUNICIPALITY)	
PEAK STATIC PRESSURE:	56 PSI
RESIDUAL PRESSURE:	51 PSI
FLOWING GPM:	2860 GPM @ 20 psi
(IF NOT MODELED BY THE MUNICIPALITY)	


$$1/8" = 1'-0"$$

0' 4' 8' 16'

1. REFER TO CIVIL DRAWING C105 FOR CONTINUATION OF SERVICES.
2. LOCATIONS AND SIZING BY FIRE PROTECTION CONTRACTOR SYSTEM SHALL BE HYDRAULICALLY CALCULATED AND DESIGNED TO LATEST APPLICABLE NFPA & IBC. ALL ROOMS SHALL BE PROTECTED.
3. MOST REMOTE HEAD.
4. REFER TO FIRE RISER DETAIL A5/FX501 FOR ADDITIONAL INFORMATION.
5. REFER TO FIRE ENTRY DETAIL C4/FX501 FOR ADDITIONAL INFORMATION.
6. INSPECTOR'S TEST VALVE. TERMINATE IN ACCORDANCE WITH NFPA-13. REFER TO TEST C5P-601.
7. PROVIDE ORDINARY HAZARD GROUP I COVERAGE AT DESIGN DENSITY 0.15 GPM/ 1500 SQ. FT.
8. PROVIDE HORIZONTAL DRY PRE-CHARGED SIDEWALL SPRINKLERS BELOW CANOPY.
9. SPRINKLER HEADS IN THIS AREA SHALL BE CUSTOMIZED AT FACTORY WITH CUSTOM PAINT CODE.
10. 2" MAIN DRAIN DISCHARGED TO GRADE IN A CODE COMPLIANT MANNER. COORDINATE WITH LANDSCAPE DESIGNER FOR EROSION CONTROL.
11. FIRE PROTECTION UP TO DORM PENTHOUSE. COORDINATE WITH OTHER TRADES. SERVED FROM WET RISER #1.

FX-101



GENERAL NOTES

- A. THE CONTRACTOR SHALL COMPLY WITH NFPA-13 AND REQUIREMENTS OF THE AHJ.
- B. THE CONTRACTOR SHALL SUBMIT SHOP DRAWINGS TO THE ARCHITECT/ENGINEER FOR APPROVAL PRIOR TO COMMENCING WORK.
- C. ALL EQUIPMENT AND MATERIALS SHALL CONFORM TO NFPA STANDARDS AND BE UL LISTED.
- D. SPRINKLER SYSTEMS SHALL BE DESIGNED FOR LIGHT HAZARD WITH DESIGN DENSITY OF 0.10 GPM / 1500 SQ.FT. THROUGHOUT ENTIRE BUILDING UNLESS NOTED OTHERWISE.
- E. MAXIMUM SPRINKLER HEAD COVERAGE SHALL BE 225 SQ.FT. PER HEAD IN LIGHT HAZARD AREAS.
- F. THE CONTRACTOR SHALL COORDINATE THEIR WORK WITH THE MECHANICAL, PLUMBING, AND ELECTRICAL PRIOR TO FABRICATION AND DURING INSTALLATION.
- G. THE CONTRACTOR SHALL SUPPLY AND INSTALL AN INSPECTOR'S TEST CONNECTION (ITC) FOR EACH SPRINKLER SYSTEM. RUN THROUGH EXTERIOR WALLS WHERE APPROVED BY ARCHITECT / ENGINEER.
- H. THE ARCHITECT SHALL APPROVE THE AESTHETICS OF THE SPRINKLER HEADS AND EXPOSED PIPING LAYOUT.
- I. PROVIDE PENDANT AND UPRIGHT SPRINKLERS IN ALL CONCEALED COMBUSTIBLE SPACES.
- J. USE FLUSH CONCEALED HEADS IN ALL TOILET ROOMS. PROVIDE SPRINKLERS UNDER EXPOSED DUCT OR OBSTRUCTIONS 48" WIDE AND LARGER.
- K. REFER TO CEILING TILE DETAIL D4FX-501 FOR SPRINKLER HEAD LOCATIONS IN CEILING TILES.
- L. PROVIDE SIDEWALL SPRINKLER HEADS AT TOP OF SKYLIGHTS.
- M. REFER TO NFPA APPENDIX FOR ALL APPROPRIATE HAZARD CLASSIFICATION ASSIGNMENTS FOR BUILDING SPACES. MORE STRINGENT CLASSIFICATION SHALL APPLY.

KEYNOTES

- 1. PROVIDE ORDINARY HAZARD GROUP I COVERAGE AT DESIGN DENSITY 0.15 GPM / 1500 SQ. FT.
- 2. FIRE PROTECTION UP FROM BELOW. COORDINATE WITH OTHER TRADES. SERVED FROM WET RISER #1.

fbt | architects


MAIL: 6501 Americas Pkwy NE, Ste. 300
Albuquerque, NM 87110

PHO: 505.883.6200
FAX: 505.884.6290
WEB: www.fbtarch.com

CONSULTANT

BRIDGERS & PAXTON

4600 C Montgomery Blvd. NE
Albuquerque, NM 87109 | 505.883.4111 | www.bpcce.com



Dzilth-Na-O-Dith-Hle - New Dormitory Building

CONSTRUCTION DOCUMENTS

35 Road 7585, Bloomfield, NM 87413

DECEMBER 4, 2020

MARK	DATE	DESCRIPTION
	11/17/20	Addendum Changes
ISSUE:		
DATE:		
PROJECT NO:		751
CAD DWG FILE:		
DRAWN BY:		AJM/SNB
CHECKED BY:		NZ

SHEET TITLE

FIRE PROTECTION ROOF PLAN

FX-131

CONSULTANT

DECEMBER 4, 2020


MARK	DATE	DESCRIPTION
------	------	-------------

ISSUE:	
DATE:	
PROJECT NO:	751
CAD DWG FILE:	
DRAWN BY:	AJM/SNB
CHECKED BY:	NZ

SHEET TITLE


FIRE PROTECTION DETAILS

FX501



D5 FIRE SPRINKLER CEILING TILE DETAIL

SCALE: NOT TO SCALE



- 1

AMES IN-BUILDING RISER, STAINLESS STEEL TYPE 304. SEE PLANS FOR SIZE AND SERVICE
- 2

DUCTILE IRON OR PVC WATER SERVICE.
- 3

MECHANICAL JOINT FROM SUPPLY PIPE TO STAINLESS STEEL, CONTINUE INTO BUILDING WITH STAINLESS STEEL.

4

CONCRETE THRUST BLOCK SIZED IN ACCORDANCE WITH IBC IF REQUIRED BY AHJ

5

PIPE SLEEVE, SEE SPECIFICATIONS

6


MEGALUG PIPE RESTRAINT HARNESS

7

VERTICAL SECTION OF RISER LOCATED AS CLOSE AS POSSIBLE TO WALL

C4 WATER ENTRY THRU FOOTING DETAIL

SCALE: NOT TO SCALE



- 1

EXTERIOR WALL
- 2

1" SUPPLY FROM SPRINKLER SYSTEM ZONE
- 3

1" TEST & DRAIN VALVE WITH SIGNAGE (NORMALLY CLOSED) AT 9'-0" AFF.
- 4

MOST REMOTE HEAD

5

1" GALVANIZED WALL PLATE TO COVER EXISTING OPENING

6


1" GALVANIZED 45 DEGREE ELBOW

7

SMOOTH BORE CORROSION RESISTANT OUTLET WITH FLOW EQUAL TO ONE SPRINKLER WITH SMALLEST ORIFICE

C5 INSPECTORS TEST DRAIN VALVE

SCALE: NOT TO SCALE



- 1

RETARDING CHAMBER
- 2

ELECTRIC ALARM LOCATED 8'-0" AFG & ADJACENT TO SIAMESE FIRE DEPARTMENT INLET CONNECTION
- 3

AUTOMATIC DRIP
- 4

RESTRICTED VENT
- 5

DRIP CUP W/DRAIN LINE TO EXTERIOR DISCHARGE
- 6

ALARM SWITCH
- 7

TO SPRINKLER SYSTEM
- 8

WATER PRESSURE GAUGE
- 9

ALARM SHUT-OFF VALVE & CHECK VALVE (NORMALLY OPEN)
- 10

ALARM TEST VALVE (NORMALLY CLOSED)

11

FROM FIRE DEPT. CONNECTION

12

FULL SIZED MAIN DRAIN VALVE

13

TO EXTERIOR DISCHARGE

14

FROM FIRE PROTECTION MAIN SUPPLY LINE

15

ALARM CHECK VALVE

16

INDICATING BUTTERFLY VALVE, USED FOR FORWARD FLOW TEST (NORMALLY CLOSED)

17

WAFFER CHECK VALVE

18


FLOW SWITCH

19

INDICATING BUTTERFLY VALVE

A5 SPRINKLER ALARM VALVE

SCALE: NOT TO SCALE



A1 FIRE PROTECTION DIAGRAM

SCALE: NOT TO SCALE


NOTE: NOT ALL ABBREVIATIONS OR SYMBOLS APPLY TO THIS PROJECT

<p>A. ALL PIPING AND DUCTS IN FINISHED ROOMS OR SPACES SHALL BE CONCEALED IN FURRED CHANNELS OR SUSPENDED CEILINGS, UNLESS OTHERWISE NOTED.</p>	<p>H. PROVIDE TURNING VANES IN ALL SQUARE ELBOWS, EXCEPT TRANSFER AIR SOUND ELBOWS.</p>	<p>M. CONTRACTOR SHALL PROVIDE RETURN AIR OR TRANSFER AIR OPENINGS IN FULL HEIGHT WALLS SIZED AT 350 FPM (UNLESS OTHERWISE SPECIFICALLY SHOWN ON THE DRAWINGS) TO CREATE AND/OR MAINTAIN A RETURN AIR PATH AS REQUIRED. FIRE DAMPERS AND/OR SMOKE DAMPERS SHALL BE PROVIDED IN SUCH OPENINGS WHERE REQUIRED BY NOTE "J".</p>
<p>B. PROVIDE ACCESS PANELS OR DOORS IN INACCESSIBLE CEILINGS AND/OR CHASES FOR ALL VALVES, TRAPS, DAMPERS, CLEANOUTS, COILS, FANS, CONTROLS, ETC. TO BE FURNISHED UNDER THE ARCHITECT'S RATING. ACCESS DOOR RATING SHALL MATCH CLASSIFICATION OF WALL AND CEILING FIRE RATING.</p>	<p>I. REFER TO THE ARCHITECTURAL DRAWINGS FOR EXACT LOCATION OF ALL FIRE RATED AND/OR SMOKE RATED WALLS AND ASSEMBLIES. PROVIDE APPROVED FIRE DAMPERS IN ALL REQUIRED PENETRATIONS FOR DUCTWORK, GRILLES, REGISTERS AND DIFFUSERS. ALL PIPE AND DUCTWORK PENETRATIONS OF FIRE, SMOKE AND FULL HEIGHT WALLS SHALL BE CALKED AIRTIGHT TO THE ADJACENT STRUCTURE BY MEANS OF U.L. APPROVED FIRE PROOF CALKING MATERIAL.</p>	<p>N. SEAL ALL TRANSVERSE JOINTS, LONGITUDINAL SEAMS, DUCT WALL PENETRATIONS AND FITTING CONNECTIONS ON ALL DUCT SYSTEMS.</p>
<p>C. WATER PIPE CONNECTIONS TO WATER COILS SHALL BE MADE SO THERE WILL BE COUNTER FLOW BETWEEN WATER AND AIR.</p>	<p>J. CONTRACTOR SHALL COORDINATE ALL DUCTWORK, PIPING, PLUMBING AND FIRE PROTECTION PIPING WITH STRUCTURAL AND ELECTRICAL SYSTEMS AND SHALL PROVIDE NECESSARY OFFSETS TO AVOID CONFLICTS AND TO MAINTAIN EQUIPMENT ACCESS AND SERVICEABILITY.</p>	<p>O. MECHANICAL ITEMS SUCH AS ROOF DRAINS, FLOOR DRAINS, PLUMBING FIXTURES, ETC. SHOWN ON THE ARCHITECTURAL DRAWINGS BUT NOT SHOWN ON THE MECHANICAL DRAWINGS SHALL BE INCLUDED IN THE PROJECT. THESE ITEMS SHALL BE BROUGHT TO THE ATTENTION OF THE ARCHITECT FOR INCLUSION IN ADDENDUM.</p>
<p>D. COORDINATE THE LOCATION OF ALL DIFFUSERS, GRILLES, REGISTERS, ACCESS PANELS, ETC. WITH THE ARCHITECTURAL DRAWINGS (FLOOR PLANS).</p>	<p>K. CONTRACTOR SHALL FURNISH ALL NECESSARY STRUCTURES, INSERTS, SLEEVES, AND HANGING DEVICES FOR INSTALLATION OF MECHANICAL AND PLUMBING EQUIPMENT, DUCTWORK AND PIPING, ETC. CONTRACTOR SHALL COORDINATE WITH GENERAL CONTRACTOR AND ALL BUILDING TRADES TO AVOID CONFLICTS AND TO MAINTAIN EQUIPMENT ACCESS AND SERVICEABILITY.</p>	
<p>E. ALL ROUND RUNOUTS AND DROPS TO DIFFUSERS SHALL BE THE SAME NOMINAL SIZE AS THE SCHEDULED DIFFUSER NECK SIZE.</p>	<p>L. CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING ALL NECESSARY MISCELLANEOUS ANGLES, CHANNELS, UNISTRUT, ETC. AS MAY BE REQUIRED TO ADEQUATELY SUPPORT THE MECHANICAL PIPING, DUCTWORK, AND EQUIPMENT IN A MANNER APPROVED BY THE ARCHITECT, WHICH WILL NOT OVERLOAD THE BUILDING STRUCTURAL SYSTEM.</p>	
<p>F. THE FIRST FIGURE OF DUCT SIZE INDICATES DIMENSION OF FACE SHOWN OR INDICATED. ALL DUCT SIZES SHOWN ON DRAWINGS ARE NET INSIDE DIMENSIONS. PROVIDE ONE INCH ACOUSTICAL LINING (TYPE D3 INSULATION) IN LOW VELOCITY RECTANGULAR DUCTWORK FOR THE FIRST 10 DIAMETERS OF DUCTWORK CONNECTED TO DEVICE, OR AS INDICATED ON DRAWINGS, WHICHEVER IS GREATER. FOR THE REMAINDER OF THIS DUCTWORK PROVIDED AS INDICATED IN THE INSULATION SPECIFICATIONS.</p>		
<p>G. PROVIDE 1/2" MANUAL AIR VENTS AT ALL HIGH POINTS OF CLOSED SYSTEM PIPING AND 1/2" MANUAL DRAIN VALVES WITH HOSE CONNECTION AT LOW POINTS AS REQUIRED TO PROVIDE COMPLETE SYSTEM DRAINAGE. WHERE DRAIN VALVES OCCUR ABOVE CEILING AREAS AND IN AREAS OUTSIDE MECHANICAL RANGE PROVIDE HOSE CONNECTION ON VALVE.</p>		

Diagram illustrating the components of a typical equipment label:

- LETTERS REFER TO THE EQUIPMENT TYPE
- NUMBERS REFER TO SPECIFIC EQUIPMENT
- SYMBOL INDICATES EQUIPMENT IDENTIFIED IN EQUIPMENT SCHEDULE
- SIDEWALL GRILLE DIMENSION WHERE SHOWN ON PLANS
- SYMBOL INDICATES GRILLE OR DIFFUSER IDENTIFIED IN EQUIPMENT SCHEDULE
- CFM

4600 C Montgomery Blvd. NE
Albuquerque, NM 87109 | 505.883.4111 | www.bpce.com



35 Road 7585, Bloomfield, NM
87413

DECEMBER 4, 2020


MARK	DATE	DESCRIPTION
------	------	-------------

ISSUE:	
DATE:	
PROJECT NO:	751
CAD DWG FILE:	
DRAWN BY:	NZ
CHECKED BY:	IM

SHEET TITLE

MECHANICAL LEGEND

M-001



A1 HVAC FLOOR PLAN

1/8" = 1'-0"

0' 4' 8' 16'

GENERAL NOTES

- A. ALL INTERIOR CONCEALED SUPPLY SHALL BE WRAPPED WITH 1.5" TYPE D-1. SEE SPECIFICATION 230700 FOR ADDITIONAL INSULATION INFORMATION.
- B. ALL BRANCH DUCTWORK TO SUPPLY DIFFUSERS SHALL BE SIZED TO MATCH NECK SIZE OF DIFFUSER AS INDICATED ON "GRILLE AND DIFFUSER" SCHEDULE ON SHEET M-702.
- C. ALL BRANCH DUCTWORK TO SUPPLY DIFFUSERS AND EXHAUST GRILLES NOT FURNISHED WITH OPPOSED BLADE DAMPERS SHALL INCLUDE BALANCING DAMPER WITH LOCKING QUADRANT.
- D. COORDINATE ALL DUCT AND PIPE ROUTING AND INSTALLATION WITH STRUCTURAL PLANS AND ARCHITECTURAL FLOOR PLANS.
- E. THERMOSTATS SHALL BE MOUNTED AT 48" A.F.F. ALL THERMOSTATS IN STUDENT AREAS SHALL BE FURNISHED AND INSTALLED WITH METAL LOCKING COVERS.
- F. ALL EXPOSED DUCTWORK AND GRILLES SHALL BE CLEANED, DEGREASED AND PREPPED FOR PAINTING. DUCTWORK SHALL BE PAINTED PER ARCHITECTURAL DRAWINGS AND SPECIFICATIONS.
- G. 24X24 CEILING ACCESS DOORS SHALL BE PROVIDED AT ALL BALANCING DAMPERS, FIRE DAMPERS AND DUCT MOUNTED SMOKE DETECTOR LOCATIONS ABOVE HARD CEILINGS.
- H. SEE SHEETS M-501 TO M-503 FOR MECHANICAL DETAILS.

KEYNOTES

- 1. PROVIDE WALL MOUNTED SPLIT SYSTEM. DRAIN SIZED PER MANUFACTURER'S INSTRUCTIONS. COORDINATE CONDENSATE DRAIN WITH PLUMBING CONTRACTOR. PROVIDE PIPING AS SIZED ON PLAN. VERIFY EXACT PIPE SIZES REQUIRED WITH MANUFACTURER AND TRAP AND SLOPE REFRIGERANT LINES PER MANUFACTURER'S INSTRUCTIONS. CONTRACTOR TO COORDINATE SHORTEST CONCEALED ROUTING TO ASSOCIATED REMOTE CONDENSING UNIT. PROVIDE ALL VALVES AND ACCESSORIES FOR A COMPLETE AND OPERATIONAL SYSTEM. REFER TO DETAILS AND EQUIPMENT SCHEDULE FOR ADDITIONAL INFORMATION.
- 2. 14"x14" EXHAUST DUCT UP TO EF-4 ON THE ROOF.
- 3. 12"x12" EXHAUST DUCT UP TO EF-3 ON THE ROOF.
- 4. 12"x12" EXHAUST DUCT UP TO EF-2 ON THE ROOF.
- 5. 14"x14" EXHAUST DUCT UP TO EF-1 ON THE ROOF.
- 6. 44"x22" SUPPLY DUCT UP TO AHU-1 IN THE PENTHOUSE. SEE SHEET M-401 FOR CONTINUATION.
- 7. INSTALL SMOKE DETECTOR AND SAMPLING TUBES FURNISHED BY DIVISION 28 IN DUCTWORK. POWER AND WIRING BY DIVISION 26 AND DIVISION 28.
- 8. INSTALL STATIC PRESSURE SENSOR FOR SUPPLY FAN CONTROL IN DUCT AT APPROXIMATE LOCATION SHOWN.
- 9. STAINLESS STEEL RESIDENTIAL HOOD (HD-1) MOUNTED 30" - 36" ABOVE COOK TOP. COORDINATE INSTALLATION WITH KITCHEN CABINETS AND DIV 28. INSTALL HOOD AND ASSOCIATED EXHAUST DUCT PER MANUFACTURER'S INSTRUCTIONS. WRAP THE FLUE PER MANUFACTURER'S REQUIREMENT. SEE MECHANICAL SCHEDULE M-702 FOR MORE INFO.
- 10. EXTEND 8" DIA FLUE UP TO THE ROOF. PROVIDE 12"x12" STAINLESS STEEL DUCT COVER. WRAP THE FLUE PER MANUFACTURER'S REQUIREMENT.
- 11. EXTEND 4" VENT UP THRU ROOF AND TERMINATE WITH GOOSENECK. PROVIDE DUCT THRU ROOF CURB. GOOSENECK DISCHARGE SHALL BE APPROX. 24" ABOVE FINISHED ROOF. DRYER VENT DUCTWORK MUST NOT HAVE ANY SCREWS OR OTHER FASTENERS PROJECTING INSIDE THE DUCTWORK. INSTALL PER CODE. COORDINATE EXACT MOUNTING HEIGHT REQUIRED WITH DRYER VENT OUTLET.
- 12. PROVIDE LINEAR DIFFUSER PRICE SCD-100, 300 CFM, 4 FEET, 4 SLOT, 10" DIA INLET, NC-22.
- 13. PROVIDE LINEAR DIFFUSER PRICE SCD-100, 400 CFM, 3 FEET, 4 SLOT, 8" DIA INLET, NC-35.
- 14. 72"x20" RETURN DUCT UP TO AHU-1 IN PENTHOUSE. SEE SHEET M-401 FOR CONTINUATION. PROVIDE 1" LINER ON THE RA DUCT.
- 15. 12"x12" EXHAUST DUCT UP TO EF-5 ON THE ROOF.

CONSULTANT

Dzilth-Na-O-Dith-Hle - New Dormitory Building
CONSTRUCTION DOCUMENTS

35 Road 7585, Bloomfield, NM 87413


DECEMBER 4, 2020

MARK	DATE	DESCRIPTION
	11/17/20	Addendum Changes
ISSUE:		
DATE:		
PROJECT NO:		751
CAD DWG FILE:		NZ
DRAWN BY:		IM
CHECKED BY:		

SHEET TITLE
HVAC FLOOR PLAN


$$1/8'' = 1'-0''$$

MH-131



A1 MECHANICAL HEATING HOT WATER PIPING FLOOR PLAN
1/8" = 1'-0"

0' 4' 8' 16'

GENERAL NOTES

- A. PROVIDE MANUAL AIR VENTS AT ALL HIGH POINTS IN HOT WATER SYSTEM.
- B. PROVIDE DRAINS AT ALL LOW POINTS IN HOT WATER SYSTEM.
- C. SEE PLUMBING SHEETS FOR CONDENSATE DRAIN PIPING.
- D. PROVIDE 2-WAY CONTROL VALVE FOR HOT WATER REHEAT COIL AT TERMINAL UNITS UNLESS OTHERWISE NOTED. SEE TERMINAL UNIT SCHEDULE ON SHEET M-701 FOR GPM & BRANCH SIZES.

KEYNOTES

- 1. ROUTE REFRIGERANT SUCTION AND LIQUID LINES FROM FAN COIL UNIT UP TO CONDENSING UNIT ON THE ROOF. REFER TO SPLIT SYSTEM SCHEDULE ON SHEET M-702 FOR REFRIGERANT PIPE SIZES. REFER TO PLUMBING SHEETS FOR CONDENSATE DRAIN PIPING.
- 2. INDOOR FAN COIL UNIT FURNISHED WITH CONDENSATE PUMP. REFER TO PLUMBING SHEETS FOR CONDENSATE DRAIN.
- 3. SEE SHEET M-401 FOR ENLARGED MECHANICAL PLAN.
- 4. 3" HWS PIPE TO / FROM PENTHOUSE.
- 5. 2" HWR PIPE FROM PENTHOUSE.
- 6. PROVIDE 3-WAY CONTROL VALVE FOR HOT WATER REHEAT COIL AT TERMINAL UNIT. SEE TERMINAL EQUIPMENT SCHEDULE ON SHEET M-701 AND SINGLE DUCT VAV TERMINAL UNIT WITH REHEAT COIL (3-WAY VALVE) DETAIL 1108-5022 FOR PIPING CONFIGURATION.
- 7. DIFFERENTIAL PRESSURE SENSOR CONNECTED TO HWS & HWR PIPES. PUMP SPEED AND HOT WATER SYSTEM FLOW RATE SHALL BE CONTROLLED BASED ON SENSED DIFFERENTIAL PRESSURE AT THIS LOCATION.

CONSULTANT




Dzilth-Na-O-Dith-Hle - New Dormitory Building
CONSTRUCTION DOCUMENTS
35 Road 7585, Bloomfield, NM 87413

DECEMBER 4, 2020


MARK	DATE	DESCRIPTION
	11/17/20	Addendum Changes
ISSUE:		
DATE:		
PROJECT NO:		751
CAD DWG FILE:		
DRAWN BY:		NZ
CHECKED BY:		IM

SHEET TITLE
MECHANICAL PIPING FLOOR PLAN

MP-101




1 MECH ROOM ENLARGED PLAN
1/2" = 1'-0"




2 MECH RM SEC-1
1/2" = 1'-0"


- # KEYNOTES
1. EMERGENCY POWER OFF (EPO) SWITCH REQUIRED AT BOILER EXIST DOOR. COORDINATE WITH DIV. 26. THE EPO SWITCH SHALL DISCONNECT LINE VOLTAGE POWER TO BOILERS. SEE M-701 FOR BOILER INFORMATION.
 2. PROVIDE 4" HOUSEKEEPING PAD BELOW EQUIPMENT.
 3. PRIMARY HOT WATER PUMP (P-1 & P-2) INSTALLED IN VERTICAL SECTION OF HOT WATER RETURN PIPING.
 4. NOT USED.
 5. MOUNT ELECT UNIT HEATER AT 8'-0" AFF. SET THERMOSTAT TO ENERGIZE HEATER AT 60F (ADJUSTABLE).
 6. SEE PLUMBING DRAWINGS FOR DOMESTIC WATER HEATER INFO. COORDINATE VENTING AND PIPING INSTALLATION WITH OTHER TRADES.
 7. SEE PLUMBING DRAWINGS FOR DOMESTIC WATER STORAGE TANK INFO.
 8. PROVIDE DRAIN IN BOTTOM OF FLUE RISER. PIPE DRAIN TO ACID NEUTRALIZATION BOX AND THEN FLOOR DRAIN.
 9. 3" DIA. FLUE AND COMBUSTION AIR DUCT FROM WATER HEATER UP TO THE ROOF. INSTALL PER MANUFACTURER INSTRUCTIONS.
 10. 4" DIA. FLUE AND COMBUSTION AIR DUCT FROM BOILERS UP TO THE ROOF. INSTALL PER MANUFACTURER INSTRUCTIONS.
 11. PROVIDE HYDRAULIC SEPARATOR AT THIS APPROX LOCATION. PROVIDE AUTOMATIC AIR VENT AT TOP OF SEPARATOR. SEE PIPING SCHEMATIC M-601.
 12. CARBON MONOXIDE SENSOR WITH CO PPM LEVEL DISPLAY, ALARM BUILT-IN ARM CONTACTS, AND 4-20 mA OUTPUT. MOUNT SENSOR ON WALL APPROXIMATELY 48" AFF. CONNECT TO NEAREST DDO CONTROLLER. SENSOR SHALL PROVIDE CO LEVEL AND ALARM TO FMS SYSTEM. MACURCO MODEL CM-6 OR EQUIV.
 13. 3" HWS & HWR PIPING TO / FROM BUILDING.
 14. EXPANSION TANK INSTALLED AT LOWEST PRESSURE POINT IN SYSTEM. EXPANSION TANK SHALL BE RECHARGED WITH 15.2 PSIG AIR PRESSURE (ADJUSTABLE). CONNECT MAKEUP WATER PIPING AND EXPANSION PIPING TO HOT WATER SUPPLY AT THIS LOCATION. REFER TO HEATING WATER PIPING SCHEMATIC ON M-480. REFER TO PLUMBING SPECIFICATIONS FOR MAKEUP WATER AND ASSOCIATED REDUCED PRESSURE. BACKFLOW PREVENTER.
 15. FMS (DDO CONTROLS) CONDUIT TO ENTER MECHANICAL ROOM THROUGH WALL AT THIS APPROXIMATE LOCATION.
 16. 14"x8" S.O.F. LOUVER UP AND DOWN. LOUVERS SHALL BE INSTALLED AT 3'-0" F.F.E. & 10'-0" F.F.F.




MARK	DATE	DESCRIPTION
ISSUE:		
DATE:		
PROJECT NO:	751	
CAD DWG FILE:		
DRAWN BY:	NZ	
CHECKED BY:	IM	



1 MECH PENTHOUSE - ENLARGED PLAN
1/2" = 1'-0"



2 MECH PENTHOUSE SEC-1
3/8" = 1'-0"



3 MECH PENTHOUSE SEC-2
3/8" = 1'-0"

KEYNOTES

1. PROVIDE 4" HOUSEKEEPING PAD BELOW EQUIPMENT.
2. ANCHOR SECONDARY HOT WATER PUMP TO HOUSEKEEPING PAD.
3. CHEMICAL POT FEEDER PIPE ACROSS HW'S & HW'R PIPING OF SYSTEM. SEE MECH SCHEDULE FOR ADDITIONAL INFO.
4. NOT USED.
5. VARIABLE FREQUENCY DRIVES FOR SECONDARY HW PUMPS (P-3 & P-4). REFER MECH SCHEDULE FOR ADDITIONAL INFO.
6. MOUNT ELEC UNIT HEATER AT 8'-0" AFF. SET THERMOSTAT TO ENERGIZE HEATER AT 60° (ADJUSTABLE).
7. 86"x40" RELIEF AIR LOUVER.
8. 86"x36" CSA LOUVER.
9. VARIABLE FREQUENCY DRIVES FOR AHU-1 SUPPLY FANS. REFER TO MECH SCHEDULE FOR ADDITIONAL INFO.
10. VARIABLE FREQUENCY DRIVES FOR AHU-1 EXHAUST FANS. REFER MECH SCHEDULE FOR ADDITIONAL INFO.
11. PROVIDE AND INSTALL 3-WAY HOT WATER CONTROL VALVE AND HOT WATER CIRCULATING PUMP AT AHU HEATING COIL PER DETAIL 9RM-503.
12. INDOOR CUSTOM AIR HANDLING UNIT ON 4" HOUSEKEEPING PAD IN PENTHOUSE. SEE SHEET M-602 AND MECH SCHEDULE M-701 FOR ADDITIONAL INFO.
13. 3" HW'S PIPE TO / FROM FIRST FLOOR.
14. 2" HW'R PIPE TO FIRST FLOOR.
15. PROVIDE OWNER REQUESTED COMPLETE NEEDLEPOINT BIPOLAR IONIZATION AIR CLEANING SYSTEM AS MANUFACTURED BY GLOBAL PASMA SOLUTIONS (GPS). AIR CLEANER SHALL BE LOCATED UPSTREAM OF THE COILING COIL AND INSTALLED PER MANUFACTURER'S INSTALLATION MANUAL. INCLUDE ALL REQUIRED COMPONENTS FOR AIRHANDLER COILING DESIGN AIRFLOW FOR A FULLY FUNCTIONAL SYSTEM. REFER TO DIVISION 26 FOR POWER REQUIREMENTS.

**Dzilth-Na-O-Dith-Hle - New
Dormitory Building
CONSTRUCTION
DOCUMENTS**


35 Road 7585, Bloomfield, NM
87413

DECEMBER 4, 2020

MARK	DATE	DESCRIPTION
ISSUE:		
DATE:		751
PROJECT NO:		NZ
CAD DWG FILE:		IM
DRAWN BY:		
CHECKED BY:		


SHEET TITLE

ENLARGED MECHANICAL
PLANS




- 1 COORDINATE SOUND ELBOW INSTALLATION WITH STRUCTURE, LIGHTS, AND OTHER OBSTRUCTIONS
- 2 SUPPORT FROM STRUCTURE SIMILAR TO DUCTWORK
- 3 CONSTRUCT SOUND ELBOW OF 1" THICK RIGID ACOUSTIC INSULATION OR AS SHOWN ON DRAWINGS
- 4 FURNISH AND INSTALL SOUND ELBOWS AS SHOWN ON DRAWINGS
- 5 WHEN FIRE DAMPER OR SMOKE DAMPER IS NEEDED AT THE WALL, INSTALL SOUND ELBOW ATTACHED AND SEALED TO WALL.


3 SOUND ELBOW DETAIL FOR TRANSFER OPENINGS




2 DIFFUSER AND REGISTER CONNECTION DETAIL



1 POWER ROOF EXHAUSTER DETAIL
SCALE = NONE




7 PIPE PENETRATION THRU FIRE RATED BARRIER
SCALE = NONE




- NOTES
1. ANGLE A=30 MAXIMUM WHEN AIR FLOWS IN DIRECTION OF ARROS. (SUPPLY AIR)
 2. ANGLE A=15 WHEN AIR FLOWS IN OPPOSITE DIRECTION OF ARROS (R.A. OR EXHAUST)

6 LOW PRESSURE DUCT FITTING DETAIL



- 1 SECURE SOUND ELBOW TO RETURN GRILLE.
- 2 RETURN AIR GRILLE IN CEILING. SEE PLANS AND SCHEDULE FOR SIZE AND TYPE.
- 3 COORDINATE SOUND ELBOW INSTALLATION WITH STRUCTURE, LIGHTS, AND OTHER OBSTRUCTIONS. POINT OPENING AWAY FROM EQUIPMENT.
- 4 MAINTAIN SAME FREE AREA AS GRILLE. (MINIMUM).
- 5 SUPPORT FROM STRUCTURE SIMILAR TO DUCTWORK.
- 6 CONSTRUCT SOUND ELBOW OF 1" THICK RIGID ACOUSTIC INSULATION.
- 7 FURNISH AND INSTALL SOUND ELBOWS FOR EACH RETURN GRILLE UNLESS NOTED OTHERWISE ON DRAWINGS.

5 SOUND ELBOW DETAIL FOR RETURN GRILLE
SCALE = NONE




4 EXHAUST GRILLE DETAIL

SCALE = NONE

1. OPENINGS IN FLOOR OR WALLS SHALL BE LARGER THAN THE DAMPER BY 1/8" FOR EACH LINEAR FOOT IN HEIGHT AND WIDTH OF THE DAMPER TO ALLOW FOR THERMAL EXPANSION. THE DAMPER SHALL BE INSTALLED WITH LESS THAN REQUIRED TO MAINTAIN A MINIMUM OF 1/4" CLEARANCE BETWEEN THE SLEEVE AND WALL ON ALL SIDES. IN INSTALLATIONS WHERE THE OPENING IS SMALLER THAN THE WALL AND THE DAMPER IS USED TO EXHAUST (SEE 90A), THE FILLER MATERIAL SHALL BE OF FLEXIBLE CONSISTENCY TO ALLOW FOR EXPANSION OF THE FIRE DAMPER-ASSEMBLY.
2. THE FOLDED BLADE ASSEMBLY SHALL ALWAYS BE POSITIONED AT THE TOP WHEN THE DAMPER IS PLACED IN A WALL OPENING.
3. THE DAMPER SHALL BE POSITIONED IN THE OPENING SO THE HORIZONTAL CLEARANCE ALLOWED FOR EXPANSION IS EQUALLY DIVIDED AT BOTH SIDES OF THE DAMPER.
4. THE DAMPER SHALL BE POSITIONED IN THE OPENING SO THAT NO PART OF THE DAMPER PLANE FORMED BY EITHER SIDE OF THE WALL OF THE FIRE RATED FLOOR ASSEMBLY.
5. THE DUCT SHALL NOT BE CONTINUOUS THROUGH THE WALL OPENING, BUT SHALL BE CONNECTED TO THE DAMPER (OR SLEEVE DEPENDS UPON THE STYLE OF DAMPER) ON EITHER SIDE OF THE WALL.
6. APPROVED RECTANGULAR DUCT BREAKAWAY CONNECTIONS ARE: PLAIN 'S' SLP; HEMMED 'S' SLP; DOUBLE 'S' SLP; INSIDE SLP JUNT; STANDING 'S'; STANDING 'S' ANGLE OR BAR REINFORCED; STANDING 'S' ALTERNATE; OR DRIVE SLP JUNT. THE SHIELDING SYSTEM SHALL BE USED TO PROTECT THE DAMPER FROM THE WARD TDC (LOCK FORMER) AND TDC (ENGL) MAY BE USED FOR BREAKAWAY CONNECTIONS. WHEN INSTALLED IN ACCORDANCE WITH MANUFACTURER'S INSTALLATION INSTRUCTIONS, THE DAMPER SHALL BE PROTECTED FROM BREACH OF THE DAMPER BY THE WIDE DRAW BAND OR 10" SHEET METAL SCREWS, SPACED EQUALLY AROUND THE CIRCUMFERENCE OF THE DUCT IN ACCORDANCE WITH THE MANUFACTURER'S INSTALLATION INSTRUCTIONS. THE DAMPER SHALL BE SECURED TO THE DUCT CONNECTIONS TO THE DUCT-SLEEVE, SLEAT DUCT CONNECTIONS WITH HARDCAST INC.
7. DAMPER FRAME MAY BE OF DESIGN AND LENGTH AS TO FUNCTION AS THE SLEEVE IF SO TESTED AND LABELED BY UL. OTHERWISE, THE SLEEVE SHALL BE CONTINUOUS THROUGH THE WALL WITH ALL WELDED SEAMS AND SHALL EXTEND A MINIMUM DISTANCE BEYOND THE PLANES FORMED BY BOTH WALLS OR FLOOR ASSEMBLY, EQUAL TO THE WIDTH OF THE RETAINING ANGLES, BUT SHALL NOT BE GREATER THAN WALL WIDTH PLUS MOUNTING ANGLE DIMENSIONS PLUS 8".
8. THE SLEEVE GAUGE SHALL BE EQUAL TO OR DEEPER THAN THE GAUGE OF THE DUCT AS DEFINED BY THE APPROPRIATE SMAGNA DUCT CONSTRUCTION STANDARD, BUT THE SLEEVE SHALL BE AT LEAST 1/2" THICK. THE SLEEVE SHALL BE EQUIVALENT TO THE DAMPER MANUFACTURER'S UL TEST AND INSTALLATION INSTRUCTIONS.
9. THE FIRE DAMPER SHALL BE BOLTED, SCREWED, RIVETED, OR TACK WELDED TO THE SLEEVE AND THE SPACING SHALL BE IN ACCORDANCE WITH MANUFACTURER'S INSTALLATION INSTRUCTIONS.
10. THE SLEEVE-FIRE DAMPER ASSEMBLY SHALL BE THEN HELD IN PLACE IN THE WALL (OR FLOOR) BY MOUNTING ANGLE(S), MINIMUM OF 1-1/2" X 16 ANGLE, BUT NOT LESS THAN 1/4" THICK. THE SLEEVE SHALL BE ATTACHED TO THE MOUNTING ANGLE(S) ON BOTH SIDES OF WALL OR FLOOR ASSEMBLY. THESE MOUNTING ANGLE(S) SHALL BE WELDED TO THE SLEEVE AT A SPACING IN ACCORDANCE WITH MANUFACTURER'S INSTALLATION INSTRUCTIONS. THE DAMPER SHALL NOT BE ATTACHED TO THE WALL WITH A MINIMUM OF ONE (1) INCH ON ALL SIDES AND SHALL NOT BE ATTACHED TO THE WALL.
11. WHEN MULTIPLE SECTIONS OF STEEL DAMPERS ARE JOINED, THE CONNECTIONS SHALL BE ON BOTH SIDES OF DAMPER CURTAIN, AT A MAXIMUM DISTANCE OF 2" FROM ANY OF THE FOUR CORNERS AND A MAXIMUM SPACING OF 12" O.C. WITH A MINIMUM OF TWO CORNERS JOINTS IN EACH 12" TOP AND BOTTOM.
12. PROVIDE DUCT ACCESS DOORS AT ALL FIRE DAMPER LOCATIONS OF SUFFICIENT SIZE TO ALLOW EASY ACCESS TO AND REMOVAL OF DAMPER LINKAGES. PROVIDE CEILING ACCESS DOORS IN ALL GYP. BOARD, PLASTER, OF CONCEALED SPLINE LENGTHS TO SERVICE ALL REQUIRED DUCT ACCESS DOORS. PROVIDE ACCESS DOORS IN ALL WALLS AND FLOORS THAT REQUIRE ACCESS TO DAMPER LINKAGES. PROVIDE ACCESS TO THE FIRE DAMPER, DUCT ACCESS FOR SMALL FIRE DAMPERS 6" SQUARE DIAMETER AND LESS, MAY BE PROVIDED BY MEANS OF REMOVABLE FLEXIBLE DUCT SUBJECT TO THE APPROVAL OF THE BUILDING CODE AUTHORITY HAVING JURISDICTION.
13. ALL FIRE DAMPERS SHALL BE INSTALLED IN ACCORDANCE WITH MANUFACTURER'S INSTALLATION INSTRUCTIONS. UL STANDARD 555 FIRE DAMPERS AND UL STANDARD 556 FIRE DAMPERS, UL STANDARD 555S SMOKE DAMPERS AND LABELED AS UL LEAKAGE CLASS 1; NFPA STANDARD 90A AND 90B; INTERNATIONAL BUILDING CODE, 2003 EDITION, AND THE INTERNATIONAL MECHANICAL CODE, 2003 EDITION.
14. COMBINATION FIRE AND SMOKE DAMPERS SHALL BE MULTIBLADE TYPE DAMPER CLASSIFIED AS LABELED IN ACCORDANCE WITH UL 555 CLASSIFICATION AND UL 555S CLASSIFICATION AS LEAKAGE CLASS 15. DAMPER ASSEMBLY INSTALLATION SHALL BE PROVIDED IN ACCORDANCE WITH MANUFACTURER'S APPROVED INSTALLATION INSTRUCTIONS. DAMPERS SHALL BE PROVIDED WITH UL APPROVED DAMPER ACTUATOR AND FUSE LINK IN ACCORDANCE WITH SPECIFICATION SECTION 15800.
15. COMBINATION FIRE AND SMOKE DAMPERS SHALL BE MULTIBLADE TYPE DAMPER CERTIFIED AND LABELED IN ACCORDANCE WITH UL 555 CLASSIFICATION AND UL 555S CLASSIFICATION AS LEAKAGE CLASS 15. DAMPER ASSEMBLY INSTALLATION SHALL BE PROVIDED IN ACCORDANCE WITH MANUFACTURER'S APPROVED INSTALLATION INSTRUCTIONS. DAMPERS SHALL BE FURNISHED BY THE MANUFACTURER WITH UL APPROVED DAMPER ACTUATOR AND FUSE LINK IN ACCORDANCE WITH SPECIFICATION SECTION 15800.

9 FIRE DAMPER INSTALLATION NOTES
SCALE = NONE




DUCT DIMENSION ON WHICH ACCESS DOOR IS PLACED

6" - 8"	5" X 12"
9" - 12"	6" X 12"
13" - 15"	12" X 12"
16" - 33"	14" X 14"
34" - 66"	(2) 14" X 14"
67" +	(3) 14" X 14"


RECTANGULAR DUCTS

NOTE:
DUCT ACCESS DOOR MUST PROVIDE FIRE DAMP AND DUCT MOULDING AND AS REQUIRED FOR CLEANING.

8 DUCT ACCESS DOOR DETAIL
SCALE = NONE





11 FIRE DAMPER DETAIL - CURTAIN TYPE
SCALE = NONE




- 1 WALL OR FLOOR
 - 2 SLEEVE - SEE INSTALLATION NOTES, THIS SHEET
 - 3 MOUNTING ANGLES CONTINUOUS AROUND SLEEVE WITH MINIMUM 1" OVERLAP
 - 4 SQUARE OR RECTANGULAR DAMPER FRAME FOR ROUND OR OVAL DUCTS. PROVIDE DUCT TRANSITION
 - 5 BREAKAWAY DUCT CONNECTION - SEE INSTALLATION NOTES
 - 6 FIRE DAMPER FUSIBLE LINK (NOT REQUIRED FOR COMBINATION FIRE/SMOKE DAMPERS OR SMOKE DAMPERS)
 - 7 1/4" MINIMUM EXPANSION CLEARANCE - SEE INSTALLATION NOTES
 - 8 NEGATIVE SPRING (NOT REQUIRED FOR COMBINATION FIRE/SMOKE DAMPER OR SMOKE DAMPERS)
 - 9 APPROVED CAULKING MATERIAL IN ACCORDANCE WITH MANUFACTURER'S INSTALLATION INSTRUCTIONS
 - 10 U/L APPROVED DAMPER ACTUATOR ASSEMBLY WITH MOUNTING BRACKET, ELECTRIC FUSE LINK, AND OPERATING JACK SHAFT LINKAGE. DAMPER ACTUATOR SHALL BE MOUNTED ON DUCT OUTSIDE AIR STREAM
- * FUSIBLE ROD IS NOT REQUIRED FOR SMOKE DAMPER APPLICATION

10 FIRE DAMPER, SMOKE DAMPER, AND COMBINATION FIRE SMOKE DAMPER DETAILS
SCALE = NONE








- 1 CONCRETE PENTHOUSE FLOOR AND 4" CONCRETE CURB AROUND DUCT PENETRATION.
- 2 DUCT - POSITIONED SUCH THAT THERE IS NO PHYSICAL CONTACT BETWEEN THE DUCT AND THE FLOOR. ENSURE GAP OF 1/2" TO 5/8" ON ALL SIDES.
- 3 FIBERGLASS OR MINERAL WOOL TYPE INSULATION.
- 4 NON-HARDENING RESILIENT CAULK - CONTINUOUS.
- 5 MASS LOADED VINYL SIMILAR TO KINETICS KNM 100RB WITH A SURFACE DENSITY OF NO LESS THAN 1.0 LB/SQ-FT. ADHERE TO THE DUCT AND ADJACENT CONCRETE WITH AN ADHESIVE RECOMMENDED BY THE VINYL MANUFACTURER.
- 4 PENI HOUSE FLOOR DUCT PENETRATION DETAIL
- SCALE = NONE




- 1 FAN ROOM WALL - REFER TO ARCHITECTURAL DRAWINGS FOR CONSTRUCTION TYPE.
- 2 DUCT POSITIONED SUCH THAT THERE IS NO PHYSICAL CONTACT BETWEEN THE DUCT AND THE WALL. ENSURE A GAP OF 1/2" TO 5/8" ON ALL SIDES.
- 3 FIBERGLASS OR MINERAL WOOL TYPE INSULATION.
- 4 NON-HARDENING RESILIENT CAULK - CONTINUOUS.
- 5 MASS LOADED VINYL SIMILAR TO KINETICS KNM 100RB WITH A SURFACE DENSITY OF NO LESS THAN 1.0 LB/SQ-FT. ADHERE TO THE DUCT AND ADJACENT WALL WITH AN ADHESIVE RECOMMENDED BY THE VINYL MANUFACTURER.
- 3 FAN ROOM WALL PENETRATION DETAIL
- SCALE = NONE




- NOTES:
1. 5 PROVIDE SHEET METAL SLEEVE AROUND PIPE INSULATION AT ALL PIPE HANGERS. SEE SPECS. FOR INSULATION
2. "U" BOLTS SHALL BE USED AS GUIDES ONLY, NOT ANCHORS.
3. "U" BOLTS SHALL BE ON EVERY THIRD TRAPEZE (MIN.)
4. DO NOT TIGHTEN "U" BOLTS ON PIPING OR INSULATION. LEAVE LOOSE AS PIPE GUIDE.
- 1 PIPE HANGER DETAIL
- SCALE = NONE




- KEYNOTES
1. DISCHARGE PIPING
2. SUCTION PIPING
3. BUTTERFLY VALVE, 2-1/2" AND LARGER BALL VALVE, 2" AND SMALLER
4. FLEXIBLE COUPLING
5. INCREASER
6. SILENT CHECK VALVE
7. SUCTION DIFFUSER WITH STRAINER
8. COMPOUND PRESSURE GAUGE WITH GAUGE COCKS
9. INERTIA BASE WITH WELDED STEEL CHANNEL FRAME FILLED WITH CONCRETE. WEIGHT OF INERTIA BASE SHALL BE 1-1/2 TIMES THE WEIGHT OF PUMP AND MOTOR. PROVIDE HILT OR REDHEAD ANCHORS IN CONCRETE TO ANCHOR PUMP AND MOTOR
10. ADJUSTABLE SUPPORT LEG
11. STEEL SPRING VIBRATION ISOLATOR. SEE EQUIPMENT SCHEDULE AND/OR SPECS. FOR VIBRATION ISOLATOR REQUIREMENTS
12. 1/2" DRAIN LINE FROM MECHANICAL SEAL PUMPS WHICH HAVE A DRAIN FITTING AND ALL PUMPS WITH STUFFING BOXES TO NEAREST F.D.
13. 8"x8"x1/4" THICK STEEL PLATE TO DISTRIBUTE WEIGHT ON INERTIA BASES WHICH WEIGH OVER 1000 LBS
14. WHEN REQUIRED, THE MOTOR FOUNDATION SHOULD BE ELEVATED TO AVOID INTERFERENCE BETWEEN THE PUMP CASING AND THE CONCRETE BASE
- 8 PUMP AND BASE DETAIL
- SCALE = NONE




- 1 FLUE HEIGHT SHALL BE NO LESS THAN 3'-0" ABOVE THE HORIZONTAL ROOF PLANE. SHOULD ANY OBSTRUCTION WITHIN A 10 FOOT RADIUS OF THE FLUE PROJECT ABOVE THE HORIZONTAL ROOF PLANE, THE FLUE SHALL EXTEND TO 3'-0" ABOVE THE OBSTRUCTION. OBSTRUCTIONS INCLUDE BUT ARE NOT LIMITED TO ITEMS SUCH AS PARAPETS, WALLS, AIR INTAKES, AND ROOF SLOPES.
- 7 FLUE THRU ROOF DETAIL
- SCALE = NONE




- 6 IN-LINE PUMP DETAIL
- SCALE = NONE




- 5 MANUAL AIR VENT DETAIL
- SCALE = NONE




- NOTES:
1. DRAIN ALL LOW POINTS OF PIPING
2. DRAIN ALL SCALE POCKETS AS SHOWN ON PLANS AND/OR PIPING DIAGRAMS
- 11 DRAIN VALVE DETAIL
- SCALE = NONE




- NOTE:
1. INSTALL TOP OF CHEMICAL POT FEEDER NOT MORE THAN 3'-0" ABOVE FLOOR.
2. MOUNT FEEDER(S) ON STEEL SUPPORT BRACKET ADJACENT TO PUMP(S).
3. REFER TO PIPING SCHEMATIC FOR EQUIPMENT NUMBER.
- 10 CHEMICAL POT FEEDER DETAIL
- SCALE = NONE



- NOTE:
- PROVIDE MANUAL AIR VENTS AT ALL HIGH POINTS IN SYSTEM. SEE MANUAL AIR VENT DETAIL.
- SEE PLANS AND/OR PIPING SCHEMATIC FOR PIPE SIZES.
- T&P FITTINGS INSTALLED IN PIPING 2" AND SMALLER SHALL BE INSTALLED IN ELBOW OR IN THE BRANCH SIDE OF A 2" TEE.
- DRAIN VALVE AT ALL LOW POINTS OF PIPING. SEE DRAIN VALVE DETAIL
- KEYNOTES
1. SUPPLY WATER SHALL BE CONNECTED TO AIR LEAVING SIDE OF COIL
2. COLLECT ALL DRAINS, INSTALL HOSE CONNECTION AND CAP
3. TEMPERATURE AND PRESSURE (T&P) FITTING, TYP.
4. PRESSURE GAUGE, TYP
5. THERMOMETER, TYP
6. UNION, TYP.
7. AUTOMATIC THREE-WAY CONTROL VALVE. COORDINATE PORT CONFIGURATION WITH CONTROLS CONTRACTOR.
8. ISOLATION VALVE, TYP.
9. MANUAL AIR VENT
10. 1/2" SHUT-OFF VALVE AND DRAIN
11. DASHED PIPING AND COILS INDICATE TYPICAL PIPING REQUIREMENTS FOR MULTIPLE COILS
12. [FLOW BALANCE VALVE] [AUTOMATIC FLOW LIMITING VALVE]. SEE SPECIFICATIONS.
13. UNION OR FLANGE. INSTALL SO AS TO ALLOW REMOVAL OF COIL WITHOUT MAJOR REMOVAL OF PIPING.
14. GAUGE COCK, TYP.
15. IN-LINE PUMP FOR FREEZE PROTECTION. SEE EQUIPMENT SCHEDULE FOR SIZE AND CONTROL DRAWINGS FOR SEQUENCE OF OPERATION.
- 9 HOT WATER COIL PIPING SCHEMATIC (3-WAY)
- SCALE = NONE




- NOTES
- PROVIDE MANUAL AIR VENTS AT ALL HIGH POINTS IN SYSTEM. SEE MANUAL AIR VENT DETAIL.
- SEE PLANS AND/OR PIPING SCHEMATIC FOR PIPE SIZES.
- T&P FITTINGS INSTALLED IN PIPING 2" AND SMALLER SHALL BE INSTALLED IN ELBOW OR IN THE BRANCH SIDE OF A 2" TEE.
- DRAIN VALVE AT ALL LOW POINTS OF PIPING. SEE DRAIN VALVE DETAIL
- KEYNOTES
1. SUPPLY WATER SHALL BE CONNECTED TO AIR LEAVING SIDE OF COIL
2. COLLECT ALL DRAINS, INSTALL HOSE CONNECTION AND CAP.
3. TEMPERATURE AND PRESSURE (T&P) FITTING, TYP.
4. PRESSURE GAUGE AND COCK, TYP.
5. THERMOMETER
6. UNION, TYP.
7. AUTOMATIC TWO-WAY CONTROL VALVE
8. BUTTERFLY VALVE, TYP.
9. MANUAL AIR VENT
10. 1/2" SHUT-OFF VALVE AND DRAIN
11. DASHED PIPING AND COILS INDICATE TYPICAL PIPING REQUIREMENTS FOR MULTIPLE COILS
12. [FLOW BALANCE VALVE] [AUTOMATIC FLOW LIMITING VALVE]. SEE SPECIFICATIONS. NOT REQUIRED IF PRESSURE-INDEPENDENT CONTROL VALVE IS SPECIFIED.
13. UNION OR FLANGE. INSTALL SO AS TO ALLOW REMOVAL OF COIL WITHOUT MAJOR REMOVAL OF PIPING.
14. GAUGE COCK, TYP.
15. CHECK VALVE
16. IN-LINE PUMP FOR FREEZE PROTECTION. SEE EQUIPMENT SCHEDULE FOR SIZE AND CONTROL DRAWINGS FOR SEQUENCE OF OPERATION.
- 13 HOT WATER COIL PIPING SCHEMATIC (2-WAY)
- SCALE = NONE



- KEYNOTES
1. METAL STRAP SUPPORT FROM STRUCTURE (TYPICAL)
2. MANUAL AIR VENT ON COIL OR HWR PIPING
3. FACTORY FABRICATED SOUND ATTENUATOR
4. HOT WATER COIL
5. CONTROLS ENCLOSURE
6. HIGH VELOCITY FLEXIBLE SUPPLY DUCT 12" MIN., 24" MAX.
7. DRAIN
8. TEMPERATURE-PRESSURE FITTING (TYP.)
9. LOW VELOCITY DUCTWORK TO DISTRIBUTION
10. REFER TO PLANS FOR PIPE SIZES
11. 2-WAY CONTROL VALVE, NORMALLY CLOSED. FAIL TO COOL
12. BALL VALVE (TYP)
13. UNION (TYP)
14. REDUCER (TYP)
15. HIGH VELOCITY RIGID SUPPLY DUCT, 3 FT. MINIMUM STRAIGHT RUN PRIOR TO TERMINAL UNIT CONNECTION. SEE SCHEDULE FOR VALVE AND DUCT SIZES
16. FLOW BALANCING VALVE, OR FLOW LIMITING VALVE. SEE SPECIFICATIONS
17. TRANSITION FROM 2" LARGER DUCT DIAMETER THAN VALVE CONNECTION SIZE
- 12 SINGLE DUCT VAV TERMINAL UNIT WITH REHEAT COIL (2-WAY)
- SCALE = NONE

MARK	DATE	DESCRIPTION
	11/17/20	Addendum Changes
ISSUE:		
DATE:		
PROJECT NO:		751
CAD DWG FILE:		NZ
DRAWN BY:		IM
CHECKED BY:		





INDOOR VAV AIR HANDLING UNIT																															
SYMBOL	MANUFACTURER & MODEL NO.	TYPE	LOCATION	SUPPLY FAN SECTION										EXHAUST FAN SECTION										DIRECT EXPANSION COOLING COIL							
				TOTAL AIRFLOW (CFM)	FAN SIZE AND TYPE	FAN QTY.	PER FAN				QTY	MOTOR		TOTAL AIRFLOW (CFM)	FAN SIZE AND TYPE	FAN QTY	AIRFLOW (CFM)	ESP. (IN. WC)	QTY	MOTOR		REFR. TYPE	MAX. FACE VEL. (FPM)	TOTAL CAPACITY (MBH)	SENSIBLE CAPACITY (MBH)	EAT (°F) DB/WB	LAT (°F) DB/WB	AIR MAX. PD (IN. WC)			
							AIRFLOW (CFM)	EXT. SP. (IN. WC)	BHP	RPM		HP EACH	V/PH/H							HP EACH	V/PH/HZ										
AHU-1	TRANE - CSA025UA	PERFORMANCE CLIMATE CHANGER	MECH PENTHOUSE	12,000	DIRECT DRIVE PLENUM	2	6,000	2.5	6.06	2,261	2	7.5	460/3/60	12,000	DIRECT DRIVE PLENUM	2	6,000	0.6"	2	5	460/3/60	410A	481	295	295	83.9/56.5	56.4/45.9	0.22			

INDOOR VAV AIR HANDLING UNIT - CONTINUED																																				
SYMBOL	MAIN HOT WATER HEATING COIL								INDIRECT/DIRECT EVAPORATIVE COOLING SECTION																			FILTER		MIN OUTSIDE AIR (CFM)	TOTAL OPERATING WEIGHT (LBS.)	OVERALL UNIT DIMENSIONS	NOTE			
	TOTAL CAPACITY (MBH)	MAX. FACE VELOCITY (FPM)	LAT (°F)	GPM	WATER TEMP (°F)		MAX PRESSURE LOSS	INDIRECT							DIRECT							PUMP		PRE	FINAL											
					ENT.	LVG.		AIR (IN. WC)	WATER (FT. WC)	AIRFLOW RATE (CFM)	TOTAL CAPACITY (MBH)	EAT DB/WB (°F)	LAT DB/WB (°F)	STATIC PRESSURE DROP (IN H2O)	COOLING EFFICIENCY (%)	QTY	PUMP			AIRFLOW RATE (CFM)	TOTAL CAPACITY (MBH)	EAT DB/WB (°F)	LAT DB/WB (°F)			STATIC PRESSURE DROP (IN H2O)	COOLING EFFICIENCY (%)	COOLING MEDIA	QTY					PUMP		
																	HP	PER PUMP GPM	V/PH/H															HP	PER PUMP GPM	VOLT/PH/H
AHU-1	479	498	60	32	130	100	0.096	3.31	12,000	312.2	94/61	70.2/52.9	0.8	72	1	0.125	16	120/1/60	12,000	200.6	70.2/52.9	55/52.9	0.2	80%	12" CELDEK	1	0.125	16	120/1/60	MERV 8	MERV 13	4,100	11,000	298"(L)X120"(W)X111"(H)	UNIT ON 6" CONCRETE HOUSEKEEPING PAD	

INDOOR VAV AIR HANDLING UNIT - SOUND DATA								
SYMBOL	DISCHARGE SOUND POWER BY OCTIVE BAND							
	63 Hz	125 Hz	250 Hz	500 Hz	1000 Hz	2000 Hz	4000 Hz	8000 Hz
AHU-1	82	85	94	83	78	80	74	67

CONDENSING UNIT SCHEDULE																														
SYMBOL	TRANE MODEL NO.	LOCATION	CORRESPONDING INDOOR UNIT	TON	NET TOTAL CAPACITY (MBH)	EER @ AHRI	AMBIENT DB (DEG F)	SATURATED SUCTION TEMP	ELECTRICAL DATA					COMPRESSORS					CONDENSERS (MICROCHANNEL)										WEIGHT (LBS.)	LENGTH/ WIDTH/ HEIGHT (IN)
									VOLT	PH	HZ	MCA	MOCPP	COMPRESSOR TYPE	MANIFOLD COMPRESSOR SIZES		UNIT CAPACITY STEPS	REFR. TYPE	LIQUID LINE	SUCTION LINE	FAN QTY.	DIAMATER (IN)	AIR FLOW (CFM)	SIZE (IN)	FACE AREA (SF)	ROWS/FIN PER FT	REFR. STORAGE CAPACITY(LB)			
ACU-1	RAUJC2	ROOF	AHU-1	25.0	307	12.1 (COND ONLY)	100	45 (F)	460	3	60	52	70	SCROLL	13-13.5		100-42	R-410A	7/8"	2-1/8"	3	26	20,700	42X71	41.4	1/240	18.7	2,000	88-1/2"X57-5/8"X74-1/4"	
NOTE - FURNISH WITH NON-FUSED DISCONNECT, LOW VOLTAGE MONITOR, FACTORY-INSTALLED DISCHARGE AND LIQUID LINE SERVICE VALVES, STANDARD AMBIENT OPERATING RANGE, HOT GAS BYPASS TO THE EVAPORATOR INLET, SUCTION SERVICE VALVE, PRESSURE GAUGES, RETURN AIR SENSOR, UNIT SPRING ISOLATORS, CORROSION PROTECTED CONDENSER COIL																														

HYDRONIC BOILER SCHEDULE																						
SYMBOL	GENERAL UNIT DATA									CONNECTION DATA				ELECTRICAL DATA				PHYSICAL DATA				NOTE
	MANUFACTURER & MODEL NO.	SERVICE	INPUT AT SEA LEVEL (MBH)	OUTPUT AT SITE (MBH)	EFF	LWT (°F)	FLOW (GPM)	TURN DOWN	HEX WATER VOLUME	NATURAL GAS CONN SIZE (IN)	GAS PRESSURE (IN. W.G.)	VENT SIZE (IN)	COMBUSTION AIR SIZE (IN)	VOLT	PHASE	HZ	AMP DRAW	LENGTH (IN)	WIDTH (IN)	HEIGHT (IN)	OPERATING WEIGHT (LBS)	
B-1	LOCHINVAR - FTXL 600 (N)	HOT WATER SYS	600	552	92%	130	28	7:1	12 GAL	1"	4" TO 14"	4"	4"	120	1	60	12	26-1/8"	22-5/8"	53-5/8"	560	HEATING SYS BOILER MOUNTED ON 4" CONCRETE HOUSEKEEPING PAD
B-2	LOCHINVAR - FTXL 600 (N)	HOT WATER SYS	600	552	92%	130	28	7:1	12 GAL	1"	4" TO 14"	4"	4"	120	1	60	12	26-1/8"	22-5/8"	53-5/8"	560	HEATING SYS BOILER MOUNTED ON 4" CONCRETE HOUSEKEEPING PAD

PUMPS														
SYMBOL	BELL & GOSSETT MODEL NO.	LOCATION	SERVICE	TYPE	CAPACITY (GPM)	TOTAL HEAD (FT. WG)	PUMP RPM	MOTOR HP	ELECTRICAL DATA			OPERATING WEIGHT (LBS.)	NOTES	
									VOLT	PHASE	HZ			
P-1	BG-E60-1X1X5.25	BOILER ROOM	PRIMARY PUMP	INLINE	28	15	1,800	1/3	115	1	60	55	-	
P-2	BG-E60-1X1X5.25	BOILER ROOM	PRIMARY PUMP	INLINE	28	15	1,800	1/3	115	1	60	55	-	
P-3	BG-E1531-1.25AD	MECH PENTHOUSE	SECONDARY PUMP	BASE MOUNTED CLOSE COUPLED	65	45	1,800	1.5	460	3	60	130	FURNISH WITH SUCTION DIFFUSER AND RATED MOTOR, ONE PUMP IS BACK UP	
P-4	BG-E1531-1.25AD	MECH PENTHOUSE	SECONDARY PUMP	BASE MOUNTED CLOSE COUPLED	65	45	1,800	1.5	460	3	60	130	FURNISH WITH SUCTION DIFFUSER AND RATED MOTOR, ONE PUMP IS BACK UP	
P-5	BG-E60-1.25X1.25X5.25	MECH PENTHOUSE	AHU-1 HW COIL	INLINE	32	20	1,800	1/2	115	1	60	60	-	

VARIABLE FREQUENCY DRIVES										
SYMBOL	MANUFACTURER & MODEL NO.	LOCATION	SERVICE	ELECTRICAL					NOTES	
				VOLT	PHASE	HZ	MOTOR HP	MAX AMP		
VFD-1	ABB - ACH550-03A3-4	BOILER ROOM	HOT WATER PUMPS	460	3	60	1.5	3.3	FURNISH WITH BYPASS AND FUSED DISCONNECT	
VFD-2	ABB - ACH550-03A3-4	BOILER ROOM	HOT WATER PUMPS	460	3	60	1.5	3.3	FURNISH WITH BYPASS AND FUSED DISCONNECT	
VFD-3	ABB - ACH550-012A-4	MECH PENTHOUSE	AHU-1 SA FAN	460	3	60	7.5	11.9	FURNISH WITH FUSED DISCONNECT	
VFD-4	ABB - ACH550-012A-4	MECH PENTHOUSE	AHU-1 SA FAN	460	3	60	7.5	11.9	FURNISH WITH FUSED DISCONNECT	
VFD-5	ABB - ACH550-08A8-4	MECH PENTHOUSE	AHU-1 EX FAN	460	3	60	5.0	8.8	FURNISH WITH FUSED DISCONNECT	
VFD-6	ABB - ACH550-08A8-4	MECH PENTHOUSE	AHU-1 EX FAN	460	3	60	5.0	8.8	FURNISH WITH FUSED DISCONNECT	

ELECTRIC UNIT HEATER														
SYMBOL	MANUFACTURER & MODEL NO.	LOCATION	AIRFLOW (CFM)	CONTROL VOLTAGE	HEATING (KW)	ELECTRICAL DATA						WEIGHT (LBS.)	NOTES	
						MINIMUM FUSE SIZE	MAXIMUM AMP RATING	VOLT	PHASE	HZ	MOTOR HP			MOTOR RPM
EUH-1	TRANE UHEC-072AAC	BOILER ROOM	700	24	7.5	50	36.1	208	1	60	1/50	1550	50	ELEC DISCONNECT, INSTALL WITH WALL MOUNTED BRACKET, TRANSFORMER – 24V CONTROL CIRCUIT
EUH-2	TRANE UHEC-072AAC	MECH PENTHOUSE	700	24	7.5	50	36.1	208	1	60	1/50	1550	50	ELEC DISCONNECT, INSTALL WITH WALL MOUNTED BRACKET, TRANSFORMER – 24V CONTROL CIRCUIT

SINGLE DUCT TERMINAL UNIT SCHEDULE (HW HEAT)																	
GENERAL UNIT DATA				AIRFLOW DATA											PIPE SIZE (IN DIA)	CONTROL VALVE	NOTE
SYMBOL	MANUFACTURER	MODEL NO.	INLET CONNECTION SIZE (IN)	COOLING MAX. (CFM)	COOLING MIN. (CFM)	HEATING MEX. (CFM)	EAT (°F)	LAT (°F)	FLOW RATE (GPM)	EWT (°F)	LWT (°F)	CAPACITY (MBH)	NO. OF ROWS	WATER PRESSURE DROP (FT. HD.)			
TU-1-1	PRICE	SDVQ5-6	6	460	140	276	55	90	0.9	130	110	8665	2	10	3/4"	3-WAY	PROVIDE 120/24 VOLT (50VA) TRANSFORMER
TU-1-2	PRICE	SDVQ5-8	8	630	190	378	55	90	1.2	130	110	11620	2	10	3/4"	3-WAY	PROVIDE 120/24 VOLT (50VA) TRANSFORMER
TU-1-3	PRICE	SDVQ5-6	6	400	120	240	55	90	0.8	130	110	7487	2	10	3/4"	2-WAY	PROVIDE 120/24 VOLT (50VA) TRANSFORMER
TU-1-4	PRICE	SDVQ5-8	8	630	190	378	55	90	1.2	130	110	11620	2	10	3/4"	2-WAY	PROVIDE 120/24 VOLT (50VA) TRANSFORMER
TU-1-5	PRICE	SDVQ5-6	6	260	80	156	55	90	0.5	130	110	4872	2	10	3/4"	2-WAY	PROVIDE 120/24 VOLT (50VA) TRANSFORMER
TU-1-6	PRICE	SDVQ5-8	8	630	190	378	55	90	1.2	130	110	11620	2	10	3/4"	2-WAY	PROVIDE 120/24 VOLT (50VA) TRANSFORMER
TU-1-7	PRICE	SDVQ5-8	8	715	215	429	55	90	1.3	130	110	13197	2	10	3/4"	2-WAY	PROVIDE 120/24 VOLT (50VA) TRANSFORMER
TU-1-8	PRICE	SDVQ5-10	10	1070	1070	700	55	90	2.2	130	110	21796	2	10	3/4"	2-WAY	PROVIDE 120/24 VOLT (50VA) TRANSFORMER
TU-1-9	PRICE	SDVQ5-8	8	760	230	456	55	90	1.4	130	110	14056	2	10	3/4"	3-WAY	PROVIDE 120/24 VOLT (50VA) TRANSFORMER
TU-1-10	PRICE	SDVQ5-10	10	1345	400	807	55	90	2.5	130	110	24717	2	10	3/4"	2-WAY	PROVIDE 120/24 VOLT (50VA) TRANSFORMER
TU-1-11	PRICE	SDVQ5-8	8	550	165	330	55	90	1	130	110	10082	2	10	3/4"	2-WAY	PROVIDE 120/24 VOLT (50VA) TRANSFORMER
TU-1-12	PRICE	SDVQ5-8	8	800	240	500	55	90	1.5	130	110	14874	2	10	3/4"	2-WAY	PROVIDE 120/24 VOLT (50VA) TRANSFORMER
TU-1-13	PRICE	SDVQ5-10	10	980	295	588	55	90	1.9	130	110	18309	2	10	3/4"	2-WAY	PROVIDE 120/24 VOLT (50VA) TRANSFORMER
TU-1-14	PRICE	SDVQ5-6	6	120	40	72	55	90	0.2	130	110	2256	2	10	3/4"	2-WAY	PROVIDE 120/24 VOLT (50VA) TRANSFORMER
TU-1-15	PRICE	SDVQ5-8	8	800	800	480	55	90	1.5	130	110	14874	2	10	3/4"	2-WAY	PROVIDE 120/24 VOLT (50VA) TRANSFORMER
TU-1-16	PRICE	SDVQ5-10	10	1270	380	760	55	90	2.4	130	110	23619	2	10	3/4"	2-WAY	PROVIDE 120/24 VOLT (50VA) TRANSFORMER
TU-1-17	PRICE	SDVQ5-6	6	500	150	300	55	90	0.9	130	110	9184	2	10	3/4"	2-WAY	PROVIDE 120/24 VOLT (50VA) TRANSFORMER
TU-1-18	PRICE	SDVQ5-8	8	580	175	348	55	90	1.1	130	110	10821	2	10	3/4"	2-WAY	PROVIDE 120/24 VOLT (50VA) TRANSFORMER
TU-1-19	PRICE	SDVQ5-6	6	460	140	276	55	90	0.9	130	110	8665	2	10	3/4"	2-WAY	PROVIDE 120/24 VOLT (50VA) TRANSFORMER
TU-1-20	PRICE	SDVQ5-8	8	675	200	405	55	90	1.3	130	110	12378	2	10	3/4"	2-WAY	PROVIDE 120/24 VOLT (50VA) TRANSFORMER
TU-1-21	PRICE	SDVQ5-8	8	610	180	366	55	90	1.2	130	110	11461	2	10	3/4"	2-WAY	PROVIDE 120/24 VOLT (50VA) TRANSFORMER
TU-1-22	PRICE	SDVQ5-8	8	730	220	438	55	90	1.4	130	110	13617	2	10	3/4"	3-WAY	PROVIDE 120/24 VOLT (50VA) TRANSFORMER
TU-1-23	PRICE	SDVQ5-8	8	620	185	372	55	90	1.2	130	110	11540	2	10	3/4"	3-WAY	PROVIDE 120/24 VOLT (50VA) TRANSFORMER
TU-1-24	PRICE	SDVQ5-10	10	1400	420	840	55	90	2.7	130	110	26155	2	10	3/4"	2-WAY	PROVIDE 120/24 VOLT (50VA) TRANSFORMER

LOUVERED PENTHOUSE VENTILATOR							
SYMBOL	MANUFACTURER & MODEL NO.	LOCATION	AIRFLOW (CFM)	DIMENSIONS (INCH)	FACE AREA	FREE AREA	PRESSURE DROP (IN. WC)
LV-1	RUSKIN - ELF6350DD	MECH PENTHOUSE	12,000	96X36	24 SF	61%	0.09
LV-2	RUSKIN - ELF811DD	MECH PENTHOUSE	12,000	96X42	25.08	57%	0.1

EXHAUST FANS																
SYMBOL	GREENHECK MODEL NO.	AREA SERVED	TYPE	CFM	S.P. (IN. WC)	FAN RPM	BHP	MOTOR DATA					DAMPER	OPERATING WEIGHT (LBS.)	NOTES	
								HP	VOLT	PHASE	HZ	FLA				
EF-1	GREENHECK - GB-131-4	ISOLATION 220, 221, LINEN CLOSET 105A, JAN 219, HONORS RR 223A, BOY'S RR 218	CENTRIFUGAL ROOF EXHAUST FAN	1,290	0.5	1,239	0.21	1/4	115	1	60	5.8	BACKDRAFT	60	ELEC DISCONNECT, 14" ROOF CURB	
EF-2	GREENHECK - GB-091-4	RR 109, RR 120, STR-120.1	CENTRIFUGAL ROOF EXHAUST FAN	560	0.5	1,300	0.11	1/4	115	1	60	5.8	BACKDRAFT	60	ELEC DISCONNECT, 14" ROOF CURB	
EF-3	GREENHECK - GB-091-4	W RR 121, G RR 114, JAN 111	CENTRIFUGAL ROOF EXHAUST FAN	550	0.5	1,293	0.11	1/4	115	1	60	5.8	BACKDRAFT	60	ELEC DISCONNECT, 14" ROOF CURB	
EF-4	GREENHECK - GB-131-4	G RR 204, JAN 206, ISOLATION 207, HONORS RR 208A, STR 112, ISOLATION - RR 207A	CENTRIFUGAL ROOF EXHAUST FAN	1,280	0.5	1,234	0.21	1/4	115	1	60	5.8	BACKDRAFT	60	ELEC DISCONNECT, 14" ROOF CURB	
EF-5	GREENHECK - GB-101-4	LAUNDRY 105, 107	CENTRIFUGAL ROOF EXHAUST FAN	900	0.5	1,293	0.17	1/4	115	1	60	5.8	BACKDRAFT	60	ELEC DISCONNECT, 14" ROOF CURB	

EXPANSION TANK							
SYMBOL	MANUFACTURER & MODEL NO.	LOCATION	SERVICE	TANK VOLUME (GALLONS)	ACCEPTANCE VOLUME (GALLONS)	WEIGHT (LBS.)	NOTES
ET-1	AMTROL - AX40	MECH PENTHOUSE	HOT WATER SYS	21.7	11.3	300	CHARGE BLADDER TO 15 PSIG, 1" NPT CONNECTION

CHEMICAL FEED SYSTEM						
SYMBOL	MANUFACTURER & MODEL NO.	LOCATION	RECEIVER NET CAPACITY (GAL)	TEMP RATING (F)	PIPE CONNECTIONS (IN)	NOTE
CF-1	GRISWOLD DB-12-SB-CS-Z-250	MECH PENTHOUSE	12	250	2 EA - 3/4"	FURNISH WITH 3/4" VALVE PACKAGE, FUNNEL PACKAGE WITH ISOLATION VALVE. ALL COMPONENTS RATED FOR 250°F WATER TEMPERATURE

SPLIT SYSTEM INDOOR UNITS																						NOTES	
SYMBOL	MANUFACTURER	MODEL NO.	NOMINAL TON	AREA SERVED	AIR FLOW CFM	COOLING				HEATING			PIPING SIZE		ELEC	PHYSICAL DIMENSIONS							
						OUTSIDE TEMP	INDOOR DB TEMP	INDOOR WB TEMP	TOTAL BTUH	SENSIBLE BTUH	OUTSIDE TEMP	INDOOR DB TEMP	TOTAL BTUH	RS DIA	RL DIA	DRAIN DIA	V/PH/HZ	POWER CONSUMPTION	WEIGHT (LB)	WIDTH (IN)	LENGTH (IN)		HEIGHT (IN)
FC-1	mitsubishi	PKA-A18HA4	1.5	ELEC 215	420	95	80	67	18,000	10,400	15	59	13,500	1/2"	1/4"	5/8"	208/1/60	FROM CU-1	29	36	10	12	FURNISH W/ WIRED 7-DAY PROG T'STAT, CONDENSATE PUMP - SAUERMANN MODEL SI3100, CONNECT TO CU-1, R-410A REFRIGERANT, ELEC DISCONNECT BY DIV 26
FC-2	mitsubishi	PKA-A18HA4	1.5	IT 205	420	95	80	67	18,000	10,400	15	59	13,500	1/2"	1/4"	5/8"	208/1/60	FROM CU-2	29	36	10	12	FURNISH W/ WIRED 7-DAY PROG T'STAT, CONDENSATE PUMP - SAUERMANN MODEL SI3100, CONNECT TO CU-2, R-410A REFRIGERANT, ELEC DISCONNECT BY DIV 26

SPLIT SYSTEM OUTDOOR UNITS																	
SYMBOL	MANUFACTURER	MODEL NO.	NOMINAL TON	COOLING		HEATING		ELEC			PHYSICAL DIMENSION				PIPE SIZES		NOTES
				OUTDOOR TEMP	TOTAL BTUH	OUTDOOR TEMP	TOTAL BTUH	V/PH/Hz	MCA	MOCp	WEIGHT (LB)	WIDTH (IN)	LENGTH (IN)	HIGHT (IN)	RS DIA	RL DIA	
CU-1	MITSUBISHI	PUZ-A18NHA4	1.5	95	18,000	15	13,500	208/1/60	13	20	95	12	32	24	1/2"	1/4"	FURNISH W/ LO AMBIENT KIT (HEATING TO 5°F AMBIENT) AND WIND BAFFLE, INTERLOCK W/ FC-1
CU-2	MITSUBISHI	PUZ-A18NHA4	1.5	95	18,000	15	13,500	208/1/60	13	20	95	12	32	4	1/2"	1/4"	FURNISH W/ LO AMBIENT KIT (HEATING TO 5°F AMBIENT) AND WIND BAFFLE, INTERLOCK W/ FC-2

HYDRAULIC SEPARATOR								
SYMBOL	MANUFACTURER & MODEL NO.	LOCATION	SERVICE	MAX WATER FLOW (GPM)	DESIGN WATER FLOW (GPM)	WATER TEMP. (DEG F)	PIPE CONNECTION (IN)	WEIGHT (LBS)
HS-1	SPIROVENT QUAD VDX250	BOILER ROOM	HEATING WATER SYSTEM	90	65	140	3"	70

KITCHEN HOOD												
SYMBOL	MANUFACTURER	MODEL NO.	LOCATION	FLUE	CFM @ 0.0"	CFM @ 0.1"	CFM @ 0.2"	CFM @ 0.3"	HOOD DIMENSION	ELEC INFO		NOTE
										V/PH/Hz	AMP	
HD-1	VENT-A-HOOD	EPH18 - PREMIER MAGIC LUNG WALL MOUNTED	KITCHEN	8" DIA	600	531	480	430	36"x24"x18"	115/1/60	4.0	STAINLESS STEEL FINISH, 12"x12" DUCT COVER

GRILLES AND DIFFUSERS									
SYMBOL	MANUFACTURER & MODEL NO.	TYPE	FRAME STYLE	FACE DIMENSIONS (INCH)	NECK DIMENSIONS (INCH)	CFM RANGE	T.P. (IN. W.G.)	MAX NC	NOTES
SD-1	PRICE SCDA, TYPE 3	SUPPLY DIFFUSER	LAY-IN CEILING	12x12, 24x24	6	91-130	0.02-0.06	24	
	PRICE SCDA, TYPE 3	SUPPLY DIFFUSER	LAY-IN CEILING	12x12, 24x24	8	131-210	0.02-0.06	28	
	PRICE SCDA, TYPE 3	SUPPLY DIFFUSER	LAY-IN CEILING	24x24	10	211-330	0.03-0.06	30	
	PRICE SCDA, TYPE 3	SUPPLY DIFFUSER	LAY-IN CEILING	24x24	12	331-430	0.03-0.06	30	
	PRICE SCDA, TYPE 3	SUPPLY DIFFUSER	LAY-IN CEILING	24x24	14	431-530	0.04-0.06	30	
SD-2	PRICE SCDA, TYPE 3	SUPPLY DIFFUSER	LAY-IN CEILING	24x24	15	531-630	0.03-0.06	30	
	PRICE SCDA, TYPE 1	SUPPLY DIFFUSER	FIXED CEILING	12x12, 24x24	6	91-130	0.02-0.09	30	
	PRICE SCDA, TYPE 1	SUPPLY DIFFUSER	FIXED CEILING	12x12, 24x24	8	131-210	0.02-0.09	30	
	PRICE SCDA, TYPE 1	SUPPLY DIFFUSER	FIXED CEILING	24x24	10	211-330	0.02-0.08	30	
	PRICE SCDA, TYPE 1	SUPPLY DIFFUSER	FIXED CEILING	24x24	12	331-430	0.02-0.08	30	
	PRICE SCDA, TYPE 1	SUPPLY DIFFUSER	FIXED CEILING	24x24	14	431-530	0.03-0.08	30	
SR-1	PRICE 520	SIDEWALL SUPPLY	FLAT MARGIN	SEE PLAN	SEE PLANS	SEE PLANS	0.03-0.06	26	
RG-1	PRICE 80	RETURN GRILLE	LAY-IN CEILING	24x24, 24x12, 12x12	SEE PLANS	-	N/A	N/A	
RG-2	PRICE 80	RETURN GRILLE	FIXED CEILING	24x24, 24x12, 12x12	SEE PLANS	-	N/A	N/A	
RR-1	PRICE 530	RETURN GRILLE	SIDEWALL	SEE PLAN	SEE PLANS	-	N/A	N/A	
EG-1	PRICE 80	EXHAUST GRILLE	LAY-IN CEILING	24x24, 24x12, 12x12	SEE PLANS	SEE PLANS	0.01-0.08	25	
EG-2	PRICE 80	EXHAUST GRILLE	FIXED CEILING	24x24, 24x12, 12x12	SEE PLANS	SEE PLANS	0.01-0.08	25	
ER-1	PRICE 80	EXHAUST GRILLE	SIDEWALL	SEE PLAN	SEE PLANS	-	N/A	N/A	

fbt | architects

MAIL: 6501 Americas Pkwy NE., Ste. 300
Albuquerque, NM 87110

PHO: 505.883.5200
FAX: 505.884.5390
WEB: www.fbtarch.com

CONSULTANT

B **BRIDGERS
& PAXTON**

4600 C Montgomery Blvd. NE
Albuquerque, NM 87109 | 505.883.4111 | www.bpcce.com

**Dzilth-Na-O-Dith-Hle - New
Dormitory Building**

**CONSTRUCTION
DOCUMENTS**

35 Road 7585, Bloomfield, NM
87413

DECEMBER 4, 2020

MARK	DATE	DESCRIPTION
ISSUE:		
DATE:		
PROJECT NO:		751
CAD DWG FILE:		
DRAWN BY:		NZ
CHECKED BY:		IM

SHEET TITLE
MECHANICAL SCHEDULES

M-702

NOTE:
ALL EQUIPMENT SELECTIONS ARE BASED AT AN
ELEVATION OF 5,400 FEET ABOVE SEA LEVEL

[illegible]










VFD'S SHALL BE CONNECTED TO THE FMS NETWORK THROUGH A DIRECT NETWORK CONNECTION AS WELL AS THROUGH THE HARDWIRED POINTS INDICATED. IT IS THE RESPONSIBILITY OF THE FMS CONTRACTOR TO COORDINATE AND ADAPT THE FMS NETWORK TO THE COMMUNICATIONS PROTOCOLS AVAILABLE FROM THE VFD MANUFACTURER. THE FOLLOWING POINTS SHALL BE INTEGRATED INTO THE FMS:

- A. SPEED FEEDBACK
- B. FREQUENCY OUTPUT
- C. CURRENT
- D. TORQUE
- E. POWER
- F. DC BUS VOLTAGE
- G. OUTPUT VOLTAGE
- H. KWH COUNTER
- I. DRIVE TEMPERATURE
- J. ALARMS
- K. STATUSES

PROVIDE A MINIMUM OF ONE STATIC PRESSURE PROBE PER FLOOR FOR EACH AIR HANDLING UNIT. LOCATE THE STATIC PRESSURE PROBES $\frac{1}{8}$ THE LENGTH OF THE MAIN DUCT RUN.

PROVIDE FIELD INSTALLATION OF ALL SENSORS, SAFETIES, AND VALVES FURNISHED WITH THE CONDENSING UNIT IN ACCORDANCE WITH THE MANUFACTURER'S INSTALLATION INSTRUCTIONS. PROVIDE AN FMS START/STOP POINT FOR EACH COOLING STAGE IN THE CONDENSING UNIT.



MI601



- KEYED NOTES
- 

1. THE BOILER SYSTEM SHALL BE CONNECTED TO THE FMS NETWORK THROUGH A DIRECT MODBUS OR BACNET NETWORK CONNECTION AS INDICATED. THE FOLLOWING POINTS SHALL BE INTEGRATED INTO AND MONITORED BY THE FMS IF AVAILABLE FROM THE MANUFACTURER:
 - A. SYSTEM ENABLE/DISABLE COMMAND
 - B. OPERATING FIRING RATE
 - C. RUNTIME STATUS
 - D. SYSTEM ALARMS
 - E. PUMP ON/OFF COMMANDED STATUSES
 - F. BOILER OUTLET TEMPERATURE SETPOINT
 - G. BOILER OUTLET TEMPERATURE
 - H. BOILER INLET TEMPERATURE
 - I. SYSTEM HOT WATER SUPPLY SETPOINT COMMAND
 - J. SYSTEM HOT WATER SUPPLY TEMPERATURE
 - K. SYSTEM HOT WATER RETURN TEMPERATURE
2. VFD'S SHALL BE CONNECTED TO THE FMS NETWORK THROUGH A DIRECT NETWORK CONNECTION AS WELL AS THROUGH THE HARDWIRED POINTS INDICATED. IT IS THE RESPONSIBILITY OF THE FMS CONTRACTOR TO COORDINATE AND ADAPT THE FMS NETWORK TO THE COMMUNICATIONS PROTOCOLS AVAILABLE FROM THE VFD MANUFACTURER. THE FOLLOWING POINTS SHALL BE INTEGRATED INTO THE FMS:
 - A. SPEED FEEDBACK
 - B. FREQUENCY OUTPUT
 - C. CURRENT
 - D. TORQUE
 - E. POWER
 - F. DC BUS VOLTAGE
 - G. OUTPUT VOLTAGE
 - H. KWH COUNT
 - I. DRIVE TEMPERATURE
 - J. ALARMS
 - K. STATUSES

<p>Programming The FMS shall be programmed according to the following sequence of operations including all energy reduction operations described in this sequence and in the project specifications.</p> <p>System Status Display The FMS shall provide operating status for all systems controlled by the FMS. The displays shall include all points indicated on the drawings and any others required to achieve the sequence of operations. The FMS shall be able to integrate system diagnostics into control action decisions. This shall also include the ability to designate individual units as being in maintenance mode to avoid generating alarms. All system control and status events shall be recorded, at the operator's selection, in the FMS event log to facilitate troubleshooting. All detected alarms or failures shall initiate an alarm within the FMS.</p> <p>Power Failure Recovery The FMS shall contain a power failure recovery mode (operator adjustable). The power failure recovery capability shall return the system to its last state (before the building lost power). Refer to power system recovery sequence for more details.</p> <p>Occupancy Control The FMS shall be setup with an occupancy schedule for different areas of the building. The owner shall be interviewed by the contractor at start-up to establish these schedules. Some areas of the building shall be setup to be continuously occupied.</p> <p>Emergency Outdoor Air Override The FMS shall have an emergency outdoor air override switch on the main graphic at the operator workstation which will allow the operator to shutdown the outside air intake dampers and relief dampers for all air handling units in the event that toxic odors are detected outside. When the outside air and relief dampers fully close, the return air damper shall fully open. The outside air intake dampers for all units shall remain closed until the operator resets the override</p> <p>Air Handlinging Unit AHU-1 Minimum Outside Air Setpoint Control The FMS shall monitor the CO2 level in the spaces throughout the building in locations indicated on the mechanical floor plans. The time based average for each CO2 sensor shall be calculated in an interval of 20 minutes (adjustable). The calculated value shall be used for control. In the event any of the CO2 levels rise above setpoint in accordance with ASHRAE 62.1 guidelines, the FMS shall first gradually increase the flowrate of the terminal unit to induce additional outside air into the space. If the terminal unit reaches its maximum airflow setpoint and the CO2 level is still not below setpoint, the FMS shall reset the minimum outside air volume setpoint for the associated unit to induce more outside air. The minimum outside air volume setpoint shall be reset between the scheduled minimum and maximum setpoints. The FMS shall initiate an alarm if the concentration levels rise 20% (adjustable) above setpoint. The FMS shall trend all carbon dioxide levels measured.</p> <p>Minimum Outside Air Control The minimum outside air volume shall be controlled by the FMS through the outside air flow measuring damper which measures the outside air volume. The FMS shall not modulate the outside air damper below minimum outside air volume setpoint. If the air handling unit is stopped, the FMS shall close the damper. The FMS shall trend and log the outside air volume being brought in by the air handling unit. If the outside air volume falls below 85% of the setpoint for a period of 10 minutes, the FMS shall initiate an alarm.</p> <p>Mixed Air Damper Interlocks The FMS shall control the FMS system shall modulate the mixed air dampers. Upon initial start-up, the FMS system shall not begin modulation of the mixing dampers for five minutes (adjustable) to allow the control loops to stabilize.</p> <p>Supply Air Temperature Control - Heating The FMS shall control the air handling unit to maintain an adjustable supply air temperature setpoint. The temperature setpoint shall be reset based on the demand of the terminal units served by it so that at least one terminal unit is 90% open and still maintaining the room temperature setpoint. The reset range shall be between 55°F and 85°F (adjustable) drybulb. The demand for the direct/indirect (DI) section of the air handling unit shall be 2°F (adjustable) less than the supply air temperature setpoint. Wet bulb temperatures shall be calculated using dry bulb temperature and relative humidity levels.</p> <p>Supply Air Temperature Control - Cooling If the system requires cooling to maintain the supply air temperature at setpoint, the FMS shall control the unit through the following four stages.</p> <p>Stage 1: If the outside air temperature is less than the supply air temperature the FMS shall modulate the outside air and return air dampers to maintain the DI section supply temperature at setpoint. The direct and indirect cooling pumps shall be off.</p> <p>Stage 2: If the DI section setpoint cannot be maintained at setpoint with Stage 1, the FMS shall start Stage 2. The FMS shall start the indirect cooling pump and modulate the outside air and return air dampers to maintain the DI section supply temperature at setpoint. As more cooling is required, the FMS shall increase the amount of outside air being brought into the unit. If the cooling demand decreases and the outside air temperature falls below the return air temperature such that Stage 1 can meet the demand, the FMS shall stop Stage 2. The FMS shall monitor the status of the indirect pump through a current switch installed on the motor. If a pump failure occurs, the FMS shall initiate an alarm and remove Stage 2 from the staging control sequence. Once the pump is fixed and the alarm condition is cleared, Stage 2 control shall be reinserted into the staging control sequence.</p> <p>Stage 3: If the DI section setpoint cannot be maintained at setpoint with Stage 2, the FMS shall start Stage 3. If the outside air wetbulb temperature is less than the supply air temperature setpoint minus a 4°F (adjustable) offset, the FMS shall start the direct cooling pump. The FMS shall start the direct cooling pump. The FMS shall fully open the outside air dampers and close the return air dampers. If the cooling demand decreases such that Stage 2 can meet the demand, or if the return humidity level rises above 60% RH (adjustable), the FMS shall stop Stage 3. The FMS shall monitor the status of the direct pump through a current switch installed on the motor. If a pump failure occurs, the FMS shall initiate an alarm and remove Stage 3 from the staging control sequence. Once the pump is fixed and the alarm condition is cleared, Stage 3 control shall be reinserted into the staging control sequence. The indirect section shall continue to operate during Stage 3 operation.</p> <p>Stage 4: If the DI section setpoint cannot be maintained at setpoint with Stage 3 or if the outside air wetbulb temperature is not within the range specified, the FMS shall start stage 4. The FMS shall stop the direct cooling pump. The indirect section shall continue to operate during Stage 4 operation. The FMS shall stage the condensing unit to maintain the supply air temperature at setpoint. As the cooling demand decreases and the condensing unit is staged off, the FMS shall return to Stage 3 if the conditions of Stage 3 can be reached. Once Stage 4 is started, it shall operate for a minimum of one hour (adjustable) before the system can switch back to Stage 3 to prevent short cycling of the system.</p> <p>Supply Air Temperature Control - Heating If the system requires heating to maintain the supply air temperature at setpoint, the FMS shall position the outside air and return air dampers to the minimum outside air setpoint. The FMS shall modulate the hot water coil valve to maintain the supply air temperature setpoint. The direct and indirect pumps shall be off and chilled water coil valve shall be closed.</p> <p>Hot Water Coil Pump The FMS shall operate the hot water coil pump anytime the outside air temperature is below 35°F (adjustable) when the unit is operating. The FMS shall monitor the status of the pump through a current switch installed on the motor. If a pump failure is detected, the FMS shall initiate an alarm.</p> <p>Supply Air Static Setpoint Control The FMS shall reset the static pressure setpoint using a trim and respond logic within the range of 0.5" w.g. to 1.5" w.g. When the fan is off, the setpoint shall be 1.0" w.g. Once the fan is started, the setpoint shall be trimmed by 0.04" w.g. every two minutes if there are two or fewer zone pressure requests. If there are more than two zone pressure requests, respond by increasing the setpoint by 0.06" w.g. A zone pressure request is generated when a VAV damper is greater than 95% open until it drops to 80% open. All setpoints shall be adjustable through the operator workstation.</p> <p>Supply Fan Control The supply fan VFD shall be started and stopped by the FMS system based on an occupancy schedule for the building programmed into the FMS. The fan shall operate continuously during occupied periods. If during unoccupied periods, any of the space temperatures rise above the unoccupied cooling setpoint or fall below the unoccupied heating setpoint, the air handling unit shall start and operate to raise the space temperature 2°F (adjustable) before stopping. If during unoccupied periods, any of the space occupancy switches are activated, the air handling unit shall start and operate for a period of two hours before stopping.</p> <p>Supply Fan VFD Control The VFD shall be modulated to maintain the supply duct static pressure at a set point. The ramp of the VFD shall be adjusted to restrict the rate of change of the VFD output to sixty seconds for a zero to one hundred percent control signal change.</p> <p>Supply Fan Monitoring The VFD operation shall be indicated to the FMS through a set of contacts in the VFD. If an alarm condition is detected, the FMS shall initiate an alarm.</p> <p>Relief Fan VFD Control The FMS shall modulate the relief fans to maintain the building differential pressure measured in the space and the outside air pressure at a positive space pressure of 0.05" w.c. (adjustable) anytime the air handling unit is operating. The ramp of the VFD shall be adjusted to restrict the rate of change of the VFD output to sixty seconds for a zero to one hundred percent control signal change.</p> <p>Relief Fan Monitoring The VFD operation shall be indicated to the FMS through a set of contacts in the VFD. If an alarm condition is detected, the FMS shall initiate an alarm.</p> <p>Filter Monitoring The differential pressure across the filter shall be monitored by the FMS through a differential pressure transmitter. If the differential pressure exceeds set point, the FMS shall initiate an alarm.</p> <p>Freeze/ast A freeze/ast set at 35°F located downstream of the hot water coil shall initiate an alarm at the FMS and stop the supply fan, start the hot water coil pump, and open the hot water valve if an alarm condition is detected.</p> <p>Smoke Detectors Smoke detectors located in the supply air and return air streams, shall stop the fans through the fire alarm system if an alarm condition is detected. When the fans are stopped, the FMS shall position the dampers to their normal state.</p> <p>Duct Pressure Safety Switches Safety switches installed in the supply and return air ducts for each unit shall alarm the FMS if the duct pressure is above the high alarm setpoint. The high alarm setpoint shall be 150% of the normal operating static of the system. If the FMS senses an alarm condition, the FMS shall stop the supply and return fans.</p> <p>Start/Stop Optimization and Morning Warm-Up The FMS shall be programmed with a self-adjusting start/stop optimization sequence which shall provide the optimum start time for the unit in order to have the space temperature at the occupied setpoint when scheduled occupancy is to occur each day. If the spaces require heating to reach the occupied space temperature setpoints, the FMS shall operate the unit using a morning warm-up cycle. During the morning warm-up cycle, the unit shall operate with the outside air and relief air damper closed with the return air damper fully open. The FMS shall raise supply air temperature setpoint to the heating maximum temperature and operate the hot valve to maintain the supply air temperature at setpoint. Once the space temperature occupied setpoints are reached, the unit shall return to normal occupied control. During morning warm-up, the terminal units shall operate at their maximum airflow setpoints until their space temperature setpoints are reached. Terminal units which do not require heating or have reached their occupied setpoints, shall operate with their dampers closed.</p> <p>Variable Air Volume Terminal Units w/ Hot Water Reheat Each terminal unit shall modulate the supply air damper to maintain the space temperature conditions. If the zone requires cooling, the supply air damper shall be modulated between the minimum and maximum cooling air flows to maintain the space temperature at the cooling setpoint of 76 °F (adjustable) for occupied periods and 85°F (adjustable) during unoccupied periods. If the zone calls for heating, the supply air damper shall be modulated to maintain the space temperature at the heating setpoint of 72°F (adjustable) for occupied periods and 55°F for unoccupied periods. If additional heating is required when the valve is fully open, the supply air damper shall be modulated to meet the room temperature requirements. If during an unoccupied period the space occupancy switch is activated, the space shall return to the occupied setpoints for a period of two hours before switch back to the unoccupied state.</p> <p>General Exhaust Fans Exhaust Fan Control Each fan shall operate based on the occupancy schedule in the FMS. The fan shall operate continuously during occupied periods.</p> <p>Exhaust Fan Monitoring The fan operation shall be indicated to the FMS through a current switch installed in the motor starter. If a fan failure is detected, the FMS shall stop the fan and initiate an alarm</p> <p>Exhaust Fan Isolation Damper Control Each exhaust fan damper shall be open anytime the fan is operating. If the fan is stopped, the damper shall close.</p> <p>Typical Split System Each unit shall be provided with a factory packaged control system which shall control the unit to maintain the space temperature at setpoint. The FMS shall monitor the space temperature through a separate space temperature sensor and shall initiate an alarm if the space temperature rises above the space high temperature alarm setpoint.</p> <p>Domestic Hot Water Pump Pump Control Each pump shall operate based on the occupancy schedule in the FMS. The pump shall operate continuously during occupied periods.</p> <p>Pump Monitoring The pump operation shall be indicated to the FMS through a current switch installed in the motor starter. If a pump failure is detected, the FMS shall stop the pump and initiate an alarm.</p>	<p>Hot Water Plant Control Boiler Plant Enable The FMS shall enable the boiler plant through a user input from the operator workstation or anytime the building requires heat. The lead boiler shall operate whenever the boiler water plant is enabled.</p> <p>Hot Water Temperature Control The FMS shall monitor the alarm and status conditions of each boiler through the BACnet network connection. Upon sensing a boiler failure, the FMS shall initiate an alarm. The next boiler in the sequence shall be enabled (if the boiler fails while running or trying to start). The failed boiler shall be disabled.</p> <p>Boiler Control The boiler control system shall control individual stages of each boiler to maintain the secondary hot water supply temperature at setpoint based on the factory recommended staging configuration.</p> <p>Boiler Rotation Automatic rotation of the boilers sequence shall be allowed based on the manufacturer's standard rotation sequence. The boiler control panel shall start the associated boiler pump anytime the boiler is enabled.</p> <p>Boiler Failure Detection and Recovery The FMS shall monitor the status of each primary pump through a current switch installed in the motor starter and the commanded status of the pump through the Modbus network connection. Upon a primary pump failure, the FMS shall initiate an alarm.</p> <p>Secondary Hot Water Differential Pressure Setpoint Control The FMS shall reset the system differential pressure setpoint using a trim and respond logic within the range of 5 psig to 15 psig once the minimum hot water temperature setpoint is reached. Once the setpoint is reached, the differential pressure setpoint for the controlling zone shall be trimmed by 0.1 psig every two minutes until a valve in the system is 50% open. When a valve in the system rises to 50% open, the differential pressure setpoint for the controlling zone shall be increased by 0.1 psig every two minutes. All setpoints shall be adjustable through the operator workstation for each differential pressure setpoint.</p> <p>Secondary Hot Water Pump Control Each set of secondary hot water pumps shall operate in a lead/lag configuration. The lead pump shall operate anytime the hot water system is enabled. The FMS shall modulate the pumps to maintain differential pressure at setpoint as measured by differential pressure sensors. With just the lead pump operating, if the speed of the pump reaches 100%, the FMS shall start the lag pump and operate at the same speed to maintain the differential pressure setpoint. With both pumps operating, if the speed of the pumps falls below 40%, the FMS shall stop the lag pump and operate the lead pump</p>
--	---

fbt architects		
MAIL: 6501 Americas Pkwy NE, Ste. 300 Albuquerque, NM 87110	PHO: 505.883.5200 FAX: 505.884.5390 WEB: www.fbtarch.com	
CONSULTANT		
<div>BRIDGERS & PAXTON</div> <div>4600 C Montgomery Blvd. NE Albuquerque, NM 87109 505.883.4111 www.bpcce.com</div>		
<div></div> <div>ENGINEER</div>		
Dzilh-Na-O-Dith-Hle - New Dormitory Building		
CONSTRUCTION DOCUMENTS		
35 Road 7585, Bloomfield, NM 87413		
DECEMBER 4, 2020		
MARK	DATE	DESCRIPTION
ISSUE:		
DATE:		
PROJECT NO:		751
CAD DWG FILE:		
DRAWN BY:		NZ
CHECKED BY:		IM
SHEET TITLE		
MECHANICAL CONTROLS DIAGRAMS		
MI603		

GENERAL NOTES

A. COMPLY WITH NFPA 70, 2017 ED. AND NFPA 72 2016 ED.

KEYNOTES

- REFER TO SHEET E-002 FOR MOUNTING HEIGHTS FOR DEVICES. SOME DEVICES WILL REQUIRE FIELD COORDINATION PRIOR TO ROUGH-IN BY CONTRACTOR TO ENSURE ADEQUATE MOUNTING FOR EACH DEVICE TYPE.
- REFER TO ARCHITECTURAL DETAILS, ELEVATIONS BOTH INTERIOR AND EXTERIOR FOR MOUNTING HEIGHTS. HEIGHTS MAY VARY DEPENDING ON LOCATION OF DEVICE. REFER TO SHEET E-701 FOR MINIMUM MOUNTING INFORMATION AND SHEET SERIES "EL" FOR ADDITIONAL INFORMATION.

ELECTRICAL SYMBOL LEGEND (NOT ALL SYMBOLS APPLY TO THIS PROJECT)


UPDATED: 09/07/2016

ABBREV.	DEFINITION
A	AMPS, AMPERE, AMPERAGE
AC	ABOVE COUNTER
A/C	ALTERNATING CURRENT
ADA	AMERICANS WITH DISABILITIES ACT
AFF	ABOVE FINISHED FLOOR
AFG	ABOVE FINISHED GRADE
AIC	AVAILABLE INTERRUPTING CURRENT
AL	ALUMINUM
ANSI	AMERICAN NATIONAL STANDARDS INSTITUTE
ATSC	AUTOMATIC TRANSFER SWITCH CONTROL
ATS	AUTOMATIC TRANSFER SWITCH
AVG	AUDIO/VISUAL
AWG	AMERICAN WIRE GAUGE
C	CONDUIT
CB	CIRCUIT BREAKER
CCTV	CLOSED CIRCUIT TELEVISION
CKT	CIRCUIT
CL	CLOCK
CLF	CURRENT LIMITING FUSE
CO	CONDUIT ONLY
CU	COPPER
D	DIMMING
DC	DIRECT CURRENT
DL	DAY-LIGHTING
DIA	DIAMETER
E	EMERGENCY
EC	EMERGENCY, CRITICAL
EG	ENGINE GENERATOR
EL	EMERGENCY, LIFE SAFETY
EQ	EMERGENCY, EQUIPMENT
EX	EXISTING
FUT	FUTURE
FA	FIRE ALARM
FAACP	FIRE ALARM ANNUNCIATOR
FATC	FIRE ALARM CONTROL PANEL
FDR	FIRE ALARM TERMINAL CABINET
FMS	FACILITY MANAGEMENT SYSTEM
GEN	GENERATOR
GFI	GROUND FAULT INTERRUPTER
G OR GFCI	GROUND FAULT CIRCUIT INTERRUPTER
GFEP	GROUND FAULT EQUIPMENT PROTECTION
GFP	GROUND FAULT PROTECTION
GND	GROUND
HQA	HAND-OFF-AUTOMATIC
HP	HORSEPOWER
IEEE	INSTITUTE OF ELECTRICAL AND ELECTRONICS ENGINEERS
IG	ISOLATED GROUND
KCMIL	THOUSAND CIRCULAR MILS
KV	KILOVOLT
KVA	KILOVOLT AMPS
KVAR	KILOVOLT AMPS REACTIVE
KW	KILOWATT
KWH	KILOWATT HOUR
LSIG	LONG TIME, SHORT TIME, INSTANTANEOUS, AND GROUND FAULT PROTECTION
MAX	MAXIMUM
MCC	MOTOR CONTROL CENTER
MH	MANHOLE
MIN	MINIMUM
MM	MIXED MEDIA
MTS	MANUAL TRANSFER SWITCH
MVA	MEGAVOLT AMPS
N	NEW
N/A	NOT APPLICABLE
NC	NORMALLY CLOSED
NEC	NATIONAL ELECTRICAL CODE
NEMA	NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION
NEUT	NEUTRAL
NFPA	NATIONAL FIRE PROTECTION ASSOCIATION
NIC	NOT IN CONTRACT
NL	NORMAL
NM	NEW MEXICO
NO	NORMALLY OPEN
OH	OVERHEAD
P	POLE
PA	PUBLIC ADDRESS
PC	PHOTOCELL
PH	PHASE
PMCS	POWER MONITORING AND CONTROL SYSTEM
R	REMOVED/REMOVAL
RC	ROOM CONTROLLER
RSC	RIGID STEEL CONDUIT
SEC	SECURITY
SPD	SURGE PROTECTIVE DEVICE
SW	SWITCH
TEMP	TEMPORARY
TTB	TELEPHONE TERMINAL BOARD
TV	TELEVISION
TVSS	TRANSIENT VOLTAGE SURGE SUPPRESSOR
TYP.	TYPICAL
UC	UNDER COUNTER
UG	UNDERGROUND
UGE	UNDERGROUND ELECTRIC
UL	UNDERWRITERS' LABORATORIES
UON	UNLESS OTHERWISE NOTED
UPS	UNINTERRUPTIBLE POWER SUPPLY
V	VOLTS, VOLTAGE
VFD	VARIABLE FREQUENCY DRIVE
W	WALL MOUNTED
WG	WEATHERPROOF AND GFCI
WP	WEATHERPROOF
XFER	TRANSFER
XFMR (TRANSF)	TRANSFORMER

REFERENCE TAGS

SYMBOL	DEFINITION
○	KEYED NOTE REFERENCE
VAV-9	MECHANICAL EQUIPMENT REFERENCE
+44"	DENOTES MOUNTING HEIGHT AFF
□	KITCHEN EQUIPMENT REFERENCE
○	MEDICAL EQUIPMENT REFERENCE


EQUIPMENT NAMING CONVENTION



RACEWAY & CONDUCTORS

SYMBOL	DESCRIPTION
↑ = GROUND = HOT/PHASE = NEUTRAL ? = SWITCH LEG	CONDUCTOR IDENTIFICATION SYMBOLS. REFER TO PLANS FOR COMBINATION USE. CONDUCTOR IDENTIFICATION MOSTLY USED IN HOMERUN LOCATION, BUT CAN ALSO BE USED IN BRANCH CIRCUITING WHERE APPLIED. GROUND CONDUCTORS WILL BE INSTALLED IN ALL RACEWAYS WHETHER SHOWN OR NOT.
LA-1	HOMERUN FROM EQUIPMENT LOCATION. THE CIRCUIT NUMBER ADJACENT TO HOMERUN INDICATES PANEL SOURCE AND INDIVIDUAL SINGLE POLE CIRCUIT BREAKER(S). CONDUCTOR IDENTIFICATION SYMBOL INDICATES NUMBER OF CONDUCTORS IN HOMERUN. MINIMUM #12 CONDUCTORS AND 3/4" RACEWAY PATH WILL BE PROVIDED IN HOMERUN UON. ALL HOMERUNS WILL INCLUDE GROUND CONDUCTOR.
LA-1,3	HOMERUN FROM EQUIPMENT LOCATION. THE CIRCUIT NUMBER ADJACENT TO HOMERUN INDICATES PANEL SOURCE AND INDIVIDUAL SINGLE POLE CIRCUIT BREAKER(S). SYMBOL REPRESENTS A MULTI-BRANCH CIRCUIT. NUMBER OF CONDUCTORS IN HOMERUN WILL INCLUDE A SEPARATE NEUTRAL FOR EACH CIRCUIT PHASE CONDUCTOR. MINIMUM #12 CONDUCTORS AND 3/4" RACEWAY PATH WILL BE PROVIDED IN HOMERUN UON. ALL HOMERUNS WILL INCLUDE GROUND CONDUCTOR.
LA-5,7,9	HOMERUN FROM EQUIPMENT LOCATION. THE CIRCUIT NUMBER ADJACENT TO HOMERUN INDICATES PANEL SOURCE AND INDIVIDUAL SINGLE POLE CIRCUIT BREAKER(S). CONDUCTOR IDENTIFICATION SYMBOL INDICATES NUMBER OF CONDUCTORS IN HOMERUN. MINIMUM #12 CONDUCTORS AND 3/4" RACEWAY PATH WILL BE PROVIDED IN HOMERUN UON. ALL HOMERUNS WILL INCLUDE GROUND CONDUCTOR.
LA-1,3	HOMERUN FROM EQUIPMENT LOCATION. THE CIRCUIT NUMBER ADJACENT TO HOMERUN INDICATES PANEL SOURCE AND INDIVIDUAL TWO OR THREE POLE CIRCUIT BREAKERS. CONDUCTOR IDENTIFICATION SYMBOL INDICATES NUMBER OF CONDUCTORS IN HOMERUN. MINIMUM #12 CONDUCTORS AND 3/4" RACEWAY PATH WILL BE PROVIDED IN HOMERUN UON. ALL HOMERUNS WILL INCLUDE GROUND CONDUCTOR.
LA-5,7,9	HOMERUN FROM EQUIPMENT LOCATION. THE CIRCUIT NUMBER ADJACENT TO HOMERUN INDICATES PANEL SOURCE AND INDIVIDUAL TWO OR THREE POLE CIRCUIT BREAKERS. CONDUCTOR IDENTIFICATION SYMBOL INDICATES NUMBER OF CONDUCTORS IN HOMERUN. MINIMUM #12 CONDUCTORS AND 3/4" RACEWAY PATH WILL BE PROVIDED IN HOMERUN UON. ALL HOMERUNS WILL INCLUDE GROUND CONDUCTOR.
DOWN UP	CONDUIT STUBBED AND CAPPED
B	BUSWAY
G	GROUNDING CONDUCTOR
PHASE	CABLE TRAY - POWER AND TELECOMMUNICATIONS
T	TELECOMMUNICATIONS RACEWAY
D	DATA RACEWAY
VID	VOICE/DATA COMBINATION RACEWAY
FA	FIRE ALARM RACEWAY

GENERAL DRAWING SYMBOLS



DEMOLITION

SYMBOL	DESCRIPTION	NOTES
○	DASHED SYMBOL INDICATES EXISTING DEVICE OR EQUIPMENT TO BE REMOVED	REFER TO DEMOLITION PLANS FOR ADDITIONAL INFORMATION
R	REMOVE EXISTING RACEWAY IN ALL ACCESSIBLE AREAS. CAPPED AND ABANDONED IF IN UNACCESSIBLE AREA	
○	SOLID SYMBOL, LIGHTER IN COLOR INDICATES EXISTING DEVICE OR EQUIPMENT TO REMAIN	
EX	EXISTING CONDUIT TO BE REUSED	

DEVICES

SYMBOL	DESCRIPTION	MOUNTING LOC.	HT.
○	BLANK FOR NORMAL POWER G = GFCI RATED IG = ISOLATED GROUND T = TAMPERPROOF WG = WEATHERPROOF AND GFCI WP = WEATHERPROOF (IN-USE COVER) CL = CLOCK TV = TELEVISION		
○	IN FLOOR DUPLEX RECEPTACLE. CONFIGURATION AS INDICATED ON PLANS	FLOOR	VARIES
○	IN FLOOR DOUBLE DUPLEX (QUADPLEX) RECEPTACLE. CONFIGURATION AS INDICATED ON PLANS		
○	IN FLOOR EMERGENCY DUPLEX RECEPTACLE. CONFIGURATION AS INDICATED ON PLANS		
○	IN FLOOR EMERGENCY DOUBLE DUPLEX (QUADPLEX) RECEPTACLE. CONFIGURATION AS INDICATED ON PLANS		
○	COMBINATION DUPLEX RECEPTACLE AND COMMUNICATIONS FLOORBOX. DEVICE CONFIGURATION AS INDICATED ON PLANS.		
○	CEILING MOUNTED DUPLEX RECEPTACLE		
○	CEILING MOUNTED DOUBLE DUPLEX (QUADPLEX) RECEPTACLE		
○	CEILING MOUNTED EMERGENCY DUPLEX RECEPTACLE	CEILING	FLUSH
○	CEILING MOUNTED EMERGENCY DOUBLE DUPLEX (QUADPLEX) RECEPTACLE		
○	COMBINATION POWER/COMMUNICATION IN CEILING OUTLET. CONFIGURATION AS INDICATED ON PLANS		
○	SIMPLEX RECEPTACLE		
○	DUPLEX RECEPTACLE		
○	DOUBLE DUPLEX (QUADPLEX) RECEPTACLE	WALL, UON	
○	EMERGENCY DUPLEX RECEPTACLE		
○	EMERGENCY DOUBLE DUPLEX (QUADPLEX) RECEPTACLE		
○	SPECIAL PURPOSE RECEPTACLE. NEMA CONFIGURATION AND AMPERAGE AS NOTED ON PLANS		
○	MULTI-OUTLET ASSEMBLY (SURFACE MOUNTED RACEWAY)	VARIES SEE PLANS	VARIES SEE PLANS
○	COMBINATION POWER/COMMUNICATION POLE. CONFIGURATION AS NOTED ON PLANS		
○	WALL MOUNTED CODE SIZE J-BOX		
○	CODE SIZE JUNCTION BOX	VARIES SEE PLANS	VARIES SEE PLANS
○	CODE SIZE PULLBOX (OR AS SIZED ON PLAN)		
○	PUSHBUTTON (EMERGENCY POWER OFF - EPO)		
○	PHOTOCELL		
○	LIGHTNING PROTECTION AIR TERMINAL	ROOF	
○	THERMOSTAT	WALL	
○	ENCLOSED CIRCUIT BREAKER		
○	AMPERAGE/NEMA ENCLOSURE RATING, 3 POLE UON		
○	NON-FUSED DISCONNECT SWITCH. AMPERAGE/NEMA ENCLOSURE RATING, 3 POLE UON		
○	FUSED DISCONNECT SWITCH. AMPERAGE/NEMA ENCLOSURE RATING, 3 POLE UON		
○	MOTOR STARTER. STARTER SIZE INDICATED BY NUMBER/NEMA ENCLOSURE RATING, SINGLE SPEED UON	VARIES	VARIES
○	COMBINATION FUSIBLE DISCONNECT SWITCH AND MOTOR STARTER. NEMA STARTER SIZE/AMPERAGE/NEMA ENCLOSURE RATING, 3 POLE UON		
○	MOTOR. NUMBER INDICATES HORSEPOWER RATING FOR 1HP AND LARGER	N/A	N/A
○	MOTOR. "F" INDICATES FRACTIONAL HORSEPOWER		

EQUIPMENT

SYMBOL	DESCRIPTION
MSB	MAIN SWITCHBOARD. DASHED LINES INDICATE CLEARANCES.
DB	DISTRIBUTION BOARD OR PANEL. DASHED LINES INDICATE CLEARANCES.
H1A	FLUSH MOUNTED PANELBOARD. DASHED LINES INDICATE CLEARANCES.
L1A	SURFACE MOUNTED PANELBOARD. DASHED LINES INDICATE CLEARANCES.
MCC	MOTOR CONTROL CENTER. DASHED LINES INDICATE CLEARANCES.
T1A	DRY TYPE TRANSFORMER (15kVA OR ABOVE), WITH EQUIPMENT TAG (TAG INSIDE OR OUTSIDE, DEPENDING ON SIZE). IN MOST CASES, ACTUAL SIZE SHOWN ON PLANS (ELECTRICAL ROOMS).
T	DRY TYPE TRANSFORMER (LESS THAN 15kVA), WITH NO EQUIPMENT TAG. SIZE, TYPE AND LOCATION NOTED ON PLANS.
VFD	VARIABLE FREQUENCY DRIVE
UPS-A	UNINTERRUPTIBLE POWER SUPPLY. DASHED LINES INDICATE CLEARANCES.
ATS-1	AUTOMATIC TRANSFER SWITCH. DASHED LINES INDICATE CLEARANCES.
G	GROUND BAR

LIGHTING

SYMBOL	DESCRIPTION	MOUNTING LOC.	HT.
○	HATCHING INDICATES EMERGENCY LIGHTING. HATCH WILL BE MODIFIED FOR EACH LUMINAIRE TYPE. EMERGENCY LUMINAIRE DESIGNATED WITH "E" IN TYPE DESIGNATION.	VARIES	
○	RECESSED MOUNTED LUMINAIRE. SMALL CASE "4" DENOTES SWITCHING, NUMBER "3" DENOTES BRANCH CIRCUITING. SYMBOL "A" DENOTES LUMINAIRE TYPE.	CEILING	
○	SURFACE MOUNTED LUMINAIRE. LUMINAIRE TYPE AS INDICATED ON PLANS		
○	LINEAR DIRECT/INDIRECT LUMINAIRE. CABLE OR STEM MOUNTED		
○	DOWN LIGHT LUMINAIRE. CEILING MOUNTED		
○	WALL MOUNTED LUMINAIRES	WALL	
○	TRACK MOUNTED LUMINAIRES		
○	STRIP LUMINAIRE	SURFACE	
○	EXIT LUMINAIRE. SHADED SIDE INDICATES FACE SIDE. PROVIDE DIRECTIONAL ARROW(S) AS INDICATED ON PLANS	VARIES	
○	DOUBLE FACE EXIT LUMINAIRE. SHADED SIDE INDICATES FACE SIDE. PROVIDE DIRECTIONAL ARROW(S) AS INDICATED ON PLANS		
○	EMERGENCY BATTERY PACK LUMINAIRE (BUG-EYE/FROG-EYE)		
○	SINGLE HEAD, POLE MOUNTED LUMINAIRE	EXTERIOR	AS DETAILED
○	DOUBLE HEAD, POLE MOUNTED LUMINAIRE		
○	DEVICE INDICATOR LETTER. "X" EQUALS DESIGNATION BELOW (TYPICAL FOR MOST SWITCH TYPES): a = SMALL CASE LETTER DENOTES SWITCHING CONTROL 2 = DOUBLE POLE TOGGLE SWITCH 3 = THREE-WAY TOGGLE SWITCH 4 = FOUR-WAY TOGGLE SWITCH P = PILOT LIGHT TOGGLE SWITCH M = MOMENTARY CONTACT SWITCH K = KEY OPERATED SWITCH WP = WEATHERPROOF TOGGLE SWITCH T = MANUAL MOTOR STARTER SWITCH WITH THERMAL OVERLOAD PROTECTION D = DIMMER SWITCH TW = TWIST TIMER SWITCH WALL MOUNTED OCCUPANCY SENSOR; TYPE AS INDICATED ON PLANS	WALL	
○	CEILING MOUNTED OCCUPANCY SENSOR; TYPE AS INDICATED ON PLANS	CEILING	
○	DAY-LIGHTING SENSOR; TYPE AS INDICATED ON PLANS		
○	ROOM CONTROLLER; TYPE AS INDICATED ON PLANS		

UTILITIES

SYMBOL	DESCRIPTION
○	DISTRIBUTION POLE FOR OVERHEAD ELECTRICAL OR COMMUNICATIONS AS INDICATED ON PLAN.
○	OVERHEAD UTILITY AND/OR SYSTEM DISTRIBUTION. 3PH = THREE PHASE 1PH = SINGLE PHASE P = ELECTRICAL PRIMARY S = ELECTRICAL SECONDARY T = TELECOMMUNICATION TV = TELEVISION E = EMERGENCY POWER ATSC = AUTOMATIC TRANSFER SWITCH CONTROL N = NEW EX = EXISTING
○	UNDERGROUND UTILITY AND/OR SYSTEM DISTRIBUTION.
UT	UTILITY OR FACILITY TRANSFORMER
S	PAD MOUNTED SWITCH
CC	CONNECTION CABINET (UTILITY METER MOUNT)
PM	PRIMARY SITE METER ENCLOSURE
ME	METER ENCLOSURE. EITHER ON BUILDING OR ON UTILITY EQUIPMENT
CT	CT ENCLOSURE. EITHER ON BUILDING OR ON UTILITY EQUIPMENT
MH	MANHOLE - POWER OR COMMUNICATION AS INDICATED ON PLANS
HH	HAND HOLE - POWER OR COMMUNICATION AS INDICATED ON PLANS
EG	ENGINE GENERATOR
TP	TELECOMMUNICATION PEDESTAL
TVP	TELEVISION PEDESTAL

FIRE ALARM

SYMBOL	DESCRIPTION	MOUNTING LOC.	HT.
FACP	FIRE ALARM CONTROL PANEL		
FATC	FIRE ALARM TERMINAL CABINET (EQUIPMENT NAMING CONVENTION PER PLANS)	WALL	
FAA	FIRE ALARM ANNUNCIATOR PANEL		
F	PULL STATION	WALL	
F	FIREMAN'S TELEPHONE OUTLET		
F	HORN NOTIFICATION		
S	SPEAKER NOTIFICATION		
S	CHIME NOTIFICATION		
S	COMBINATION SPEAKER AND CHIME NOTIFICATION	WALL	
S	SPEAKER/HORN WITH STROBE LIGHT		
S	STROBE LIGHT ONLY		
B	BELL (GONG)		
P	PHOTOELECTRIC SMOKE DETECTOR		
P	IONIZATION SMOKE DETECTOR		
P	COMBINATION RATE OF RISE / FIXED TEMPERATURE	CEILING	SURFACE
P	FIXED TEMPERATURE; TEMPERATURE AS NOTED ON PLANS OR SPECIFICATIONS		
P	RATE OF RISE ONLY		
BT	BEAM TRANSMITTER	CEILING OR WALL	VARIES
BR	BEAM RECEIVER		
U	UNDER FLOOR SMOKE DETECTOR	UNDER FLOOR	SEE PLANS
U	DUCT DETECTOR	AT DUCT	SEE PLANS
PS	PRESSURE SWITCH		
TS	TAMPER SWITCH	PIPE	VARIES
FS	FLOW SWITCH		
PV	POST INDICATOR VALVE		
M	MAGNETIC DOOR HOLDER		
R	CONTROL RELAY		
MM	MONITOR MODULE	VARIES	SEE PLANS
R	REMOTE ALARM INDICATING LIGHT		
R	ADDRESSABLE/SUPERVISED RELAY		

ONE-LINE DIAGRAM

SYMBOL	DESCRIPTION
○	CIRCUIT BREAKER; TRIP SETTING/FRAME SIZE OR NO. OF POLES, SETTINGS AND PROTECTION AS NOTED ON PLANS
○	DRAWOUT CIRCUIT BREAKER (TRIP SETTING FRAME SIZE)
○	MEDIUM VOLTAGE DRAWOUT CIRCUIT BREAKER (TRIP SETTING FRAME SIZE)
○	TRANSFORMER. TRANSFORMER NAME, TRANSFORMER KVA RATING, PRIMARY VOLTAGE AND WIRING CONFIGURATION, SECONDARY VOLTAGE, K RATING (IF APPLICABLE)
○	CURRENT TRANSFORMER, NUMBER "3000/5" DENOTES RATIO.
○	POTENTIAL TRANSFORMER.
○	DISCONNECT SWITCH. "300A" DENOTES AMPERAGE RATING
○	FUSE. "300A" DENOTES AMPERAGE RATING
○	GROUND FAULT PROTECTION
○	SHUNT TRIP OPERATOR
○	GROUND CONNECTION
○	TRANSFER SWITCH. SEE PLANS FOR TYPE OF SWITCH
○	SURGE ARRESTOR
○	SURGE PROTECTIVE DEVICE
○	KILOWATT METER
○	ELECTRONIC METER
○	KIRK KEY INTERLOCK No. 1
○	RELAY No. 1
○	AMMETER SWITCH
○	AMMETER
○	VOLTMETER SWITCH
○	VOLTMETER
○	DELTA CONNECTED
○	WYE CONNECTED
○	GENERATOR
○	VFD CONNECTION
○	MOTOR CONNECTION
○	UPS

Dzilth-Na-O-Dith-Hle - New Dormitory Building CONSTRUCTION DOCUMENTS

35 Road 7585, Bloomfield, NM 87413

DECEMBER 4, 2020

MARK	DATE	DESCRIPTION
	11/17/20	Addendum Changes

ISSUE:

DATE:

PROJECT NO:

CAD DWG FILE:

DRAWN BY:

CHECKED BY:

TLM



JMM

SHEET TITLE

ELECTRICAL LEGEND


A. REFER TO ARCHITECTURAL DETAILS, ELEVATIONS, BOTH INTERIOR AND EXTERIOR, FOR EACH TYPE OF DEVICE. MOUNTING HEIGHTS MAY VARY DEPENDING ON ROUGH-IN NEEDS. CONTRACTOR WILL VERIFY ALL DEVICE TYPE MOUNTING PRIOR TO COMMENCEMENT OF ANY WORK WITH ALL TRADES.

B. COMPLY WITH NFPA 70, 2017 ED. AND NFPA 72 2016 ED.



A1 **DEVICE MOUNTING DETAILS**
SCALE: 1/2" = 1'-0"

SCALE: 1/2" = 1'-0"



B3 ELECTRICAL SITE PLAN
SCALE: 1" = 20'-0"

GENERAL NOTES

- A. SEE SHEET E-602 FOR FIRE ALARM RISER DIAGRAM AND ADDITIONAL INFORMATION.
- B. REFER TO SHEET SERIES "C", "AS", "M", "T" AND "P" FOR OTHER UTILITIES WITHIN ROUTING PATH OF ELECTRICAL RACEWAYS.
- C. REFER TO SHEET E-601 FOR ONE-LINE DIAGRAM AND ADDITIONAL ELECTRICAL DISTRIBUTION INFORMATION.
- D. REFER TO SHEET SERIES "T" FOR TELECOMMUNICATION ROOMS, EQUIPMENT LAYOUTS AND EQUIPMENT SIZES.
- E. ALL EXTERIOR BUILDING LUMINAIRES AND POLE MOUNTED SITE LUMINAIRES WILL BE ROUTED THROUGH A TIME CLOCK LOCATED IN THE ELECTRICAL ROOM WHERE PANEL CIRCUITING THOSE LUMINAIRES IS LOCATED. THE EXTERIOR BUILDING LUMINAIRES AND SITE LUMINAIRES MUST BE CONTROLLED SEPARATELY.
- F. REFER TO SHEET E-701 FOR LUMINAIRE SCHEDULE.
- G. SHOULD CONTRACTOR AT ANY TIME NOTICE THAT THE ACTUAL FIELD CONDITIONS DO NOT CORRESPOND TO THE INFORMATION GIVEN ON THE DRAWINGS, THEN IT WILL BE THEIR RESPONSIBILITY TO NOTIFY THE ARCHITECT FOR CLARIFICATION, PRIOR TO COMMENCING SUCH WORK.
- H. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO COORDINATE WITH ALL TRADES FOR THE EXACT LOCATION OF EQUIPMENT THAT REQUIRE ELECTRICAL CONNECTIONS.
- I. FOR CIRCUITING FOR ALL LUMINAIRES ON SITE, REFER TO SHEET ES-101 IN SCHOOL PACKAGE.
- J. COMPLY WITH NFPA 70, 2017 ED. AND NFPA 72 2016 ED.

KEYNOTES

- 1. ELECTRICAL ROOM. REFER TO SHEETS EP-101 FOR ELECTRICAL EQUIPMENT LAYOUT.
- 2. UTILITY TRANSFORMER. REFER TO SHEET E-601 AND E-601S FOR ADDITIONAL INFORMATION.
- 3. REFER TO SHEET ES-101 IN SCHOOL PACKAGE FOR ADDITIONAL INFORMATION.
- 4. PIV. PROVIDE A 1" CONDUIT WITH CONDUCTORS TO FACP; REFER TO SHEET E-603 AND C-210 FOR ADDITIONAL INFORMATION.
- 5. NEW ATS. PROVIDE A 3/4" CONDUIT WITH PULL ROPE TO MECHANICAL ROOM AND CONNECT TO FMS MECHANICAL CONTROL PANEL.
- 6. POLE LUMINAIRE AND POLE. REFER TO SHEET E-601 FOR ADDITIONAL INFORMATION.
- 7. HOT BOX. PROVIDE TWO DEDICATED CIRCUITS FOR HEATERS, 20A-1P EACH CIRCUIT. PROVIDE 2#10 & 1#10 GND IN 1" CONDUIT. PROVIDE SEPARATE 3/4" CONDUITS WITH CONDUCTORS TO FACP IN BUILDING. REFER TO SHEET E-603 AND C-210 FOR ADDITIONAL INFORMATION.
- 8. PIV. PROVIDE A 1" CONDUIT WITH CONDUCTORS TO FACP; REFER TO SHEET E-603 AND C-210 FOR ADDITIONAL INFORMATION.
- 9. PROVIDE A 3/4" CONDUIT WITH PULL ROPE TO MECHANICAL ROOM AND CONNECT TO FMS MECHANICAL CONTROL PANEL.
- 10. PROVIDE CONCRETE ENCASUREMENT OF CONDUIT UNDERFOOTING. CONCRETE ENCASUREMENT WILL PROTECT CONDUITS. CONCRETE ENCASUREMENT SHOULD BE 4000PSI, EXTEND 12" ON EITHER SIDE OF FOOTING, AND PROVIDE MINIMUM 3" OF COVER AROUND EACH CONDUIT.
- 11. PROVIDE A WEATHERPROOF GFCI RECEPTACLE FOR CAMERA'S POWER. REFER TO SHEET E-701 AND LUMINAIRE SCHEDULE FOR ADDITIONAL INFORMATION.

CONSULTANT



Dzilth-Na-O-Dith-Hle - New Dormitory Building
CONSTRUCTION DOCUMENTS

35 Road 7585, Bloomfield, NM 87413


DECEMBER 4, 2020

MARK	DATE	DESCRIPTION
	11/17/20	Addendum Changes
ISSUE:		
DATE:		
PROJECT NO:		751
CAD DWG FILE:		
DRAWN BY:		AMH
CHECKED BY:		JMM

SHEET TITLE
ELECTRICAL SITE PLAN



EL-101



GENERAL NOTES

- A. ALL EXIT SIGNS ARE TYPE "E" (SINGLE FACE), "E2" (DOUBLE FACE) OR "E3" UNLESS OTHERWISE NOTED. ALL EXIT SIGNS WILL BE CONNECTED TO CIRCUIT SERVING THE ROOM THEY ARE LOCATED IN AND FROM NO OTHER CIRCUIT. AT ALL EXIT SIGNAGE LOCATIONS, AN ADDITIONAL HIGH ABUSE TYPE "E3" SIGN SHALL BE PROVIDED AT 12 INCHES ABOVE THE FINISHED FLOOR MEASURED TO THE BOTTOM OF THE SIGN.
- B. FOR ELECTRICAL LUMINAIRE SCHEDULE, SEE SHEET E-701.
- C. REFER TO SHEET SERIES "EP" FOR ELECTRICAL ROOMS AND ELECTRICAL EQUIPMENT LAYOUT.
- D. FOR LUMINAIRE MOUNTING, REFER TO DETAILS A5 AND B5 ON SHEET E-501.
- E. REFER TO SHEET SERIES "A" FOR ADDITIONAL CEILING GRID MOUNTING SUPPORT INFORMATION. ALL LUMINAIRES WILL BE SECURELY SUPPORTED SEPARATELY FROM CEILING GRIDS TO CEILING STRUCTURE.
- F. FOR EXTERIOR LIGHTING ELEVATIONS, SEE ARCHITECTURAL SHEET SERIES AE200.
- G. ALL CORRIDOR AND LOBBY LUMINAIRES WILL BE ROUTED THROUGH A TIME CLOCK LOCATED IN THE SAME ELECTRICAL ROOM AS THE PANEL SERVING THOSE LUMINAIRES.
- H. ALL EXTERIOR BUILDING MOUNTED LUMINAIRES AND POLE MOUNTED SITE LUMINAIRES WILL BE ROUTED THROUGH A TIME CLOCK LOCATED IN THE SAME ELECTRICAL ROOM AS THE PANEL SERVING THOSE LUMINAIRES. THE EXTERIOR BUILDING MOUNTED LUMINAIRES AND POLE MOUNTED SITE LUMINAIRES MUST BE CONTROLLED SEPARATELY.
- I. ALL LUMINAIRES IN DASHED AREA WILL BE CONNECTED TO CIRCUIT INDICATED UNLESS OTHERWISE NOTED. CONTROL IS INDICATED OR NOTED.
- J. COVER PLATES OF ALL DEVICES WILL BE LABELED WITH CIRCUIT IT IS CONNECTED TO, SUCH DEVICES ARE, BUT NOT LIMITED TO, SWITCHES AND RECEPTACLES. REFER TO SPECIFICATION SECTION 260553 FOR ADDITIONAL INFORMATION.
- K. COMPLY WITH NFPA 70, 2017 ED. AND NFPA 72 2016 ED.

REFER TO SHEET E-701 FOR LIGHTING SEQUENCE OF OPERATION.
(A) INDICATES SEQUENCE IN EACH ROOM.

KEYNOTES

- EL02 REFER TO SHEET EP141 FOR ELECTRICAL EQUIPMENT LAYOUT IN THIS ROOM. CONTRACTOR TO STEM MOUNT LIGHTING AND UTILIZE UNISTRUT SO THAT LOCATION IS CENTERED AND AWAY FROM OBSTRUCTION.
- EL10 ONE PROGRAMMABLE TIME CLOCK WITH CONTRACTOR FOR SITE LIGHTING. REFER TO DETAIL A1 ON SHEET E-501 FOR ADDITIONAL INFORMATION.

fbt | architects

MAIL: 6501 Americas Play NE, Ste. 300
Albuquerque, NM 87110

PHO: 505.883.5200
FAX: 505.884.5290
WEB: www.fbtarch.com

CONSULTANT

BRIDGERS & PAXTON

4600 C Montgomery Blvd. NE
Albuquerque, NM 87109 | 505.883.4111 | www.bpcce.com

ENGINEER

Dzilth-Na-O-Dith-Hle - New Dormitory Building

CONSTRUCTION DOCUMENTS

35 Road 7585, Bloomfield, NM 87413

DECEMBER 4, 2020

MARK	DATE	DESCRIPTION
	11/17/20	Addendum Changes

ISSUE:

DATE:

PROJECT NO: 751

CAD DWG FILE:

DRAWN BY: AMH

CHECKED BY: JMM

SHEET TITLE

LIGHTING PENTHOUSE PLAN


EL-141

Dzilth-Na-O-Dith-Hle - New Dormitory Building

D:\Revit\2019\Projects\8226_DCS Dom. MEP_AMHeresS22\CD.rvt

12/20/2020 1:25:53 PM

Bridgers & Paxton Project No. 8226



- GENERAL NOTES
- A. GFCI RECEPTACLES WILL BE INSTALLED AT ALL LOCATIONS AS REQUIRED BY THE LATEST VERSION OF NEC, STATE AND LOCAL CODES WHETHER INDICATED ON PLANS OR NOT. SOME LOCATIONS WILL BE WITHIN 6'-0" OF SINKS, EXTERIOR DOORS AND WET LOCATIONS. ALL EXTERIOR RECEPTACLE LOCATIONS WILL BE GFCI RATED AND WEATHERPROOF.

B. CONTROLS FOR ALL MECHANICAL EQUIPMENT WILL BE AS INDICATED IN 'M' SHEET SERIES. RACEWAY PATHS FOR CONTROLS AND WIRING AS INDICATED ON CONTROL DIAGRAMS. REFER ALSO TO SPECIFICATION SECTION 230549 FOR ADDITIONAL INFORMATION. CONTRACTOR WILL PROVIDE A 3/4" CONDUIT FOR CONTROL WIRING AS REQUIRED BY 'M' SHEET SERIES. CONTROL WILL BE BY LOCAL SWITCHES. PROVIDE PILOT LIGHT SWITCHES WHERE LOCAL SWITCHES ARE REQUIRED PER CONTROL DIAGRAMS.

C. COORDINATE ALL 120 VOLT POWER REQUIREMENTS AND LOCATIONS WITH THE CONTROLS / ACCESS / SECURITY CONTRACTORS IN THE FIELD. REFER TO SPECIFICATION 230549 FOR ADDITIONAL INFORMATION.

D. LOCATION OF EQUIPMENT AND OTHER DEVICES SHOWN ON PLANS ARE APPROXIMATE AND SHOULD BE FIELD VERIFIED.

E. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO COORDINATE WITH ALL TRADES FOR EXACT LOCATION OF EQUIPMENT AND APPURTENANCES THAT REQUIRE ELECTRICAL CONNECTIONS AND REQUIRE ALIGNMENT OF DEVICES.

F. INSTALL ALL CONDUITS IN OPEN CEILING SPACE AS CLOSE TO STRUCTURE AS POSSIBLE.

G. ALL CIRCUITS FOR GENERAL POWER WITH-IN DASHED AREA WILL BE CONNECTED TO PANEL INDICATED UNLESS OTHERWISE NOTED.

H. COVER PLATES OF ALL DEVICES WILL BE LABELED WITH CIRCUIT IT IS CONNECTED TO. SUCH DEVICES ARE, BUT NOT LIMITED TO, SWITCHES AND RECEPTACLES. REFER TO SPECIFICATION SECTION 280553 FOR ADDITIONAL INFORMATION.

I. ALL THERMAL RATED SWITCHES SHALL BE RATED FOR 1HP MINIMUM.

J. COMPLY WITH NFPA 70, 2017 ED. AND NFPA 72 2016 ED.

- KEYNOTES
- EP01 MOUNT DEVICE(S) 6" ABOVE COUNTER TOP BACK SPLASH, TABLE TOP OR SINK. RECEPTACLE WILL BE GFCI RATED IF DESIGNATED WITH A "G".

EP02 GROUNDING ELECTRODE GROUND BAR. REFER TO MAIN GROUNDING ELECTRODE BUS BAR DETAIL A5 ON SHEET E-501 AND ELECTRICAL GROUNDING DIAGRAM ON SHEET E-602 FOR ADDITIONAL INFORMATION.

EP03 FIRE ALARM CONTROL PANEL (FACP) OR FIRE ALARM TERMINAL CABINET (FATC). REFER TO SHEET E-602 FOR ADDITIONAL INFORMATION. PROVIDE 120V POWER.

EP04 LOCATION OF BATTERY INVERTER. REFER TO SHEET EL-101 AND SHEET E-701 FOR ADDITIONAL INFORMATION.

EP05 RECEPTACLE FOR WALL MOUNTED DISPLAY. MOUNT ADJACENT TO DATA/OUTLETS COORDINATE WITH SHEET SERIES "IT" FOR ADDITIONAL INFORMATION.

EP06 PROVIDE DEVICE FOR ELECTRIC WATER COOLER/BOTTLE FILLER. PROVIDE GFCI CIRCUIT BREAKER IN PANEL. NOT AT RECEPTACLE. MOUNT DEVICE SO IT IS CONCEALED BEHIND UNIT ALONG WITH CORD. COORDINATE WITH MANUFACTURERS FOR ALL REQUIREMENTS PRIOR TO COMMENCEMENT OF ANY WORK.

EP07 LOCATION OF TIME-CLOCK. REFER TO SHEET EL-101 AND SHEET E-501 FOR ADDITIONAL INFORMATION.

EP08 REFER TO SHEET SERIES "M" AND TO SHEET E-701 FOR ADDITIONAL ELECTRICAL INFORMATION REQUIRED FOR CONNECTION OF SYSTEM EQUIPMENT.

EP09 CONDENSATE PUMP AS REQUIRED.

EP10 POWER FROM ROOF MOUNTED OUTDOOR UNIT ASSOCIATED WITH SPLIT SYSTEM. REFER TO SHEET EP-131 FOR ADDITIONAL INFORMATION.

EP14 DEVICES IN IT ROOM WILL BE SURGE-PROTECTED RECEPTACLES. ONE (1) 20A (120V) DUPLEX WILL BE MOUNTED TO TOP OF RACK MOUNTED CABLE TRAY AT EACH RACK LOCATION UTILIZING UNISTRUT. VERIFY CONNECTOR TYPE AND LOCATION WITH SHEET SERIES "IT".

EP16 MOUNT DEVICE 42" AFF BEHIND REFRIGERATOR. CONTRACTOR WILL MATCH NEMA CONFIGURATION OF RECEPTACLE WITH UNIT PLUG. COORDINATE PRIOR TO ORDERING RECEPTACLE DEVICE.

EP20 SPLIT SYSTEM INDOOR UNIT. PROVIDE A KNIFE BLADE DISCONNECT SWITCH ADJACENT TO UNIT. RACEWAY AND CONDUCTORS WILL BE EXTENDED TO ASSOCIATED ROOF UNIT FOR THIS SPLIT SYSTEM UNIT WILL BE PACKAGED WITH CONTROLS. PROVIDE JUNCTION BOX FOR SEPARATION OF POWER TO CONDENSATE PUMP AND FC UNIT. REFER TO SHEET SERIES "M" FOR ADDITIONAL INFORMATION. REFER TO SHEET E-701 FOR ELECTRICAL CONNECTION AND OTHER INFORMATION.

EP24 FOR EACH UNIT. REFER TO SHEET SERIES "M-700" FOR MECHANICAL EQUIPMENT CHARACTERISTICS. REFER TO SHEET E-701 FOR ELECTRICAL CONNECTION AND OTHER INFORMATION.

EP29 EXTEND BRANCH CIRCUIT, RACEWAY, AND CONDUCTORS BETWEEN INDOOR AND EXTERIOR UNITS.

EP32 DEVICE FOR WASHER/DRYER. PROVIDE DEDICATED CIRCUIT. MOUNT DEVICE AT 42" AFF. PROVIDE 2#10 & 1#10 GND IN 3/4" CONDUIT FOR DRYER.

EP46 PROVIDE POWER FOR CONNECTION TO DOOR HARDWARE. 3/4" CONDUIT BETWEEN EACH JUNCTION BOX AND PERMANENT CONDUCTORS PER DOOR HARDWARE INSTALLERS INSTRUCTIONS.

EP50 POWER FOR FIRE SMOKE DAMPERS AND SMOKE DAMPERS. REFER TO SHEET SERIES "FA" FOR FIRE ALARM CONNECTION INFORMATION. COORDINATE POWER LOCATION AND REQUIREMENTS WITH SHEET SERIES "M" PRIOR TO COMMENCEMENT OF ANY WORK.

EP58 PROVIDE JUNCTION BOX WITH POWER FOR TECHNOLOGIES SUCH AS ADA ACCESS, CARD ACCESS AND ANY OTHER SUCH SYSTEMS FOR DOORS INDICATED BY ARCHITECTS DOOR SCHEDULE. COORDINATE ALL TERMINATIONS WITH TECHNOLOGY AND HARDWARE PROVIDER OR INSTALLER PRIOR TO ROUGH-IN FOR COMPLETE INSTALLATION REQUIREMENTS.

EP60 DEVICES WILL BE A COMBINATION RECEPTACLE AND USB PORT. USB TYPE WILL BE USB 3.0.

EP61 DEVICES WILL BE A COMBINATION RECEPTACLE AND USB PORT. PROVIDE QUADPLEX OUTLET AND (2) USB 3.0 PORTS.

fbt

architects

MAIL: 6501 Americas Pkwy NE, Ste. 300
Albuquerque, NM 87110

PHO: 505.883.5200
FAX: 505.884.5290
WEB: www.fbtarch.com

CONSULTANT

BRIDGERS & PAXTON

4600 C Montgomery Blvd. NE
Albuquerque, NM 87109 | 505.883.4111 | www.bpcce.com

JOHN M. MONTANO

15344

12/20/20

REGISTERED PROFESSIONAL ENGINEER

ENGINEER

Dzilth-Na-O-Dith-Hle - New Dormitory Building

CONSTRUCTION DOCUMENTS

35 Road 7585, Bloomfield, NM 87413

DECEMBER 4, 2020

MARK	DATE	DESCRIPTION
	11/17/20	Addendum Changes

ISSUE:

DATE:

PROJECT NO:

CAD DWG FILE:

DRAWN BY:

CHECKED BY:

SHEET TITLE


POWER FLOOR PLAN

EP-101

Dzilth-Na-O-Dith-Hle - New Dormitory Building

12/29/2020 1:25:57 PM D:\Revit\2019\Projects\8226_DCS Dom. MEP_AMHeresS2\NC.rvt

Bridgers & Paxton Project No. 8226



- GENERAL NOTES
- A.

GFCI RECEPTACLES WILL BE INSTALLED AT ALL LOCATIONS AS REQUIRED BY THE LATEST VERSION OF NEC, STATE AND LOCAL CODES WHETHER INDICATED ON PLANS OR NOT. SOME LOCATIONS WILL BE WITHIN 6'-0" OF SINKS, EXTERIOR DOORS AND WET LOCATIONS. ALL EXTERIOR RECEPTACLE LOCATIONS WILL BE GFCI RATED AND WEATHERPROOF.
- B.

CONTROLS FOR ALL MECHANICAL EQUIPMENT WILL BE AS INDICATED IN 'M' SHEET SERIES. RACEWAY PATHS FOR CONTROLS AND WIRING AS INDICATED ON CONTROL DIAGRAMS. REFER ALSO TO SPECIFICATION SECTION 230549 FOR ADDITIONAL INFORMATION. CONTRACTOR WILL PROVIDE A 3/4" CONDUIT FOR CONTROL WIRING AS REQUIRED BY 'M' SHEET SERIES. CONTROL WILL BE BY LOCAL SWITCHES. PROVIDE PILOT LIGHT SWITCHES WHERE LOCAL SWITCHES ARE REQUIRED PER CONTROL DIAGRAMS.
- C.

COORDINATE ALL 120 VOLT POWER REQUIREMENTS AND LOCATIONS WITH THE CONTROLS / ACCESS / SECURITY CONTRACTORS IN THE FIELD. REFER TO SPECIFICATION 230549 FOR ADDITIONAL INFORMATION.
- D.

LOCATION OF EQUIPMENT AND OTHER DEVICES SHOWN ON PLANS ARE APPROXIMATE AND SHOULD BE FIELD VERIFIED.
- E.

IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO COORDINATE WITH ALL TRADES FOR EXACT LOCATION OF EQUIPMENT AND APPURTENANCES THAT REQUIRE ELECTRICAL CONNECTIONS AND REQUIRE ALIGNMENT OF DEVICES.
- F.

INSTALL ALL CONDUITS IN OPEN CEILING SPACE AS CLOSE TO STRUCTURE AS POSSIBLE.
- G.

ALL CIRCUITS FOR GENERAL POWER WITH-IN DASHED AREA WILL BE CONNECTED TO PANEL INDICATED UNLESS OTHERWISE NOTED.
- H.

COVER PLATES OF ALL DEVICES WILL BE LABELED WITH CIRCUIT IT IS CONNECTED TO. SUCH DEVICES ARE, BUT NOT LIMITED TO, SWITCHES AND RECEPTACLES. REFER TO SPECIFICATION SECTION 280553 FOR ADDITIONAL INFORMATION.
- I.

ALL THERMAL RATED SWITCHES SHALL BE RATED FOR 1HP MINIMUM.
- J.

COMPLY WITH NFPA 70, 2017 ED. AND NFPA 72 2016 ED.

- KEYNOTES
- EP08

REFER TO SHEET SERIES 'M' AND TO SHEET E-701 FOR ADDITIONAL ELECTRICAL INFORMATION REQUIRED FOR CONNECTION OF SYSTEM EQUIPMENT.
- EP22

ROOF MOUNTED RECEPTACLE. PROVIDE 2#10 & #10 GROUND IN 3/4" CONDUIT. REFER TO DETAIL D3 ON SHEET E-501 FOR ADDITIONAL INFORMATION.
- EP24

FOR EACH UNIT, REFER TO SHEET SERIES 'M-700' FOR MECHANICAL EQUIPMENT CHARACTERISTICS. REFER TO SHEET E-701 FOR ELECTRICAL CONNECTION AND OTHER INFORMATION.
- EP29

EXTEND BRANCH CIRCUIT, RACEWAY, AND CONDUCTORS BETWEEN INDOOR AND EXTERIOR UNITS.
- EP57

MOUNT RECEPTACLE TO BACK SIDE OF STRUT RACK PER NOTES.
- EP62

PROVIDE 2" CONDUIT FROM 10"x10"x10 PULLBOX TO
- EP63

PROVIDE JUNCTION BOX FOR FUTURE AIR CLEANER EQUIPMENT.

fbt

architects

MAIL: 6501 Americas Play NE, Ste. 300
Albuquerque, NM 87110

PHO: 505.883.5200
FAX: 505.884.5290
WEB: www.fbtarch.com

CONSULTANT

BRIDGERS
& PAXTON

4600 C Montgomery Blvd. NE
Albuquerque, NM 87109 | 505.883.4111 | www.bpce.com

JOHN M. MONTANO
NEW MEXICO
15344
12/29/20
LICENSED PROFESSIONAL ENGINEER

ENGINEER

Dzilth-Na-O-Dith-Hle - New Dormitory Building

CONSTRUCTION DOCUMENTS

35 Road 7585, Bloomfield, NM 87413

DECEMBER 4, 2020

MARK	DATE	DESCRIPTION
	11/17/20	Addendum Changes

ISSUE:

DATE:

PROJECT NO:

CAD DWG FILE:

DRAWN BY:

CHECKED BY:

751


TLA

JMM

SHEET TITLE

ELECTRICAL ROOF PLAN

EP-141



GENERAL NOTES

A. LIGHTNING PROTECTION SYSTEM IS SHOWN DIAGMAMTICALLY. CONTRACTOR WILL INSTALL PER NFPA 780 AND SPECIFICATION 264112 TO ACHIEVE MASTER LABEL.

B. REFER TO SHEET E-502 FOR LIGHTNING PROTECTION DETAILS AND ADDITIONAL INFORMATION.

C. COMPLY WITH NFPA 70, 2017 ED. AND NFPA 72 2016 ED.

IT IS THE INTENT OF THESE DOCUMENTS TO SHOW A BASIC REPRESENTATION OF THE LIGHTNING PROTECTION SYSTEM. DEVICES INDICATED ON THESE DOCUMENTS ARE IN NO WAY IMPLIED TO BE COMPREHENSIVE OF THE FINAL DESIGN. IT IS THE RESPONSIBILITY OF THE LIGHTNING PROTECTION CONTRACTOR TO PROVIDE A DESIGN/BUILD LIGHTNING PROTECTION SYSTEM BASED UPON A THOROUGH REVIEW OF ALL CONTRACT DOCUMENTS. IT IS THE RESPONSIBILITY OF THE LIGHTNING PROTECTION CONTRACTOR TO ENSURE THAT THE LIGHTNING PROTECTION SYSTEM IS CODE COMPLIANT, MEETS THE REQUIREMENTS OF THE AHJ AND COMPREHENSIVELY COVERS AND INCLUDES ALL NECESSARY PARTS AND LABOR ASSOCIATED WITH OTHER TRADES AND SYSTEMS IMPACTING THE LIGHTNING PROTECTION SYSTEM. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO ACHIEVE A MASTER LABEL FOR THE LIGHTNING PROTECTION SYSTEM. NO CHANGE ORDERS WILL BE APPROVED FOR THE BASE SCOPE OF WORK.

KEYNOTES


1. 24" TALL LIGHTNING ARRESTORS.

2. LIGHTNING CONDUCTOR EXPOSED AND MOUNTED TO TOP OR SIDE OF BUILDING.

3. ATTACH LIGHTNING PROTECTION TO MECHANICAL EQUIPMENT.

4. DOWN CONDUCTOR FROM ROOF TO LIGHTNING ARRESTORS TO COUNTERPOISE AND GROUND RODS. ROUTING OF DOWN CONDUCTOR TO COUNTERPOISE WILL BE INTERIOR TO WALL STRUCTURE.

5. GROUND RODS.



fbt | architects

MAIL: 6501 Americas Play NE, Ste. 300
Albuquerque, NM 87110

PHO: 505.883.5200
FAX: 505.884.5290
WEB: www.fbtarch.com

CONSULTANT

BRIDGERS & PAXTON

4600 C Montgomery Blvd. NE
Albuquerque, NM 87109 | 505.883.4111 | www.bpcce.com

ENGINEER

Dzilth-Na-O-Dith-Hle - New Dormitory Building

CONSTRUCTION DOCUMENTS

35 Road 7585, Bloomfield, NM 87413

DECEMBER 4, 2020

MARK	DATE	DESCRIPTION
	11/17/20	Addendum Changes

ISSUE:

DATE:

PROJECT NO: 751

CAD DWG FILE:


DRAWN BY: AMH

CHECKED BY: JMM

SHEET TITLE

LIGHTNING PROTECTION ROOF PLAN - OVERALL

LP-141



A1 FIRE ALARM FLOOR PLAN
1/8" = 1'-0"

KEYNOTES

- FA01. FIRE ALARM CONTROL PANEL (FACP). REFER TO FIRE ALARM RISER DIAGRAM ON SHEET E-603 FOR ADDITIONAL INFORMATION.
- FA02. FIRE ALARM ANNUNCIATOR (FAA). REFER TO FIRE ALARM RISER DIAGRAM ON SHEET E-603 FOR ADDITIONAL INFORMATION.
- FA03. FIRE SMOKE DAMPER. REFER TO SHEET SERIES "M" FOR ACTUAL LOCATION.
- FA17. FIRE RISER. REFER TO SHEET F-101 FOR ADDITIONAL INFORMATION.

GENERAL NOTES

- GROUP RESIDENTIAL-DORMITORY. REFER TO SHEET SERIES "G" FOR OCCUPANCY LOCATIONS AND ADDITIONAL INFORMATION.
- CONTRACTOR WILL COORDINATE SIGNALING DEVICES AT EGRESS PATH OR DOORS WITH ARCHITECTURAL SHEET SERIES "G".
- SIGNAL TYPE DETECTORS MAY BE OMITTED FROM NON-COMBUSTIBLE SPACES AND FROM CONCEALED COMBUSTIBLE SPACES PROVIDED WITH AN AUTOMATIC FIRE SPRINKLER SYSTEM.
- PROVIDE DETECTION DEVICES IN ALL UNOCCUPIED SPACES INCLUDING ELECTRICAL ROOMS, MECHANICAL ROOMS, STORAGE ROOMS, JANITOR'S CLOSETS, ETC.
- PROVIDE VOICE EVACUATION SPEAKER/STROBE NOTIFICATION DEVICES IN ALL OCCUPIED AREAS PER THE REQUIREMENTS OF THE NFPA AND LOCAL CODES AND OCCUPANCY TYPE.
- WALL MOUNTED AUDIBLE NOTIFICATION DEVICES SHALL HAVE THEIR TOPS MOUNTED AT 90" MINIMUM AND 100" MAXIMUM FROM FINISHED FLOOR AND NO CLOSER THEN 6" TO A HORIZONTAL STRUCTURE. CMU BLOCK WALL AND CELLS OF BLOCK WILL VARY THE DIMENSION HEIGHTS. COORDINATE PRIOR TO COMMENCEMENT OF ANY WORK.
- PROVIDE DUCT DETECTORS IN ALL SUPPLY AND RETURN AIR DUCTS FOR HVAC UNITS 2000 CFM AND FOR ALL MECHANICAL DUCTS, UNITS, FIRE SMOKE DAMPERS AND OTHER EQUIPMENT REQUIRING FIRE ALARM SIGNAL AND NOTIFICATION. CONTRACTOR TO FIELD VERIFY THESE UNITS IN EACH BUILDING. REFER TO SHEET SERIES "M" FOR ALL MECHANICAL REQUIREMENTS AND EQUIPMENT LOCATIONS.
- PROVIDE ADDRESSABLE DEVICES FOR FIRE/SMOKE DAMPERS. QUANTITY TO BE VERIFIED BY CONTRACTOR. COORDINATE SMOKE/FIRE DAMPER LOCATIONS IN FIELD WITH OWNER AND INTERCONNECT AS REQUIRED. VERIFY THAT THE EXISTING DAMPER MOTORS ARE ON A 120V CIRCUIT. PROVIDE ADDRESSABLE MODULES AS REQUIRED. REFER TO SPECIFICATIONS FOR ADDITIONAL PRICING INFORMATION.
- HEAT DETECTORS MAY BE USED IN LIEU OF SMOKE DETECTORS IN THE FOLLOWING AREAS:
 - MECHANICAL, ELECTRICAL AND STORAGE ROOMS.
 - CLOSETS AND SMALL STORAGE ROOMS (100 SQUARE FEET IN AREA OR LESS), OR OTHER SMALL UNCONDITIONED SPACES.
- FIRE ALARM SUPERVISION IS REQUIRED FOR ALL FIRE ALARM AND FIRE SPRINKLER FLOW ALARMS AND TAMPER SWITCHES PER NFPA 72 BY AN APPROVED SUPERVISING STATION IN ACCORDANCE WITH CBC CHAPTER 9.
- WALL MOUNTED VISUAL NOTIFICATION DEVICES SHALL HAVE THEIR BOTTOMS MOUNTED AT 80" MINIMUM AND 96" MAXIMUM FROM FINISHED FLOOR. CMU BLOCK WALL AND CELLS OF BLOCK WILL VARY THE DIMENSION HEIGHTS. COORDINATE PRIOR TO COMMENCEMENT OF ANY WORK.
- IT IS THE CONTRACTOR'S RESPONSIBILITY TO PROVIDE A CODE COMPLIANT, NICET LEVEL III DESIGN TO BE APPROVED BY THE STATE AND BIA FIRE MARSHAL. ADD DEVICES AS REQUIRED TO MEET ALL NATIONAL AND LOCAL CODE REQUIREMENTS. COORDINATE IN FIELD ALL INSTALLATIONS.
- INFORMATION ON CONTRACT DOCUMENTS IS FOR GENERAL INFORMATION AND BID PURPOSES ONLY. PERFORM REQUIRED CALCULATIONS AND FIELD COORDINATION AND PROVIDE ADDITIONAL DEVICES AS REQUIRED.
- ADDITIONAL MATERIALS AND LABOR REQUIRED TO SUPPORT CHANGES REQUESTED BY THE AUTHORITY HAVING JURISDICTION SHALL BE PROVIDED AT NO ADDITIONAL COST TO THE OWNER. PROVIDE UNIT COST IN BID FOR INSTALL OF ALL SYSTEM DEVICES, WIRING, AND PLACEMENT ON WALLS AND CEILINGS.
- ALL NEW NOTIFICATION AND SIGNALING DEVICES SHALL BE RECESSED INTO THE WALLS WHERE INDICATED TO BE REQUIRED ON PLAN OR CEILINGS. PROVIDE A RACEWAY PATH ABOVE THE ACCESSIBLE CEILING AS NECESSARY.
- WHERE APPLICABLE DO NOT INSTALL SMOKE DETECTORS IN A DIRECT AIR FLOW OR CLOSER THAN 3 FEET FROM AN AIR SUPPLY DIFFUSER OR RETURN AIR OPENING.
- INSTALLATION OF THE SYSTEMS SHALL NOT BE STARTED UNTIL DETAILED DESIGN DOCUMENTS AND SPECIFICATION, INCLUDING STATE AND BIA FIRE MARSHAL LISTING NUMBERS FOR EACH COMPONENT OF THE SYSTEM HAS BEEN APPROVED BY THE ENGINEER.
- A STAMPED SET OF APPROVED FIRE ALARM DESIGN DOCUMENTS SHALL BE ON THE JOB SITE AND USED FOR INSTALLATION.
- THE CONTRACTOR SHALL ADJUST/INSTALL ALL DEVICES TO MAXIMIZE PERFORMANCE AND TO MINIMIZE FALSE ALARMS.
- ALL FIRE ALARM WIRING SHALL BE FPL OR FPLP (FIRE POWER LIMITED OR FIRE POWER LIMITED PLENUM) AS REQUIRED PER NFPA 72. IN AREA OF CONSTRUCTION OR POSSIBLE DAMAGE/CONTAMINATION ON NEWLY INSTALLED FIRE ALARM DEVICES SHALL BE COVERED UNTIL THAT AREA IS READY TO BE TURNED OVER TO THE OWNER.
- SMOKE DETECTORS SHALL NOT BE ANY CLOSER THAN 1" FROM FIRE SPRINKLERS OR 3" FROM ANY SUPPLY DIFFUSER. IN AREA OF CONSTRUCTION OR POSSIBLE DAMAGE/CONTAMINATION ON NEWLY INSTALLED FIRE ALARM DEVICES SHALL BE COVERED UNTIL THAT AREA IS READY TO BE TURNED OVER TO THE OWNER.
- ALL FIRE ALARM CIRCUITS SHALL BE IN CONDUIT, SURFACE RACEWAY OR OPEN RUN ABOVE CEILINGS, AND IN WALLS IN A NEAT AND PROTECTED MANNER AS INDICATED ON DESIGN DOCUMENTS.
- FIRE ALARM PANEL, REMOTE ANNUNCIATOR, AND COMPONENTS SHALL BE SECURED TO MOUNTING SURFACES PER MANUFACTURER'S SPECIFICATIONS. NO SINGLE DEVICE SHALL EXCEED THE WEIGHT OF 20 LBS WITHOUT SPECIAL MOUNTING DETAILS.
- A DEDICATED BRANCH CIRCUIT SHALL BE PROVIDED FOR FIRE ALARM EQUIPMENT. THIS CIRCUIT SHALL BE ENERGIZED FROM THE COMMON USE AREA PANEL AND SHALL HAVE NO OTHER OUTLETS. THE BREAKER SHALL HAVE A RED LOCKING DEVICE TO BLOCK THE HANDLE IN THE "ON" POSITION. THE CIRCUIT BREAKER SHALL BE LABELED "FIRE ALARM CIRCUIT CONTROL". CIRCUIT ID TO BE LABELED AT FIRE PANEL EXTENDERS. PROVIDE SURGE PROTECTOR AT EACH FIRE ALARM PANEL OR POWER SUPPLY.
- THE INSTALLING CONTRACTOR SHALL PROVIDE A RECORD OF COMPLETION PER NFPA 72, FIGURE 10.16.2.1.1, 22) CONTROL PANELS, REMOTE ANNUNCIATORS SHALL BE INSTALLED WITH THEIR BOTTOMS MOUNTED AT 48".
- OWNER SHALL BE RESPONSIBLE FOR ESTABLISHING A FIRE SYSTEM MONITORING CONTRACT OR PROVISIONS.
- ENGINEER AND OWNER SHALL BE NOTIFIED A MINIMUM OF 48 HOURS PRIOR TO THE FINAL INSPECTION AND / OR TESTING.
- UPON COMPLETION OF THE INSTALLATION OF THE SYSTEMS, A SATISFACTORY TEST OF THE ENTIRE SYSTEM SHALL BE MADE IN ACCORDANCE WITH THE SPECIFICATIONS.
- COORDINATE WITH OWNER. FOR NEW FIBER OPTIC STRANDS NEEDED FOR CONNECTIONS TO NEW FIRE ALARM PANEL.
- REFER TO SHEET E-603 FOR FIRE ALARM RISER DIAGRAM.
- ALL STROBES IN CORRIDORS AND COMMON AREAS WILL FLASH AT THE SAME TIME.
- WHERE A VOICE EVACUATION SYSTEM IS NECESSARY PER THE OCCUPANCY TYPE, ASSEMBLY OF OCCUPANCY TYPE, NICET LEVEL III OR HIGHER DESIGNER AND INSTALLER PROFESSIONAL, AND AS APPROVED BY THE STATE FIRE MARSHAL'S OFFICE, CONTRACTOR WILL REFER TO SPECIFICATION 283111 FOR VOICE EVACUATION SYSTEM REQUIREMENTS.
- CONTRACTOR WILL VERIFY WITH ARCHITECTURAL REFLECTED CEILING PLANS FOR EACH SPACE CEILING TYPES OR HEIGHTS OR LACK THERE OF A CEILING. MOUNTING OF ANY DEVICE TO A CEILING OR STRUCTURE WILL BE COORDINATED PRIOR TO COMMENCEMENT OF ANY WORK.
- COMPLY WITH NFPA 70, 2017 ED. AND NFPA 72 2016 ED.

IT IS THE INTENT OF THESE DOCUMENTS TO SHOW A BASIC REPRESENTATION OF THE FIRE ALARM SYSTEM DEVICES INDICATED ON THESE DOCUMENTS ARE IN NO WAY IMPLIED TO BE COMPREHENSIVE OF THE FINAL DESIGN. IT IS THE RESPONSIBILITY OF THE FIRE ALARM CONTRACTOR TO PROVIDE A DESIGN/BUILD FIRE ALARM SYSTEM BASED UPON A THOROUGH REVIEW OF ALL CONTRACT DOCUMENTS. IT IS THE RESPONSIBILITY OF THE FIRE ALARM CONTRACTOR TO ENSURE THAT THE FIRE ALARM SYSTEM IS CODE COMPLIANT, MEETS THE REQUIREMENTS OF THE AHJ AND COMPREHENSIVELY COVERS AND INCLUDES ALL NECESSARY PARTS AND LABOR ASSOCIATED WITH OTHER TRADES AND SYSTEMS IMPACTING THE FIRE ALARM SYSTEM. NO CHANGE ORDERS SHALL BE APPROVED FOR THE BASE SCOPE OF WORK.

ENTIRE FIRE ALARM SYSTEM WILL BE IN RACEWAYS; NO EXCEPTIONS!

fbt | architects

MAIL: 6501 Americas Play NE, Ste. 300
Albuquerque, NM 87110

PHO: 505.883.5200
FAX: 505.884.5290
WEB: www.fbtarch.com

CONSULTANT

BRIDGERS & PAXTON

4600 C Montgomery Blvd. NE
Albuquerque, NM 87109 | 505.883.4111 | www.bpcpe.com

ENGINEER

Dzilth-Na-O-Dith-Hle - New Dormitory Building

CONSTRUCTION DOCUMENTS

35 Road 7585, Bloomfield, NM 87413

DECEMBER 4, 2020

MARK	DATE	DESCRIPTION
	11/17/20	Addendum Changes

ISSUE:

DATE:

PROJECT NO: 751

CAD DWG FILE:


DRAWN BY: AMH

CHECKED BY: JMM


SHEET TITLE

FIRE ALARM FLOOR PLAN


FA-101



D4 MECHANICAL ROOM ENLARGED PLAN- RM 154
SCALE: 1/4" = 1'-0"



C4 KITCHEN ENLARGED PLAN
SCALE: 1/4" = 1'-0"



A4 LAUNDRY ROOM ENLARGED PLAN
1/4" = 1'-0"

GENERAL NOTES

- GFCI RECEPTACLES WILL BE INSTALLED AT ALL LOCATIONS AS REQUIRED BY THE LATEST VERSION OF NEC, STATE AND LOCAL CODES WHETHER INDICATED ON PLANS OR NOT. SOME LOCATIONS WILL BE WITHIN 6'-0" OF SINKS, EXTERIOR DOORS AND WET LOCATIONS. ALL EXTERIOR RECEPTACLE LOCATIONS WILL BE GFCI RATED AND WEATHERPROOF.
- CONTROLS FOR ALL MECHANICAL EQUIPMENT WILL BE AS INDICATED IN 'M' SHEET SERIES. RACEWAY PATHS FOR CONTROLS AND WIRING AS INDICATED ON CONTROL DIAGRAMS. REFER ALSO TO SPECIFICATION SECTION 230549 FOR ADDITIONAL INFORMATION. CONTRACTOR WILL PROVIDE A 3/4" CONDUIT FOR CONTROL WIRING AS REQUIRED BY 'M' SHEET SERIES. CONTROL WILL BE BY LOCAL SWITCHES. PROVIDE PILOT LIGHT SWITCHES WHERE LOCAL SWITCHES ARE REQUIRED PER CONTROL DIAGRAMS.
- COORDINATE ALL 120 VOLT POWER REQUIREMENTS AND LOCATIONS WITH THE CONTROLS / ACCESS / SECURITY CONTRACTORS IN THE FIELD. REFER TO SPECIFICATION 230549 FOR ADDITIONAL INFORMATION.
- LOCATION OF EQUIPMENT AND OTHER DEVICES SHOWN ON PLANS ARE APPROXIMATE AND SHOULD BE FIELD VERIFIED.
- IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO COORDINATE WITH ALL TRADES FOR EXACT LOCATION OF EQUIPMENT AND APPURTENANCES THAT REQUIRE ELECTRICAL CONNECTIONS AND REQUIRE ALIGNMENT OF DEVICES.
- INSTALL ALL CONDUITS IN OPEN CEILING SPACE AS CLOSE TO STRUCTURE AS POSSIBLE.
- ALL CIRCUITS FOR GENERAL POWER WITH-IN DASHED AREA WILL BE CONNECTED TO PANEL INDICATED UNLESS OTHERWISE NOTED.
- COVER PLATES OF ALL DEVICES WILL BE LABELED WITH CIRCUIT IT IS CONNECTED TO. SUCH DEVICES ARE, BUT NOT LIMITED TO, SWITCHES AND RECEPTACLES. REFER TO SPECIFICATION SECTION 260553 FOR ADDITIONAL INFORMATION.
- ALL THERMAL RATED SWITCHES SHALL BE RATED FOR 1HP MINIMUM.
- COMPLY WITH NFPA 70, 2017 ED. AND NFPA 72 2016 ED.

KEYNOTES

- EP01 MOUNT DEVICE(S) 6" ABOVE COUNTER TOP BACK SPLASH, TABLE TOP OR SINK. RECEPTACLE WILL BE GFCI RATED IF DESIGNATED WITH A "G".
- EP13 EMERGENCY POWER OFF (EPO) RED MUSHROOM HEAD PUSH BUTTON FOR BOILER AND WATER HEATER SHUT OFF. TERMINATE CONDUCTORS TO EACH BOILER AND WATER HEATER PER MANUFACTURERS DIRECTION. EACH BOILER AND WATER HEATERS CIRCUIT WILL BE ROUTED THROUGH A CONTACTOR (8 POLE) WHICH WILL BE MOUNTED FOR EASY ACCESS TO THE CONTRACTOR WITHOUT A LADDER. REFER TO DETAIL 84 ON SHEET E-501 FOR ADDITIONAL INFORMATION.
- EP16 MOUNT DEVICE 42" AFF BEHIND REFRIGERATOR. CONTRACTOR WILL MATCH NEMA CONFIGURATION OF RECEPTACLE WITH UNIT PLUG. COORDINATE PRIOR TO ORDERING RECEPTACLE DEVICE.
- EP24 FOR EACH UNIT, REFER TO SHEET SERIES "M-700" FOR MECHANICAL EQUIPMENT CHARACTERISTICS. REFER TO SHEET E-701 FOR ELECTRICAL CONNECTION AND OTHER INFORMATION.
- EP26 DISHWASHER. INSTALL OUTLET WITHIN BASE CABINERY AT ACCESSIBLE LOCATION. COORDINATE WITH EQUIPMENT INSTALLER.
- EP27 ELECTRIC RANGE/STOVE. MOUNT DEVICE BEHIND UNIT. CONTRACTOR WILL MATCH NEMA CONFIGURATION OF RECEPTACLE WITH UNIT PLUG. COORDINATE PRIOR TO ORDERING RECEPTACLE DEVICE.
- EP28 DEVICE TO SERVE RESIDENTIAL TYPE EXHAUST HOOD (ABOVE COOKING RANGE). COORDINATE ROUGH-IN LOCATION AND REQUIREMENTS WITH EQUIPMENT INSTALLER AND CASEWORK INSTALLER.
- EP31 MOUNT DEVICE BEHIND FREEZER. CONTRACTOR WILL MATCH NEMA CONFIGURATION OF RECEPTACLE WITH UNIT PLUG. COORDINATE PRIOR TO ORDERING RECEPTACLE DEVICE.
- EP32 DEVICE FOR WASHER/DRYER. PROVIDE DEDICATED CIRCUIT. MOUNT DEVICE AT 42" AFF. PROVIDE 2#10 & #10 GND IN 3/4" CONDUIT FOR DRYER.
- EP59 DEDICATED CIRCUIT FOR MICROWAVE. MOUNT DEVICE BEHIND MICROWAVE LOCATION. REFER TO SHEET A-402 FOR ADDITIONAL INFORMATION.
- EP60 DEVICES WILL BE A COMBINATION RECEPTACLE AND USB PORT. USB TYPE WILL BE USB 3.0.

CONSULTANT









Dzilth-Na-O-Dith-Hle - New Dormitory Building
CONSTRUCTION DOCUMENTS

35 Road 7585, Bloomfield, NM 87413

DECEMBER 4, 2020





MARK	DATE	DESCRIPTION
	11/17/20	Addendum Changes
ISSUE:		
DATE:		
PROJECT NO:		751
CAD DWG FILE:		
DRAWN BY:		TLA
CHECKED BY:		JMM

SHEET TITLE
ENLARGED PLANS



GENERAL NOTES

A. COMPLY WITH NFPA 70, 2017 ED. AND NFPA 72 2016 ED.



MARK	DATE	DESCRIPTION
	11/17/20	Addendum Changes

ISSUE:	
DATE:	
PROJECT NO:	751
CAD DWG FILE:	
DRAWN BY:	AMH
CHECKED BY:	JMM

SHEET TITLE
ELECTRICAL DETAIL SHEET

A. LOCATE AIR TERMINALS AS SHOWN. TAKE CARE TO INSURE THAT ALL POINTS ARE WITHIN 2'-0" OF OUTSIDE BUILDING EDGE. OUTSIDE AIR INTAKE SHALL BE PROTECTED BY A MINIMUM OF 2'-0" EXTEND 20'-0" AND THAT MINIMUM PROJECTION ABOVE OPEN PROTECTED IS 10'-0" PROTECTING 24" MAY BE SPACED @ 25'-0" MAXIMUM.

B. CONDUCTOR SHALL BE PROTECTED BY MINIMUM COURSE OF 1/2" CONDUCTOR. INSURE THAT ALL BENDS HAVE AT LEAST AN 8" RADIUS AND DO NOT EXCEED 90 DEGREES.

C. CONDUCTOR SHALL BE INSTALLED WITH LEAD AND BONDING CABLES 3'-0" ON CENTER MAXIMUM. VERIFY COMPATIBILITY OF ADHESIVE ON MEMBRANE ROOF APPLICATION REQUIRED FOR INSTALLATION.

D. ALL WIRING SHALL BE INSTALLED AS SHOWN, BUT IN NO INSTANCE SHALL THEY BE LESS THAN 1"-0" BELOW GRADE AND 2'-0" FROM THE FOUNDATION WALL. DRIVEN RODS SHALL PENETRATE THE FOUNDATION TO 10'-0" MINIMUM.

E. BOND TO WATER AND OTHER PIPING SYSTEMS AS SHOWN AND AS REQUIRED BY CODE.

F. PROVIDE LIGHTNING PROTECTION GROUND TO ELECTRIC, TELEPHONE, AND OTHER BUILDING GROUND SYSTEMS AS SHOWN OR AS REQUIRED BY CODE.

G. ALL MATERIALS ARE TO BE SUBMITTED AS INSURE PROPER CODE COMPLIANCE AND SYSTEM CERTIFICATION. ANY MAJOR VARIANCE SHALL BE SUBMITTED FOR APPROVAL.

H. ALL MATERIALS ARE TO BE SUBMITTED IN ACCORDANCE WITH CERTIFICATION PROCEDURE.

I. ALL MATERIALS ARE TO BE UNDERWRITER'S LABORATORIES APPROVED WITH "K" LABELS ON CONDUCTOR @ 10'-0" INTERVALS.

J. COMPLETED INSTALLATION AS SHOWN SHALL BEAR UL MASTER LABEL "C" TO BE SECURED BY SYSTEM INSTALLER PER UL384.

K. ALL MATERIALS ARE TO BE SUBMITTED IN ALL RESPECTS TO PLI 175. INSTALLATION SHALL BE MADE UNDER THE SUPERVISION OF AN FLI CERTIFIED MASTER INSTALLER.

L. FOR SPECIFICATIONS AND DETAILS SEE 264117 FOR ADDITIONAL INFORMATION AND APPROVED MANUFACTURERS. ALL MATERIALS SHOWN AND INTENDED FOR USE ARE BY:

VFC LIGHTING PROTECTION
90 NORTH CULTRIDGE DRIVE
NORTH SALT LAKE, UTAH 84054
PHONE: (801) 292-2826
FAX: (801) 292-2146
EMAIL: cad@vfc.com

M. INTERNET: www.vfc.com

M. COMPLY WITH NFPA 701, 2017 ED. AND NFPA 72 2016 ED.

- A. TYPICAL BODIES OF CONDUCTANCE AS NOTED BELOW. USE FULL SIZE CONDUCTOR AND APPROPRIATE FITTING SHOWN FOR CONNECTION.
- B. (PLUMBING STACK) REQUIRES BONDING WITH MAIN SIZE CABLE ONLY. FITTING 6-07 (1/28IN) OF LIGHTNING PROTECTION SYSTEM.
- C. TYPICAL BODIES OF INDUCTANCE AS NOTED BELOW. USE SECONDARY SIZE (SMALLER) CONDUCTOR AND APPROPRIATE FITTING SHOWN FOR CONNECTION.
- D. BONDING CONNECTIONS AND FITTINGS SHOWN ARE TYPICAL. FITTINGS, MATERIAL CONDITIONS REQUIRED TO MEET CODES AS NOTED BELOW. ADJUST FITTING TYPE AS REQUIRED TO SUIT FIELD CONDITIONS.




DECEMBER 4, 2020



ISSUE:	
DATE:	
PROJECT NO:	751
CAD DWG FILE:	
DRAWN BY:	AMH
CHECKED BY:	JMM

LIGHTNING PROTECTION DETAILS


E-502




NO SCALE



NO SCALE




NO SCALE










NOTE: INSTALLATION OF DOWNLOAD CABLE WILL VARY AT EACH LOCATION SHOWN ON SHEET "EP141". REFER TO ARCHITECTURAL WALL SECTIONS FOR ADDITIONAL INFORMATION FOR THE VARIOUS INSTALLATIONS. COORDINATE INSTALLATION PRIOR TO COMMENCEMENT OF ANY WORK.

NO SCALE



All fasteners to be VFC ZEROPEN #ZP3412 with appropriate loop supports. No support penetrations shall be made in any sheet metal flashing or roof top equipment. Sheet metal screws shall not be used. Appropriate adhesive supports and construction mastic may be used on Membrane roof surfaces only. Adhesive supports and construction mastic shall not be used on any sheet metal surfaces.

The contractor shall furnish 10 Year Adhesion Warranty on the VFC ZEROPEN fastener system.



USE TO SPLICE MAIN
SIZE CONDUCTOR TO
MAIN SIZE CONDUCTOR

NO SCALE

NO SCALE

COPPER FEEDER SCHEDULE				
NOTE: ALL CONDUCTORS ARE COPPER, TYPE THWN/THHN UNLESS OTHERWISE NOTED.				
DESIGNATION	CONDUCTORS	GROUND	CONDUIT	NOTES
THREE PHASE THREE WIRE & GROUND FEEDER				
20A	3#12	12	3/4"	
25A	3#10	10	3/4"	
30A	3#10	10	3/4"	
35A	3#8	10	3/4"	
40A	3#8	10	3/4"	
45A	3#8	10	3/4"	
50A	3#8	10	3/4"	
60A	3#6	10	1"	
70A	3#4	8	1 1/4"	
80A	3#4	8	1 1/4"	
90A	3#2	8	1 1/4"	
100A	3#2	8	1 1/4"	
125A	3#1	6	1 1/2"	
150A	3#1/0	6	1 1/2"	
175A	3#2/0	6	2"	
200A	3#3/0	6	2"	
225A	3#4/0	4	2 1/2"	
250A	3-250 KCML	4	3"	
300A	3-350 KCML	4	3"	
350A	3-500 KCML	2	4"	
400A	3-600 KCML	2	4"	
450A	(2) 3#4/0	(2) 2	(2) 2 1/2"	
500A	(2) 3-250 KCML	(2) 2	(2) 3"	
600A	(2) 3-350 KCML	(2) 1	(2) 3"	
700A	(2) 3-500 KCML	(2) 1	(2) 4"	
800A	(2) 3-600 KCML	(2) 1/0	(2) 4"	
1000A	(3) 3-400 KCML	(3) 2/0	(3) 3"	
1200A	(3) 3-600 KCML	(3) 3/0	(3) 4"	
1600A	(4) 3-600 KCML	(4) 4/0	(4) 4"	
2000A	(5) 3-600 KCML	(5) 250 KCML	(5) 4"	
2500A	(6) 3-600 KCML	(6) 350 KCML	(6) 4"	
3000A	(8) 3-600 KCML	(8) 400 KCML	(8) 4"	
4000A	(10) 3-600 KCML	(10) 500 KCML	(10) 4"	
THREE PHASE FOUR WIRE & GROUND FEEDER				
20Y	4#12	12	3/4"	
25Y	4#10	10	3/4"	
30Y	4#10	10	3/4"	
35Y	4#8	10	3/4"	
40Y	4#8	10	3/4"	
45Y	4#8	10	3/4"	
50Y	4#8	10	3/4"	
60Y	4#6	10	1"	
70Y	4#4	8	1 1/4"	
80Y	4#4	8	1 1/4"	
90Y	4#2	8	1 1/4"	
100Y	4#2	8	1 1/4"	
125Y	4#1	6	1 1/2"	
150Y	4#1/0	6	2"	
175Y	4#2/0	6	2"	
200Y	4#3/0	6	2"	
225Y	4#4/0	4	2 1/2"	
250Y	4-250 KCML	4	3"	
300Y	4-350 KCML	4	3"	
350Y	4-500 KCML	2	4"	
400Y	4-600 KCML	2	4"	
450Y	(2) 4#4/0	(2) 2	(2) 2 1/2"	
500Y	(2) 4-250 KCML	(2) 2	(2) 3"	
600Y	(2) 4-350 KCML	(2) 1	(2) 3"	
700Y	(2) 4-500 KCML	(2) 1	(2) 4"	
800Y	(2) 4-600 KCML	(2) 1/0	(2) 4"	
1000Y	(3) 4-400 KCML	(3) 2/0	(3) 3"	
1200Y	(3) 4-600 KCML	(3) 3/0	(3) 4"	
1600Y	(4) 4-600 KCML	(4) 4/0	(4) 4"	
2000Y	(5) 4-600 KCML	(5) 250 KCML	(5) 4"	
2500Y	(6) 4-600 KCML	(6) 350 KCML	(6) 4"	
3000Y	(8) 4-600 KCML	(8) 400 KCML	(8) 4"	
4000Y	(10) 4-600 KCML	(10) 500 KCML	(10) 4"	
5000Y	(12) 4-600 KCML	(12) 700 KCML	(12) 4"	
THREE PHASE FOUR WIRE 200% NEUTRAL & GROUND FEEDER				
100Y-E	3#1, 2#1 NEUTRAL	2	2"	
150Y-E	3#3/0, 2#3/0 NEUTRAL	2	2 1/2"	
225Y-E	3-300 KCML, 2-300 KCML NEUTRAL	2	3"	
350Y-E	(2) 3#4/0, (2) 2#4/0 NEUTRAL	(2) 1	(2) 2 1/2"	
400Y-E	(2) 3-250 KCML, (2) 2-250 KCML NEUTRAL	(2) 1	(2) 2 1/2"	
500Y-E	(2) 3-350 KCML, (2) 2-350 KCML NEUTRAL	(2) 1/0	(2) 3"	

C1 COPPER FEEDER SCHEDULE

NONE

ALUMINUM FEEDER SCHEDULE				
NOTE: ALL CONDUCTORS ARE ALUMINUM, TYPE THWN/THHN UNLESS OTHERWISE NOTED.				
DESIGNATION	CONDUCTORS	CONDUCTOR(S)	CONDUIT	NOTES
THREE PHASE THREE WIRE & GROUND FEEDER				
200A	3-250 KCML	2	2 1/2"	
225A	3-300 KCML	2	3"	
250A	3-350 KCML	2	3"	
300A	3-500 KCML	2	4"	
350A	(2) 3#4/0	(2) 1	(2) 2 1/2"	
400A	(2) (3-250 KCML)	(2) 1	(2) 2 1/2"	
450A	(2) (3-300 KCML)	(2) 1/0	(2) 3"	
500A	(2) (3-350 KCML)	(2) 1/0	(2) 3"	
600A	(2) (3-500 KCML)	(2) 2/0	(2) 4"	
700A	(3) (3-350 KCML)	(3) 3/0	(3) 3"	
800A	(3) (3-400 KCML)	(3) 3/0	(3) 3"	
1000A	(3) (3-600 KCML)	(4) 4/0	(4) 4"	
1200A	(4) (3-600 KCML)	(4) 250	(4) 4"	
1600A	(5) (3-600 KCML)	(5) 350	(5) 4"	
2000A	(6) (3-600 KCML)	(6) 400	(6) 4"	
2500A	(8) (3-600 KCML)	(8) 600	(8) 4"	
3000A	(9) (3-600 KCML)	(9) 600 KCML	(9) 4"	
4000A	(12) (3-600 KCML)	(12) 600 KCML	(12) 4"	
THREE PHASE FOUR WIRE & GROUND FEEDER				
200Y	4-250 KCML	2	3"	
250Y	4-350 KCML	2	3"	
300Y	4-500 KCML	2	4"	
350Y	(2) 4#4/0	(2) 1	(2) 2 1/2"	
400Y	(2) (4-250 KCML)	(2) 1	(2) 3"	
450Y	(2) (4-300 KCML)	(2) 1/0	(2) 3"	
500Y	(2) (4-350 KCML)	(2) 1/0	(2) 3"	
600Y	(2) (4-500 KCML)	(2) 2/0	(2) 4"	
700Y	(3) (4-350 KCML)	(3) 3/0	(3) 3"	
800Y	(3) (4-400 KCML)	(3) 3/0	(3) 4"	
1000Y	(4) (4-600 KCML)	(4) 4/0	(4) 4"	
1200Y	(4) (4-500 KCML)	(4) 250	(4) 4"	
1600Y	(5) (4-600 KCML)	(5) 350	(5) 4"	
2000Y	(6) (4-600 KCML)	(6) 400	(6) 4"	
2500Y	(8) (4-600 KCML)	(8) 600 KCML	(8) 4"	
3000Y	(9) (4-600 KCML)	(9) 600 KCML	(9) 4"	
4000Y	(12) (4-600 KCML)	(12) 600 KCML	(12) 4"	
THREE PHASE FOUR WIRE 200% NEUTRAL & GROUND FEEDER				
100Y-E	3#1, 2#1 NEUTRAL	2	2"	
150Y-E	3#3/0, 2#3/0 NEUTRAL	2	2 1/2"	
225Y-E	3-300 KCML, 2-300 KCML NEUTRAL	2	3"	
350Y-E	(2) 3#4/0, (2) 2#4/0 NEUTRAL	(2) 1	(2) 2 1/2"	
400Y-E	(2) 3-250 KCML, (2) 2-250 KCML NEUTRAL	(2) 1	(2) 2 1/2"	
500Y-E	(2) 3-350 KCML, (2) 2-350 KCML NEUTRAL	(2) 1/0	(2) 3"	

C2 ALUMINUM FEEDER SCHEDULE

NONE

FAULT CURRENT CALCULATIONS																					
Source		DESCRIPTION										Assumptions: 1) 600 Volt rated conductors/cables only.									
Fault Point	Equipment	SES Size (Amps)	XFMR Size (kVA)	XFMR mounting	Primary Voltage	Secondary Voltage	Phase	Xfmr FLA (Amps)	Xfmr Impedance e (Ohms)	Xfmr Impedance e adjusted value	Let-Thru Short Current	Manual input Let-Thru Short Current	Value based on JMEZ available Fault								
SF	MSB	1200	500	PAD	12470	480	3	601	5.75			65000									
KNOWN FAULT INFORMATION						SECOND TRANSFORMER IN SYSTEM (DRY-TYPE)						FEEDER/BRANCH CIRCUIT CALCULATION						RESULT			
Fault Point	Equipment	Source of Fault	Available Fault Current	Voltage	PHASE	XFMR Size (kVA)	Secondary Voltage	Xfmr Impedance e (Ohms)	Xfmr Impedance e (user input)	"I" factor	"M" factor	Conductor Type	Conductor Size	3 single conductor s?	Conduit Type	Number of sets	Length to fault	"C" value	"I" factor	"M" factor	Available Short Circuit Current at Fault
F1	MSB	UT1	65000	480	3							C	600	Y	P	3	72	28033	0.201	0.833	54141
F2	DDPH1	MSB	54141	480	3							C	600	Y	P	1	142	28033	0.988	0.503	27228
F3	PRI-DT1A	DDPH1	27228	480	3							C	3/0	Y	S	1	30	12844	0.229	0.814	22151
F4	SEC-DT1A	PRI-DT1A	22151	208	3	112.5	208	1.07		0.76	0.569										12593
F5	DL1A	SEC-DT1A	12593	208	3							C	600	Y	S	1	30	22965	0.137	0.880	11077
F6	MPA	DDPH1	27228	480	3							C	4/0	Y	S	1	130	15082	0.846	0.542	14751
F7	PRI-DT2A	DDPH1	27228	480	3							C	3/0	Y	S	1	130	12844	0.993	0.502	13660
F8	SEC-DT2A	PRI-DT2A	13660	208	3	112.5	208	1.07		0.47	0.681										9305
F9	DPLA	SEC-DT2A	9305	208	3							C	600	Y	S	1	30	22965	0.101	0.908	8450
F10																					
F11	PRI-TUP	MSB	54141	480	3							C	6	Y	P	1	30	2430	2.409	0.293	15882
F12	SEC-TUP	PRI-TUP	15882	208	3	30	208	1.00		1.91	0.344										5463
F13	UP	SEC-TUP	5463	208	3							C	2	Y	P	1	30	6044	0.226	0.816	4458

D3 FAULT CURRENT CALCULATION

1" = 1'-0"

VOLTAGE DROP CALCULATIONS

Project: Dzilh-Na-O-Dith-Hle CS
Project No: 8226
Estimator: Joseph Montana
Calc by: Tacy Austin
Date: 8-Jun-20

Maximum voltage drop for a Branch Circuit shall be less than 3% (NEC 210.19.A. FPN 4).
Maximum voltage drop for a Feeder shall be less than 3% (NEC 215.2. FPN 2).
Maximum combined voltage drop for a Feeder and Branch shall be less than 5%.

Run	Feeder or Branch Circuit Run:	Type of Circuit	Voltage	Phase	Conductor Material	Length (ft)	Size	Load Current (Amps)	Qty Parallel Runs	Load on feeder	Resistance	Voltage Drop	End Voltage	% Voltage Drop Feeder	% Voltage Drop Branch
1	UT1 to MSB	Feeder	480.0	3	C	72	600	1600	3	533	0.021	1.42	478.58	0.30%	
2	MSB to DDPH1	Feeder	480.0	3	C	142	600	400	1	400	0.021	2.11	477.89	0.44%	
3	DDPH1 to DT1A	Feeder	480.0	3	C	30	3/0	200	1	200	0.077	0.80	479.20	0.17%	
4	DT1A to DL1A	Feeder	208.0	3	C	30	600	400	1	400	0.021	0.44	207.56	0.21%	
5	DDPH1 to MPA	Feeder	480.0	3	C	130	4/0	225	1	225	0.061	3.08	476.92	0.64%	
6	DDPH1 to DT2A	Feeder	480.0	3	C	130	3/0	200	1	200	0.077	3.45	476.55	0.72%	
7	DT2A to DPLA	Feeder	208.0	3	C	30	600	400	1	400	0.021	0.44	207.56	0.21%	
8															
9	MSB to TUP	Feeder	480.0	3	C	30	6	60	1	60	0.491	1.53	478.47	0.32%	
10	TUP to UP	Feeder	208.0	3	C	30	2	100	1	100	0.194	1.01	206.99	0.48%	

C3 VOLTAGE DROP CALCULATION

1" = 1'-0"

GENERAL NOTES


- PANELBOARD AIC RATINGS ARE INDICATED ON THE PANEL SCHEDULES.
- INFORMATION SHOWN IS DIAGRAMMATIC AND IS NOT INTENDED TO REPRESENT PHYSICAL ARRANGEMENTS, LOCATIONS, ROUTING OR CONNECTIONS. PHYSICAL LAYOUTS ARE TO BE PER FIELD CONDITIONS AND AS INDICATED ELSEWHERE IN THE ELECTRICAL PLANS.
- REFERENCE THE SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS REGARDING EQUIPMENT AND INSTALLATION. NOT ALL INFORMATION IS SHOWN ON THIS DIAGRAM.
- ALL PANELS WILL HAVE DOOR-IN-DOOR, EACH DOOR KEY LOCKABLE, ACCESSIBILITY FOR EACH PANEL.
- CONTRACTOR WILL MEASURE AND TORQUE ALL PANEL FEEDERS, MEASURE RESISTANCE TO GROUND AT SERVICE GROUND AND PROVIDE WRITTEN DOCUMENTATION OF TEST RESULTS. CONTRACTOR WILL COORDINATE TIME SO THAT SCHOOL REPRESENTATIVE IS PRESENT DURING TEST.
- CONTRACTOR WILL LABEL ALL DISTRIBUTION EQUIPMENT PRIOR TO FINAL OBSERVATION WALK THROUGH.
- REFER TO GROUNDING DIAGRAM ON SHEET E-602.
- ALL ELECTRICAL EQUIPMENT DIRECTORIES WILL BE TYPED.
- COMPLY WITH NFPA 70, 2017 ED. AND NFPA 72 2016 ED.

KEYNOTES

- REFER TO SHEET ES-601 FOR CONTINUATION OF ELECTRICAL DISTRIBUTION.
- REFER TO SHEET E-601S FOR CONTINUATION OF ELECTRICAL DISTRIBUTION IN SCHOOL BUILDING.
- REFER TO SHEET ES-601 FOR ADDITIONAL INFORMATION ON NEW MSB.
- SOLID STATE, ELECTRONIC TRIP CIRCUIT BREAKER WITH LONGTIME, SHORT-TIME, INSTANTANEOUS FUNCTIONS. 100% RATED WITH ADJUSTABLE SETTINGS. PROVIDE WITH ENERGY REDUCTION MAINTENANCE SWITCH.
- MOLDED CASE, THERMAL-MAGNETIC CIRCUIT BREAKERS WITH LOCKABLE CAPABILITIES.
- SPD MOUNTED INTERNALLY TO SWITCHBOARD/PANELBOARD. REFERENCE SECTION 264313 FOR ADDITIONAL INFORMATION.
- REFER TO SHEET E-602 FOR GROUNDING INFORMATION FOR THIS EQUIPMENT.
- PROVIDE TWO (2) SPARE CIRCUIT BREAKERS; AS INDICATED.
- PROVIDE TWO (2) SPARE ONLY FOR FUTURE CIRCUIT BREAKERS; SIZE AS INDICATED.
- INTEGRAL POWER MONITOR IN ELECTRICAL GEAR. REFER TO SPECIFICATION 262413 FOR METERING INSTRUMENTATION REQUIREMENTS AND ADDITIONAL SWITCHBOARD INFORMATION.
- PROVIDE REVERSIBLE BREAKER FOR PHOTOVOLTAIC SYSTEM.
- EXTEND RACEWAY AND CONDUCTORS TO PHOTOVOLTAIC MAIN DISCONNECTING MEANS AND TERMINATE. VENDOR TO PROVIDE ALL RACEWAY, WIRING AND EQUIPMENT FOR PHOTOVOLTAIC SYSTEM.

Electrical Service Calc.-DCS Dormitory - Project #8226.							
Description of Load		Connected Load KVA	Demand % Multiplier	Demand Load KVA	Service % Multiplier	Service Load KVA	Notes
Lighting Interior		6	100%	6	125%	8	1,2,3
Lighting Exterior		1	100%	1	125%	1	3
Receptacle		68	First 10KVA @ 100% Remmder over 10KVA @ 50%	39	100%	39	
Largest Motor		43	125%	54	100%	54	
All other Motors		103	100%	103	100%	103	
Non-continuous loads		22	100%	22	100%	22	
Kitchen Equipment		7	6 and more @ 65%	4	100%	4	
Subtotal of loads KVA		249		229		231	
Future Capacity				25%		58	
Total Service load KVA						288	
Voltage of Service (480-3PH)						0.831	
Total Service Ampacity						347	
13,889 Sq. Ft.		0.43 watts/sq.ft. for lighting loads	=	6,000 VA			
13,889 Sq. Ft.		0.07 watts/sq.ft. for exterior lighting load	=	1,000 VA			
13,889 Sq. Ft.		4.90 watts/sq.ft. for receptacle loads	=	68,000 VA			
13,889 Sq. Ft.		10.51 watts/sq.ft. for mechanical loads	=	146,000 VA			
13,889 Sq. Ft.		1.57 watts/sq.ft. for non-continuous loads	=	21,800 VA			
13,889 Sq. Ft.		0.47 watts/sq.ft. for kitchen loads	=	6,500 VA			
NOTES							
1. Meets required New Mexico State energy requirement. IECC required educational space watts/sq.ft. of 1.2.							
2. Occupancy sensors were utilized through building for control to meet requirements of IECC.							
3. A programmable system is also used for automatic control for energy savings.							

A2 ELECTRICAL GROUNDING DIAGRAM
1/8" = 1'-0"



GENERAL NOTES

- A. INSTALL GROUNDING CONNECTIONS TO BUILDING STRUCTURE AND WATER PIPES AT LOCATIONS THAT ARE VISIBLE AND ACCESSIBLE FOR INSPECTION, MAINTENANCE, AND TESTING.
- B. INSTALL AN INSULATED THROAT GROUNDING BUSHING ON EACH METALLIC SERVICE ENTRANCE CONDUIT. BOND TO SERVICE ENTRANCE EQUIPMENT GROUND BUS USING NEC TABLE 250.102 (C)(1).
- C. INSTALL AN INSULATED THROAT GROUNDING BUSHING ON EACH METALLIC FEEDER CONDUIT. BOND TO GROUND BUS USING CONDUCTOR THAT IS SIZED EQUAL TO EQUIPMENT GROUNDING CONDUCTOR.
- D. BOND ELECTRICAL EQUIPMENT ENCLOSURES TO GROUND BAR USING SAME SIZE CONDUCTOR AS FEEDER EQUIPMENT GROUND CONDUCTOR OR FACTORY PROVIDED GREEN SCREW.
- E. CLEAN COATED RE-BAR PRIOR TO PERFORMING ELECTRICAL CONNECTIONS.
- F. COMPLY WITH NFPA 70, 2011 ED. AND NFPA 72 2016 ED.

KEYNOTES

- 1. REFER TO ONE-LINE DIAGRAM AND FEEDER SCHEDULE FOR GROUNDING CONDUCTOR SIZE.
- 2. CONNECT GROUNDING ELECTRODE CONDUCTOR TO GROUND ROD.
- 3. FOR EQUIPMENT GROUNDING CONDUCTOR SIZE REFER TO ONE-LINE DIAGRAM AND FEEDER SCHEDULE.
- 4. PROVIDE GROUNDING ELECTRODE CONDUCTOR SIZE BASED ON THE CONDUCTOR SIZE OF THE SECONDARY OF THE TRANSFORMER. SIZE PER NEC 250.66 AND PER SCHEDULE ON THIS SHEET.
- 5. COVER THE EXTERIOR LIGHTNING PROTECTION DOWN CONDUCTOR WITH NON-CONDUCTIVE MATERIAL FROM THE FINAL GRADE TO 8' ABOVE FINISHED FLOOR.
- 6. BOND EACH PERIMETER STRUCTURAL STEEL COLUMN TO THE CONCRETE-ENCASED MAIN GROUNDING ELECTRODE. USE EXOTHERMIC WELDS FOR SINGLE POINT GROUNDING. LOCATE AT AN ACCESSIBLE POINT NEAR THE SERVICE ENTRANCE EQUIPMENT. MAKE OTHER CONNECTIONS TO THE GROUND BAR USING TWO-HOLE COMPRESSION SPADE LUGS THAT MEET IEEE 837 REQUIREMENTS. LABEL EACH CONNECTION.
- 7. PROVIDE A 1/4" X 4" X 12" MAIN GROUNDING ELECTRODE GROUND BAR FOR EACH TELECOMMUNICATIONS ROOM. CONNECT CABLES TO THE TELECOMMUNICATIONS GROUNDING BUSBAR USING COMPRESSION SPADE LUGS. LABEL CONDUCTORS PER ANSI-JSTD-607-A. LABEL EACH CONNECTION. SEE PLAN FOR BAR LENGTH AND LOCATIONS.
- 8. BONDING JUMPER SIZED PER GROUNDING ELECTRODE CONDUCTOR SCHEDULE THIS SHEET.
- 9. INSTALL A 1/4" X 4" COPPER "TELECOMMUNICATIONS GROUNDING BUSBAR" IN EACH TELECOMMUNICATIONS ROOM. CONNECT CABLES TO THE TELECOMMUNICATIONS GROUNDING BUSBAR USING COMPRESSION SPADE LUGS. LABEL CONDUCTORS PER ANSI-JSTD-607-A. LABEL EACH CONNECTION. SEE PLAN FOR BAR LENGTH AND LOCATIONS.
- 10. BONDING JUMPER SIZED PER GROUNDING ELECTRODE CONDUCTOR SCHEDULE THIS SHEET.
- 11. BOND HOT WATER PIPE TO COLD WATER PIPE AT EACH WATER HEATER WITH A #6 BARE COPPER CONDUCTOR.
- 12. PROVIDE A GROUND RING PER NEC 250.52 A.4.
- 13. PROVIDE A GROUND ROD PER NEC 250.52 A.5.
- 14. BOND ALL METALLIC PIPING SYSTEMS WITHIN STRUCTURE.
- 15. PROVIDE A GROUNDING ELECTRODE SYSTEM PER 2014 NMEC.
- 16. MAIN BONDING JUMPER AND/OR SYSTEM BONDING JUMPER SIZE BASED ON UNGROUNDING CONDUCTOR SIZE AND GROUNDING ELECTRODE CONDUCTOR SCHEDULE ON THIS SHEET UNLESS UNGROUNDING CONDUCTOR SIZE OR EQUIVALENT IS GREATER THAN 1100 KCMIL. IF GREATER THAN 1100 KCMIL (OR 1750 KCMIL FOR ALUMINUM) SIZE JUMPER PER NEC TABLE 250.102 (C)(1).
- 17. LIGHTNING PROTECTION COUNTERPOISE - #40 BARE COPPER.
- 18. BOND EACH CORNER STRUCTURAL STEEL AND PERIMETER STRUCTURAL STEEL AT NO MORE THAN 50 FOOT SPACING TO THE LIGHTNING PROTECTION COUNTERPOISE.
- 19. COVER THE EXTERIOR LIGHTNING PROTECTION DOWN CONDUCTOR WITH NON-CONDUCTIVE MATERIAL FROM THE FINAL GRADE TO 8' ABOVE FINISHED FLOOR.

CONSULTANT

Dzilth-Na-O-Dith-Hle - New Dormitory Building
CONSTRUCTION DOCUMENTS

35 Road 7585, Bloomfield, NM 87413


DECEMBER 4, 2020

MARK	DATE	DESCRIPTION
	11/17/20	Addendum Changes
ISSUE:		
DATE:		
PROJECT NO:		751
CAD DWG FILE:		
DRAWN BY:		TLA
CHECKED BY:		JMM

SHEET TITLE
GROUNDING DIAGRAM

LEED LPD - DCS DORMITORY - <i>Building Area Method.</i>							
Description of Load		Connected Load KVA	Demand % Multiplier	Demand Load KVA	Service % Multiplier	Service Load KVA	Notes
Lighting Interior		6	100%	6	125%	8	1,2,3
Lighting Exterior		1	100%	1	125%	1	3
13,889 Sq. Ft.		0.45 Watts/Sq. ft. for Interior Lighting loads =				6,300 VA	
13,889 Sq. Ft.		0.05 Watts/Sq. ft. for Exterior Lighting loads=				740 VA	
NOTES							
1. Meets required New Mexico State energy requirement. IECC required educational space							
2. Sensors were utilized through out building for control to meet requirements of IECC.							
3. A programmable system is also used for automatic control for energy savings.							
LEED Plug & Process Loads - DCS DORMITORY							
Description of Load		Connected Load KVA	Demand % Multiplier	Demand Load KVA	Service % Multiplier	Service Load KVA	Notes
Plug Loads Overall		68	First 10KVA @ 100% Remainder over 10KVA @ 50%	39	100%	39	
Plug & Process Loads		12	First 10KVA @ 100% Remainder over 10KVA @ 50%	11	100%	11	
13,889 Sq. Ft.		4.90 Watts/Sq. ft. for Plug loads Overall =				68,000 VA	
13,889 Sq. Ft.		0.83 Watts/Sq. ft. for Plug Process loads =				11,500 VA	
NOTES							

D3 LIGHTING POWER DENSITY- DORM
1" = 1'-0"



D4 FIRE ALARM RISER DIAGRAM
NO SCALE

GENERAL NOTES

- A. FIRE ALARM DIAGRAM INDICATES GENERAL DIAGRAMMATIC CONNECTIONS ONLY. ALL CONNECTIONS AND INSTALLATION WILL BE PER FIRE ALARM SYSTEM MANUFACTURER'S SHOP DRAWINGS.
- B. SEE CLOUDSHEET FOR ADDITIONAL INFORMATION ON THIS DRAWING. REFER TO "FA" SHEET SERIES FOR ADDITIONAL INFORMATION.
- C. REFER TO SPECIFICATION SECTION 283111 FOR FIRE ALARM SYSTEM REQUIREMENTS.
- D. FIRE ALARM WIRING AND CABLING SHALL BE IN CONFORMANCE WITH NEC AND TYPE SHALL BE AS RECOMMENDED BY FIRE ALARM SYSTEM MANUFACTURER.
- E. ALL PENETRATIONS THROUGH WALLS, FLOOR, CEILING AND ROOF PER PENETRATIONS SPECIFIED REQUIREMENTS. SEAL WILL MATCH THE FIRE RATING OF EACH PENETRATION LOCATION.
- F. COMPLY WITH, BUT NOT LIMITED TO NFPA 70, 72, 5000 AND 2017 ED.
- G. REFER TO SHEET FA-101 FOR FIRE ALARM SYSTEM INFORMATION.

IT IS THE INTENT OF THESE DOCUMENTS TO SHOW A BASIC REPRESENTATION OF THE FIRE ALARM SYSTEM. DEVICES INDICATED ON THESE DOCUMENTS ARE IN NO WAY IMPLIED TO BE COMPREHENSIVE OF THE FINAL DESIGN. IT IS THE RESPONSIBILITY OF THE FIRE ALARM CONTRACTOR TO PROVIDE A DESIGN/BUILD FIRE ALARM SYSTEM BASED UPON A THOROUGH REVIEW OF ALL CONTRACT DOCUMENTS. IT IS THE POLICY OF THE FIRE ALARM CONTRACTOR TO INSURE THAT THE FIRE ALARM SYSTEM IS CODE COMPLIANT, MEETS THE REQUIREMENTS OF THE AHJ AND COMPREHENSIVELY COVERS AND INCLUDES ALL NECESSARY PARTS AND LABOR ASSOCIATED WITH OTHER TRADES AND SYSTEMS IMPACTING THE FIRE ALARM SYSTEM. NO CHANGE ORDERS SHALL BE APPROVED FOR THE BASE SCOPE OF WORK.

ENTIRE FIRE ALARM SYSTEM WILL BE IN RACEWAYS; NO EXCEPTIONS

KEYNOTES

1. MINIMUM 3/4" CONDUIT AND FIRE ALARM CABLE AS REQUIRED BY THE FIRE ALARM MANUFACTURER
2. NOTIFY THE SUPERVISOR EACH FLOW AND TAMPER SWITCH WITH AN ACCESSIBLE MODEL. REFERENCE TO FIRE PROTECTION PLUMBING PLANS FOR EACH LOCATION
3. PROVIDE CONTROL PANEL (FACP) WILL BE FACTORY MANUFACTURED, UL LABELED PANELS, THE FACP WILL ENCLOSE ALL TERMINATIONS FOR DEVICES ON THE FLOOR OR AREA IT SERVES. INTELLIGENT CABLES AS REQUIRED OR INDEPENDENT POWER SUPPLIES AND STANDBY BATTERIES WILL BE PROVIDED AT EACH LOCATION
4. DIGITAL COMMUNICATOR CONNECTS TO TELEPHONE TERMINAL BOARD FOR REMOTE COMMUNICATION TO FIRST RESPONDERS AND/OR OWNERS SECURITY REPRESENTATIVE
5. WHERE POWER SUPPLIES (PS) ARE INSTALLED OUTSIDE OF FAC/PACT, CONTRACTOR WILL PROVIDE 120V/24V POWER CIRCUIT TO UNITS FROM NEAREST PANEL
6. PROVIDE 120V/24V POWER CIRCUIT TO EACH DEVICE BY THE FIRE ALARM INSTALLER AT TIME OF SUBMITTAL TO VERIFY NEED
7. DIGIT SMOKE DETECTOR, FURNISHED BY DIVISION 28, INSTALL AND WIRE BY DIVISION 28. CONTRACTOR TO PROVIDE MECHANICAL INTERCONNECTIONS. REFERENCE TO MECHANICAL CONDUIT DIAGRAMS FOR MECHANICAL INTERCONNECTIONS. PROVIDE DUET DETECTORS IN NEW AND EXISTING UNITS WHERE 2000CPI AND ABOVE EXIST. INSTALL PERMANENTLY
8. FIRE SMOKE DAMPER, LOWVOLT 120V/24V VIA FIRE ALARM ADDRESSABLE RELAY
9. PROVIDE SURGE PROTECTION FOR CIRCUIT TO FIRE ALARM PANEL
10. POST SIGNAGE TO ADVISE OF THE SYSTEM. SEE 105-101 FOR ADDITIONAL INFORMATION. PROVIDE 3/4" CONDUIT FOR A CONNECTION
11. REFER TO SIGHT SERIES 12P FOR CIRCUITS SERVING THIS SYSTEM
12. PROVIDE ELECTRIC ALARM TYPED TO SHEET 105-101 FOR ADDITIONAL INFORMATION



**Dzilh-Na-O-Dith-Hle - New
Dormitory Building
CONSTRUCTION
DOCUMENTS**

35 Road 7585, Bloomfield, NM
87413

DECEMBER 4, 2020

MARK	DATE	DESCRIPTION
	11/17/20	Addendum Changes
ISSUE:		
DATE:		
PROJECT NO:		751
CAD DWG FILE:		
DRAWN BY:		AMH
CHECKED BY:		JMM

SHEET TITLE

ELECTRICAL FIRE RISER DIAGRAM

LIGHTING SEQUENCE OF OPERATION

A1. BEDROOMS (GRADES 4-12):	1. ROOM LIGHTING WILL BE ENABLED AND DISABLED BY A SWITCH LOCATED AT THE CONTROL DESK.
	2. SWITCH WILL CONTROL LIGHTING IN BEDROOMS ON AND OFF PER SCHEDULE OF THE DORM PERSONNEL.
A2. HONORS BEDROOM:	1. ROOM LIGHTING WILL BE ENABLED AND DISABLED BY A SINGLE PILOT LIGHT TOGGLE SWITCH ON THE OUTSIDE OF THE ROOM.
	2. SWITCH WILL CONTROL LIGHTING IN BEDROOMS ON AND OFF PER SCHEDULE OF THE DORM PERSONNEL.
A3. ISOLATION BEDROOM:	1. ROOM LIGHTING WILL BE ENABLED AND DISABLED BY A SINGLE TOGGLE SWITCH IN THE ROOM.
	2. SWITCH WILL CONTROL LIGHTING IN BEDROOMS ON AND OFF PER SCHEDULE OF THE DORM PERSONNEL.
A4. BEDROOMS (GRADES 1-3):	1. ROOM LIGHTING WILL BE ENABLED AND DISABLED BY A SWITCH LOCATED AT THE CONTROL DESK.
	2. SWITCH WILL CONTROL LIGHTING IN BEDROOMS ON AND OFF PER SCHEDULE OF THE DORM PERSONNEL.
A5. RESTROOMS (GRADES 1-3):	1. UNOCCUPIED MODE: WHEN ROOM IS UNOCCUPIED, ALL LIGHTING IN ROOM SHALL BE DISABLED AND DE-ENERGIZED BY OCCUPANCY SENSOR(S) IN ROOM.
	2. OCCUPIED MODE: a. LIGHTING IN ROOM WILL BE CONTROLLED WITH A KEYSWITCH AS YOU ENTER ROOM AND WILL BE LEFT IN THE ON POSITION.
B. OFFICES, RECEPTION:	1. UNOCCUPIED MODE: WHEN ROOM IS UNOCCUPIED, ALL LIGHTING IN ROOM SHALL BE DISABLED AND DE-ENERGIZED BY VACANCY SENSOR(S) IN ROOM.
	2. OCCUPIED MODE: a. LIGHTING CONTROL IN ROOM WILL BE ENABLED BY PUSH BUTTON SWITCHES AT ENTRY TO ROOM. NO LUMINAIRES WILL AUTOMATICALLY ENERGIZE.
C. FACULTY LOUNGE/WORKROOM, GROUP STUDY, SEMINAR, RECEPTION COVE:	1. UNOCCUPIED MODE: WHEN ROOM IS UNOCCUPIED, ALL LIGHTING IN ROOM WILL BE DISABLED AND DE-ENERGIZED BY VACANCY SENSOR(S) IN ROOM.
	2. OCCUPIED MODE: a. LIGHTING CONTROL IN ROOM WILL BE ENABLED BY PUSH BUTTON SWITCHES AT ENTRY TO ROOM. NO LUMINAIRES WILL AUTOMATICALLY ENERGIZE.
D. ROOM CONTROLLER SERIES LMRC RATED FOR PROGRAMMING CONTROL:	1. ROOM CONTROLLER SERVES LMRC RATED FOR PROGRAMMING CONTROL.
	2. DUAL TECHNOLOGY VACANCY SENSOR SERIES LMDC.
E. RESTROOMS:	1. OCCUPANCY SENSOR WILL AUTOMATICALLY TURN ON ALL LUMINAIRES AS PEOPLE ENTER ROOM.
	2. LUMINAIRES CAN ALSO BE ENABLED BY SWITCH LOCATED AT ENTRY TO ROOM.
F. STORAGE, JANITORS:	1. OCCUPANCY SENSOR WILL AUTOMATICALLY TURN ON ALL LUMINAIRES AS PEOPLE ENTER ROOM.
	2. LUMINAIRES CAN ALSO BE ENABLED BY ON/OFF SWITCH.
G. ELECTRICAL, MFD/ID, MECHANICAL, FIRE RISER:	1. ALL LUMINAIRES IN ROOM WILL BE ENGAGED BY SWITCHES. THESE LUMINAIRES WILL NOT AUTOMATICALLY ENERGIZE OR DE-ENERGIZE.
	2. PROVIDE THE FOLLOWING FOR CONTROL:
H. CORRIDORS FOR BEDROOM WINGS:	1. CORRIDOR LIGHTING WILL BE ENABLED AND DISABLED BY A SWITCH LOCATED AT THE CONTROL DESK.
	2. SWITCH WILL CONTROL LIGHTING IN BEDROOM WING CORRIDORS ON AND OFF PER SCHEDULE OF DORM PERSONNEL.
I. EXTERIOR BUILDING LIGHTING:	1. ALL EXTERIOR BUILDING MOUNTED, PARKING AREA, WALKWAY LIGHTING WILL BE PROGRAMMED TO COME ON EITHER BY PHOTO CELL OR ASTRONOMICAL TIME SETTING.
	2. ALL LIGHTING WILL COME ON AT OR 1/2 HOUR BEFORE DUSK AND OFF AT OR 1/2 HOUR AFTER DAWN.
J. LIVING ROOM AND STUDY ROOMS:	1. UNOCCUPIED MODE: WHEN ROOM IS UNOCCUPIED, ALL LIGHTING IN ROOM WILL BE DISABLED AND DE-ENERGIZED BY VACANCY SENSOR(S) IN ROOM.
	2. OCCUPIED MODE: a. LIGHTING CONTROL IN ROOM WILL BE ENABLED BY PUSH BUTTON SWITCHES IN ROOM. NO LUMINAIRES WILL AUTOMATICALLY ENERGIZE.
K. LIVING ROOM AND STUDY ROOMS:	1. UNOCCUPIED MODE: WHEN ROOM IS UNOCCUPIED, ALL LIGHTING IN ROOM SHALL BE DISABLED AND DE-ENERGIZED BY VACANCY SENSOR(S) IN ROOM.
	2. OCCUPIED MODE: a. LIGHTING CONTROL IN ROOM WILL BE ENABLED BY PUSH BUTTON SWITCHES AT ENTRY TO ROOM. NO LUMINAIRES WILL AUTOMATICALLY ENERGIZE.
L. ROOM CONTROLLER SERIES LMRC RATED FOR PROGRAMMING CONTROL:	1. ROOM CONTROLLER SERVES LMRC RATED FOR PROGRAMMING CONTROL.
	2. DUAL TECHNOLOGY VACANCY SENSOR SERIES LMDC.
M. SINGLE OUTLET ON/OFF DIMMER/ VACANCY DIGITAL SWITCH SERIES LMSW:	1. SINGLE OUTLET ON/OFF DIMMER/ VACANCY DIGITAL SWITCH SERIES LMSW.
N. SINGLE OUTLET ON/OFF DIMMER/ VACANCY DIGITAL SWITCH SERIES LMSW:	1. SINGLE OUTLET ON/OFF DIMMER/ VACANCY DIGITAL SWITCH SERIES LMSW.

- LUMINAIRE SCHEDULE NOTES:
- MANUFACTURER'S CATALOG NUMBERS REPRESENT MANUFACTURER SERIES. SHOP DRAWING SUBMITTALS WILL INCLUDE ALL PART NUMBERS REPRESENTING ALL ITEMS OF THIS LUMINAIRE SCHEDULE. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO ORDER LUMINAIRES TO INCLUDE ALL PARTS INDICATED ON SCHEDULE FOR EACH LUMINAIRE. SUBMITTAL WILL CALL OUT EACH PART CLEARLY.
 - LUMINAIRE REQUIRES MOUNTING COORDINATION WITH ARCHITECT PRIOR TO COMMENCEMENT OF ANY WORK. THIS LUMINAIRE MAY REQUIRE A HIGHER OR LOWER MOUNTING FROM THAT PROVIDED ON THIS SCHEDULE OR NOTES ON PLAN DUE TO ARCHITECTURAL REQUIREMENTS OR CONSTRUCTION CONDITIONS.
 - ALL LUMINAIRES ON THIS LUMINAIRE SCHEDULE ARE APPROVED FOR BID ON THIS PROJECT. IF A LUMINAIRE IS SUBMITTED THAT IS NOT ON THIS SCHEDULE, IT WILL BE REJECTED.
 - SHOULD ANY LUMINAIRE BE NOT AVAILABLE AT TIME OF SUBMITTAL, CONTRACTOR WILL USE ONE OF THE OTHER LUMINAIRES INDICATED IN EACH TYPE FOR REPLACEMENT. NO OTHERS WILL BE ACCEPTED.

ELECTRICAL LUMINAIRE SCHEDULE

TYPE	DESCRIPTION	VOLTS	MOUNTING	LAMPS	BALLAST TYPE	EM. BAT. PK.	LENS	MANUFACTURER/MODEL	NOTES
A1F	1' x 4' ARCHITECTURAL LED HIGH ENERGY EFFICIENT LUMINAIRE. RECESSED, LOW PROFILE.	MULTI TAP (UNV.) (120V)	RECESSED GYP. BOARD	LED, 4000K, 40 MAX WATTS, 3900 MINIMUM DELIVERED LUMENS	LED DRIVER 0-10V DIMMING	NONE	WHITE ACRYLIC	DAY-BRITE #1-FXP-45L-840-4-DS-UNV-DIM-FMA14 LITHONIA #EPANL 1X4-4000LM-80CRI-40K-MIN10-ZT-MVOLT-DGA14 CREE #W-TR-B-FF14-40L-40K-WH METALUX #14FP4240C-DF-14W-U	1,3,4
A2	2' x 2' ARCHITECTURAL LED HIGH ENERGY EFFICIENT LUMINAIRE. RECESSED, LOW PROFILE.	MULTI TAP (UNV.) (120V)	RECESSED T-BAR	LED, 4000K, 34 MAX WATTS, 3400 MINIMUM DELIVERED LUMENS	LED DRIVER 0-10V DIMMING	NONE	WHITE ACRYLIC	DAY-BRITE #2-FXP-38L-840-2-DS-UNV-DIM LITHONIA #EPANL 2X2-3400LM-80CRI-40K-MIN10-ZT-MVOLT ELITE #22-FPL1-LED-3000L-DIM10-MVOLT-40K-85 METALUX #22FP3240C	1,3,4
B	4' GENERAL PURPOSE LED STRIP FIXTURE, DIE FORMED STEEL HOUSING, BAKED WHITE ENAMEL FINISH, WITH DIFFUSING LENS.	MULTI TAP (UNV.) (120V)	WALL MOUNTED AT 8'-0" AFF OR SURFACE MOUNTED TO CEILING OR BOTTOM OF FIXTURE IS AT 10'-0"	LED, 4000K, 57 MAX WATTS, 4700 MINIMUM DELIVERED LUMENS	LED DRIVER	NONE	FROSTED ACRYLIC	DAY-BRITE #FSS-4-55L-840-UNV-DIM LITHONIA #ZL1N-L48-5000LM-FST-MVOLT-40K 90CRI-WH COLUMBIA #LCL4-40-ML-EDU METALUX #ASNLN-LD5-47SL-LW-UNV-L840-CD1-U	1,2,3,4
BR	4' LINEAR ROUND ADJUSTABLE LED, ARCHITECTUAL HIGH EFFICIENCY COMPACT HOUSING	MULTI TAP (UNV.) (120V)	SURFACE WALL MOUNTED AS DIRECTED BY ARCHITECTURAL ELEVATIONS	LED, 4000K, 57 MAX WATTS, 4896 DELIVERED LUMENS	LED DRIVER 0-10V DIMMING	NONE	CLEAR ACRYLIC	PINNACLE #M-WHE-840VHO-4-WHXX-U-OLS-1 LUMENWERX #AXLWAD-AP0-LED-80-1200-40-4-UNV-D5-1-X-X-FINISH PRUDENTIAL # MW-LED40-HO-4-XXX-SC-UNV-XXX-DM01 AMETRIX # ASYX-X-L4-X-U-F-L40-1-UNV-X-X CORELITE #CTW-F-5050-50L-840-1-D-UNV-STD-XX-WM-4	1,3,4
BV	4' EXTREME ENVIRONMENT LED HIGH ENERGY EFFICIENT LOW PROFILE ENCLOSED LUMINAIRE. INDOOR /OUTDOOR VANDAL RESISTANT.	MULTI TAP (UNV.) (120V)	WALL MOUNTED AT 8'-6" AFF OR SURFACE MOUNTED TO CEILING OR BOTTOM OF FIXTURE IS AT 8'-2"	LED, 4000K, 39 MAX WATTS, 4300 MINIMUM DELIVERED LUMENS	LED DRIVER	NONE	POLYCARBONATE LENS	DAY-BRITE #DWPE-43L-840-4-UNV LITHONIA #FEM-L48-4000LM-IMAFI-MD-MVOLT-GZ10-35K-80CRI COLUMBIA #LEM4-40LW-RFP-EDU METALUX #4VT2-LD4-4-DR-UNV-L840-CD1-WL-U	1,2,3,4
C6	6" ROUND ARCHITECTURAL LED DOWN LIGHT. WET LOCATION RATED. HIGH ENERGY EFFICIENT.	MULTI TAP (UNV.) (120V)	RECESSED CEILING	LED, 4000K, 20 MAX WATTS, 1400 MINIMUM DELIVERED LUMENS	LED DRIVER 0-10V DIMMING	NONE	FROSTED GLASS LENS	LIGHTOLIER #6RN/P6R-DL-15-840-CD-Z10-U LDN6 35/15 L06AR LSS MVOLT GZ10 WL LITHONIA #LDN6 40/15 L06AR LSS MVOLT GZ10 WL PRESCOLITE #LF6SL-DM1-6LFSL-15L-40K8-SS-B24 HALO #HC6-15-D010-HM6-12-840-61WDH	1,3,4
C6E	6" ROUND ARCHITECTURAL LED DOWN LIGHT. WET LOCATION RATED. HIGH ENERGY EFFICIENT.	MULTI TAP (UNV.) (120V)	RECESSED CEILING	LED, 4000K, 20 MAX WATTS, 1400 MINIMUM DELIVERED LUMENS	LED DRIVER 0-10V DIMMING	INTEGRAL UL924 NICAD BATTERY	FROSTED GLASS LENS	LIGHTOLIER #6RNE/M6R-DL-15-840-CD-Z10-U LDN6 35/15 L06AR LSS MVOLT GZ10 WL PEACHTREE #6BLRD 18 40K-90-SH-RPG-DMLV1-WL-EM1-L-277 PRESCOLITE #LF6SL-DM1-EMR-6LFSL-15L-40K8-SS-B24 HALO #HC6-15-D010-IEH7-HM6-12-840-61VDH	1,3,4
D1S	WALL MOUNTED 4' LONG X 8.25" X 1.75", SQUARE HOUSING, INDIRECT 70° DIRECT 30, LED LUMINAIRE WITH METAL REFLECTOR, AND COLD-ROLLED STEEL HOUSING. COORDINATE FINISH COLOR WITH ARCHITECT AT SUBMITTAL REVIEW. FLAT ENDS.	MULTI TAP (UNV.) (120V)	WALL MOUNTED AT 7'-0" AFF	LED, 4000K, 61 MAX WATTS, 2200 DELIVERED LUMENS	LED DRIVER 0-10V DIMMING	NONE	SOFTSHINE LENS	CORELITE #DWI-WA-2-L40-1-D-UNV-SU-WA-4-STD-XX SOLERA #CURVE-48-30LED-3875-4000K-UNV-WM-MV-U/D-DM-XX VISA #CV1704-L40K-H MVOLT-L-CBA TECH LTC. #700B-CPAN-4-X-LED830-277-MOD4000K	1,3,4
E1	LED EXIT SIGN, EMERGENCY, DIE CAST ALUMINUM HOUSING WITH GREEN CHARACTERS, BLACK HOUSING AND BRUSHED ALUMINUM FACE (SINGLE FACE AND DIRECTIONAL ARROWS AS INDICATED ON LIGHTING PLANS). MEETS UL LISTINGS FOR THIS TYPE OF LUMINAIRE. WITH SELF-CONTAINED, NICKEL-CADMIUM EMERGENCY BATTERY PACK.	MULTI TAP (UNV.) (120V)	SURFACE CEILING OR WALL AT 8'-6" AFF UNLESS OTHERWISE NOTED ON LIGHTING PLANS.	GREEN LED, 3 MAX WATTS	LED DRIVER	NICKEL CADMIUM PER MFG.	BRUSHED ALUMINUM FACE	EVENLITE #CCDS-EM-G-1-AB LITHONIA #LE-S-1-G-ELN DUALLITE #SE-S-G-BNE SURE-LITES #CX7-1-G	1,2
E2	LED EXIT SIGN, EMERGENCY, DIE CAST ALUMINUM HOUSING WITH GREEN CHARACTERS, BLACK HOUSING AND BRUSHED ALUMINUM FACE (DOUBLE FACE AND DIRECTIONAL ARROWS AS INDICATED ON LIGHTING PLANS). MEETS UL LISTINGS FOR THIS TYPE OF LUMINAIRE. WITH SELF-CONTAINED, NICKEL-CADMIUM EMERGENCY BATTERY PACK.	MULTI TAP (UNV.) (120V)	SURFACE CEILING OR WALL AT 8'-6" AFF UNLESS OTHERWISE NOTED ON LIGHTING PLANS.	GREEN LED, 3 MAX WATTS	LED DRIVER	NICKEL CADMIUM PER MFG.	BRUSHED ALUMINUM FACE	EVENLITE #CCDS-EM-G-1-AB LITHONIA #LE-S-1-G-ELN DUALLITE #SE-S-G-BNE SURE-LITES #CX7-1-G	1,2,3,4
EM	CONTEMPORARY, LOW PROFILE EMERGENCY BATTERY PACK FIXTURE WITH AN INJECTED MOLDED, HIGH IMPACT, UV STABILIZED THERMOPLASTIC HOUSING, 6 V LEAD CALCIUM BATTERY. ADA COMPLIANT, ADJUSTABLE LAMP SOCKETS, SHORT CIRCUIT AND BROWNOUT PROTECTION.	MULTI TAP (UNV.) (120V)	SURFACE 8'-6" AFF UNLESS OTHERWISE NOTED ON LIGHTING PLANS.	(2) TWO LED, 4 MAX WATTS	LED DRIVER	NICKEL CADMIUM PER MFG.	ACRYLIC FRESNAL	SURELITE #LEM2 LITHONIA #ELM2-LED EVENLITE #TCL-2-W DUALLITE #EV-2	1,2,3,4
F	SLIM, LOW PROFILE, FULLY GASKETED DIE CAST ENCLOSURE, IP65 WET LOCATION RATED, HIGH IMPACT UV RESISTANT POLYCARBONATE LENS, FULL CUT OFF. INTEGRAL PHOTOCELL AND BATTERY BACKUP. COORDINATE FINISH COLOR WITH ARCHITECT AT SUBMITTAL OF LUMINAIRES.	MULTI TAP (UNV.) (120V)	EXTERIOR WALL SURFACE MOUNT AT 9'-0" AFF.	LED, 4000K, 30 MAX WATTS, 2900 MINIMUM DELIVERED LUMENS	LED DRIVER	NONE	IMPACT RESISTANT UV RESISTANT POLYCARBONATE	ECLIPSE LIGHTING #DK-E-M-30W-4K-EBU-XX LITHONIA #WDGE2 LED-P3-40K-90CRI-VF-MVOLT-SRM-XXX TRACELITE #WLZ2-4-4K-XX LUMARK #AXCS2A	1,2,3,4
FE	SLIM, LOW PROFILE, FULLY GASKETED DIE CAST ENCLOSURE, IP65 WET LOCATION RATED, HIGH IMPACT UV RESISTANT POLYCARBONATE LENS, FULL CUT OFF. INTEGRAL PHOTOCELL AND BATTERY BACKUP. COORDINATE FINISH COLOR WITH ARCHITECT AT SUBMITTAL OF LUMINAIRES.	MULTI TAP (UNV.) (120V)	EXTERIOR WALL SURFACE MOUNT AT 9'-0" AFF.	LED, 4000K, 30 MAX WATTS, 2900 MINIMUM DELIVERED LUMENS	LED DRIVER	INTEGRAL UL924 NICAD BATTERY	IMPACT RESISTANT UV RESISTANT POLYCARBONATE	ECLIPSE LIGHTING #DK-E-M-30W-4K-EBU-XX LITHONIA #WDGE2 LED-P3-40K-90CRI-MVOLT-SRM-E10WH-XXX TRACELITE #WLZ2-4-4K-XX LUMARK #AXCS2A-CBP	1,2,3,4
G1	SIGN LIGHTING. HEAVY-DUTY ALUMINUM HOUSING. LED WIDE DISTRIBUTION. COORDINATE FINISH COLOR WITH ARCHITECT AT SUBMITTAL OF LUMINAIRES.	MULTI TAP (UNV.) (120V)	SIDE MOUNTED TO SHADE STRUCTURE.	LED, 4000K, 15 MAX WATTS, 860 MINIMUM DELIVERED LUMENS	LED DRIVER	NONE	CLEAR TEMPERED GLASS LENS	HADCO #BP-D-C-H HYDREL #ASPEN P2-90-40K-120-50DEG-FLC INSIGHT #5SP-15W-40K-100-SMS-UNV-XX LUMARK #TCRS-8-W	1,2,3,4
N3S1	EXTRUDED ALUMINUM 3.5" WIDE X 4'-0" LENGTH SURFACE MOUNTED LINEAR STATIC WHITE LED LUMINAIRE. WET RATED. EXTRA DIFFUSE LENS. MUST MEET B.U.G. RATING B4 U2 G2 OR BETTER. COORDINATE FINISH COLOR WITH ARCHITECT AT SUBMITTAL OF LUMINAIRES.	MULTI TAP (UNV.) (120V)	SIDE SURFACE MOUNTED SO THAT BOTTOM OF LUMINAIRE IS FLUSH WITH BOTTOM OF BEAM.	LED, 4000K, 40 MAX WATTS, 3200 MINIMUM DELIVERED LUMENS	LED DRIVER	NONE	FROSTED HIGH-IMPACT ACRYLIC (EXTRA DIFFUSE)	PINNACLE #EX3-WET-N-835HO-4-IND-WAS-U-DD-1-XX MARK #S4LWD-LLP-4FT-MSL4 90CRI-40K-800LMF-MINI-MVOLT-XXX-ZT LUMENWERX #VIAWETW-PYC-HLO-LED-90-800LM/FT-40-UNV-D1-1-EMB	1,3,4
P6	6" PENDANT MOUNTED LED SQUARE HOUSING WITH DIFFUSE CLEAR REFLECTOR.	MULTI TAP (UNV.) (120V)	PENDANT STEM MTD. SEE LIGHTING PLANS FOR MOUNTING HEIGHTS.	LED, 4000K, 30 MAX WATTS, 1800 MINIMUM DELIVERED LUMENS	LED DRIVER 0-10V DIMMING TO 1%	NONE	IMPACT RESISTANT TEMPERED GLASS	HALO #PRS6-15-D010-SM6-12-8FS-WD-WF SPECTRUM #SGE6S QLED-FX-15L-35K-DH-82T-CA0366FX-MW-SOW LITON #LHJLD06-15C035-UE-D10P1-B60-T35-C260-LRAQ621W LITHONIA #LDN6SQ-35/15-L56-WR-LSS-MVOLT-EZ1-WL	1,2,3,4
S4	SINGLE MOUNT ARCHITECTURAL AREA LIGHT. TYPE IV OPTICS. 16" SQUARE POLE. COORDINATE FINISH COLOR WITH ARCHITECT AT SUBMITTAL OF LUMINAIRES. (PROVIDE IN POLE A RECEPTACLE FOR CAMERA POWER. REFER TO "T" SHEET SITE PLAN FOR ACTUAL CAMERA LOCATIONS.)	277 V	16'-0" SQUARE POLE	LED, 4000K, 136 MAX WATTS, 11,000 MINIMUM DELIVERED LUMENS	LED DRIVER	NONE	CLEAR ACRYLIC	GARDCO #ECF-S-32L-1A-NW-4-UNV /HAPCO #SSS16B4 LITHONIA #RSX1 LED-P3-40K-R4-MVOLT-SPA-XXX-XXX SSS-16'-4C-DM19AS-XXX HUBBELL #ASL-A-16L-4K-210-4-U LIRON #LEDEPK-100W-40K-4-MSF	1,3,4

ELECTRICAL CONNECTIONS FOR MECHANICAL EQUIPMENT SCHEDULE NOTES:

- STARTER, CONTROL SYSTEM AND DISCONNECTING MEANS FOR UNIT WILL BE PROVIDED BY DIVISION 23. CONTRACTOR WILL HAVE ONE POINT OF ELECTRICAL CONNECTION. FOR VFD OR CONTROL EQUIPMENT INFORMATION, REFER TO SHEET SERIES M-700.
- RACEWAY SYSTEM AND CONDUCTORS FOR CONTROLS WILL BE PROVIDED BY DIVISION 26 UNLESS SPECIFICALLY CALLED OUT TO BE PROVIDED BY OTHER SECTIONS OF THESE DOCUMENTS. REFER TO SHEET SERIES "M" FOR CONTROL DIAGRAMS AND ALSO REFER TO SPECIFICATION SECTION 230549.
- SIZE FUSES PER MANUFACTURER'S RECOMMENDATIONS OR A MINIMUM OF 125% OF UNIT FLA.
- STARTER, CONTROL SYSTEM FOR UNIT WILL BE PROVIDED BY DIVISION 23. CONTRACTOR WILL PROVIDE DISCONNECTING MEANS AND HAVE ONE POINT OF ELECTRICAL CONNECTION. FOR CONTROL EQUIPMENT INFORMATION, REFER TO SHEET SERIES M-700.
- CONTRACTOR WILL HAVE DIV 28 PROVIDE CUT DETECTORS FOR UNITS SUPPLY AND RETURN SECTIONS AS REQUIRED, INSTALLED BY DIVISION 23. WIRED AND CONNECTED BY DIVISION 26/28. CONTROL WIRING BY DIVISION 23.

ELECTRICAL CONNECTIONS FOR MECHANICAL EQUIPMENT SCHEDULE

EQUIPMENT NUMBER	EQUIPMENT DESCRIPTION	VOLTAGE	PHASE	BRANCH CIRCUIT CONDUCTOR DESCRIPTION	CONDUIT SIZE	MOTOR STARTER CHARACTERISTICS										DISCONNECT SWITCH CHARACTERISTICS					KEY NOTE
						STARTER TYPE	STARTER SIZE	OFF/AUTO OR HOA	PILOT LIGHT	EXTRA CONTACTS			VOLTS	FRAME AMPS	FUSE SIZE	SOLID NEUT. / GND LUG	NEMA RATING				
ACU-1	CONDENSING UNIT	480 V	3	3#8 & 1#10 GND	1	FVNR	1	HOA	X	X	2	2	2	800 V	100	C	YES	3R	B		
CU-1/FC-1	SPLIT SYSTEM	208 V	1	3#10 & 1#10 GND	3/4"	FVNR	1	HOA	X	X	2	2	2	250 V	30	C	YES	3R/1	B		
CU-2/FC-2	SPLIT SYSTEM	208 V	1	3#10 & 1#10 GND	3/4"	FVNR	1	HOA	X	X	2	2	2	250 V	30	C	YES	3R/1	B		
EUH-1	ELECTRIC UNIT HEATER	208 V	1	3#8 & 1#10 GND	1									250 V	60	C	YES	1	B.D		
EUH-2	ELECTRIC UNIT HEATER	208 V	1	3#8 & 1#10 GND	1									250 V	60	C	YES	1	B.D		
P-3 VFD-1	PUMP	480 V	3	4#12 & 1#12 GND	3/4"																
P-4 VFD-2	PUMP	480 V	3	4#12 & 1#12 GND	3/4"																
VFD-3-AHU-1 SA	AIR HANDLING UNIT EXHAUST FAN	480 V	3	4#12 & 1#12 GND	3/4"														A.B.E		
VFD-4-AHU-1 SA	AIR HANDLING UNIT EXHAUST FAN	480 V	3	4#12 & 1#12 GND	3/4"														A.B.E		
VFD-5-AHU-1 EF	AIR HANDLING UNIT EXHAUST FAN	480 V	3	4#12 & 1#12 GND	3/4"														A.B.E		
VFD-6-AHU-1 EF	AIR HANDLING UNIT EXHAUST FAN	480 V	3	4#12 & 1#12 GND	3/4"														A.B.E		


BATTERY INVERTER SCHEDULE NOTES:

- MANUFACTURER'S CATALOG NUMBERS REPRESENT MANUFACTURER SERIES. SHOP DRAWING SUBMITTALS WILL INCLUDE ALL PART NUMBERS REPRESENTING ALL ITEMS OF THIS SCHEDULE. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO ORDER BATTERY INVERTERS TO INCLUDE ALL PARTS INDICATED ON SCHEDULE FOR EACH BATTERY INVERTER. SUBMITTAL WILL CALL OUT EACH PART CLEARLY.
- ALL BATTERY INVERTERS ON THIS SCHEDULE ARE APPROVED FOR BID ON THIS PROJECT. IF A BATTERY INVERTER IS SUBMITTED THAT IS NOT ON THIS SCHEDULE, IT WILL BE REJECTED.

BATTERY INVERTER SCHEDULE

INVERTER NAME	DESCRIPTION	VOLTAGE	MANUFACTURER MODEL	NOTES
BIA	250VA BATTERY INVERTER	120V	EVENLITE #PW-25-LC-V2-XX MYERS #L-V2-R-1 DUAL LITE #LG-250-S ISOLITE #IMI-250-LC-V2-MB-XX	1,2

CONSULTANT



Dzilh-Na-O-Dith-Hle - New Dormitory Building

CONSTRUCTION DOCUMENTS

35 Road 7585, Bloomfield, NM 87413

DECEMBER 4, 2020

MARK	DATE	DESCRIPTION
1	11/17/20	Addendum Changes

ISSUE:

DATE:	
PROJECT NO:	751
CAD DWG FILE:	
DRAWN BY:	AMH
CHECKED BY:	JMM

SHEET TITLE

ELECTRICAL SCHEDULES

1	2	3	4	5	6						
<div><div>Branch Panel: MPA</div><div><div>Location: PENTHOUSE</div><div>Supply From: DDPH1</div><div>Mounting: Surface</div><div>Enclosure: Type 1</div></div><div><div>Volts: 480/277 Wye</div><div>Phases: 3</div><div>Wires: 4</div><div>Spaces: 42</div></div><div><div>MINIMUM A.I.C. Rating: 10,000</div><div>Mains Type: MCB</div><div>Mains Rating: 225 A</div></div></div>											
Notes:											
CKT	Circuit Description	Trip	Poles	A	B	C	Poles	Trip	Circuit Description	CKT	
1	EQP VFD-5-AHU-1 EF	20 A	3	2107 VA	2107 VA			3	20 A	EQP VFD-6-AHU-1 EF	2
3	--	--	--		2107 VA	2107 VA		--	--		4
5	--	--	--			2107 VA	2107 VA	--	--		6
7	EQP VFD-3-AHU-1 SA	20 A	3	3050 VA	3050 VA			3	20 A	EQP VFD-3-AHU-1 SA	8
9	--	--	--		3050 VA	3050 VA		--	--		10
11	--	--	--			3050 VA	3050 VA	--	--		12
13	EQP ACU-1	70 A	3	11529 VA	831 VA			3	20 A	EQP P-3/ VFD-1	14
15	--	--	--		11529 VA	831 VA		--	--		16
17	--	--	--			11529 VA	831 VA	--	--		18
19	EQP P-4/ VFD-2	20 A	3	831 VA	0 VA			3	20 A	SPARE	20
21	--	--	--		831 VA	0 VA		--	--		22
23	--	--	--			831 VA	0 VA	--	--		24
25	SPARE	20 A	3	0 VA	0 VA			3	20 A	SPARE	26
27	--	--	--		0 VA	0 VA		--	--		28
29	--	--	--			0 VA	0 VA	--	--		30
31	SPACE ONLY	--	--	0 VA	408 VA			1	20 A	SITE LIGHTING	32
33	SPACE ONLY	--	--		0 VA	0 VA		--	--	SPACE ONLY	34
35	SPACE ONLY	--	--			0 VA	0 VA	--	--	SPACE ONLY	36
37	SPACE ONLY	--	--	0 VA	0 VA			--	--	SPACE ONLY	38
39	SPACE ONLY	--	--		0 VA	0 VA		--	--	SPACE ONLY	40
41	SPACE ONLY	--	--			0 VA	0 VA	--	--	SPACE ONLY	42
Total Load:		23912 VA		23504 VA		23504 VA					
Total Amps:		86 A		85 A		85 A					
Legend:		Connected Load		Demand Factor		Estimated Demand		Panel Totals			
Load Classification		70512 VA		100.00%		70512 VA		Total Conn. Load: 70920 VA			
MTR		408 VA		125.00%		510 VA		Total Est. Demand: 71022 VA			
								Total Conn. Current: 85 A			
								Total Est. Demand Current: 85 A			



1. PROVIDE A VIDEO DOOR PHONE AT MAIN ENTRY DOOR. PROVIDE A DESKTOP RECEIVER WITH CHARGE BATTERY. PROVIDE APPROXIMATE 4"X10" SURFACE MOUNT VACANT RESISTANT VIDEO DOORBELL AND APPROXIMATE 10"X10" SURFACE MOUNT. APPROXIMATE DOOR RELEASE IS TO UNLOCK EXTERIOR DOOR TO UNLOCK.
2. PROVIDE AND INSTALL NEW MOMENTARY PUSHBUTTON FOR DOOR RELEASE FROM CORRIDOR 101 TO CORRIDOR 106. BOTH DOORS FROM 101 TO 102 ARE TO UNLOCK.
3. PROVIDE AND INSTALL NEW MOMENTARY PUSHBUTTON FOR DOOR RELEASE FROM RECEPTION 111 INTO HALL 357.
4. PROVIDE PUSH BUTTON ACCESS CONTROL LOCKDOWN BUTTON WITH CHARGE BATTERY RELEASE UPON RECEIVING ACCESS CONTROL DOORS ARE TO ENTER LOCKDOWN MODE AND DIGITAL CLOCKS TO READ LOCKDOWN ACTION.
5. ELECTRICAL CONTRACTOR TO PROVIDE 2"RGC CONDUIT UNDERGROUND TO RECEPTION DESK.
6. PROVIDE AND INSTALL NEW FLUSH MOUNT DIGITAL SPEAKER/COMBINATION UNIT.
7. INSTALL OPTICAL NETWORK TERMINAL ON CEILING. PROVIDE PLEATED FAN FILTER. SEE NETWORK DIAGRAM DETAIL.
8. ELECTRICAL CONTRACTOR TO PROVIDE 1"MT SEALS AS SHOWN



NOC

NETWORK CABLING, INC.

3100 LA PLATA HWY. FARMINGTON NM 87401
 505.598.5054 - WWW.NETWORKCABLINGINC.COM



T-101