



NAVAJO NATION

DILKON PASS


PIPELINE AND PUMP STATION PROJECT

MARCH 2022

CONSTRUCTION ISSUE



SALT LAKE CITY, UT



CONSTRUCTION
ISSUE



DILKON PASS
PIPELINE AND
PUMP STATION

REVISIONS

REV	DATE	DESCRIPTION

LINE IS 2 INCHES
AT FULL SIZE

DESIGNED: WILLMORE
DRAWN: T. PRIDEMORE
CHECKED: C. WILLMORE
CHECKED: ---
APPROVED: S. BRANCHLEY
FILENAME: G-000.dwg
BC PROJECT NUMBER: 157520
CLIENT PROJECT NUMBER: ---


GENERAL

COVER SHEET

DRAWING NUMBER

G-000

SHEET NUMBER
OF 59



LOCATION MAP
PLAN
NOT TO SCALE



Call at least two full working days
before you begin excavation.

ARIZONA 811
Arizona Blue Stake, Inc.

Dial 8-1-1 or 1-800-STAKE-IT (782-5348)
In Maricopa County: (602) 263-1100


Path: C:\BCP\W\02344900 FILENAME: G-001.DWG PLOT DATE: 3/4/2022 4:16 PM CAD USER: TYLER PRIDEMORE

DRAWING INDEX

GENERAL			ELECTRICAL			NHS STANDARD DETAILS FOR WATER		
SHEET NO.	DWG NO.	DWG TITLE	SHEET NO.	DWG NO.	DWG TITLE	DWG NO.	DWG TITLE	
1	G-000	COVER SHEET	46	E-001	SYMBOLS, ABBREVIATIONS AND NOTES	WS-1	1" WATER SERVICE	
2	G-001	DRAWING INDEX	47	E-002	CONTROL AND ONE-LINE DIAGRAM LEGENDS AND SYMBOLS	WS-1A	MATERIAL LIST: 1" SERVICE	
3	G-002	STANDARD SYMBOLS	48	E-003	STANDARD DETAILS - 1	WS-1B	MATERIAL LIST: 1" SERVICE	
4	G-003	STANDARD ABBREVIATIONS	49	E-004	STANDARD DETAILS - 2	WS-1C	GENERAL NOTES FOR WATER SERVICE	
5	G-004	VICINTY MAP	50	E-005	STANDARD DETAILS - 3	WS-3B	4" x 2" P.R.V.	
			51	E-100	DILKON PASS PUMP STATION SITE PLAN	WS-4C	MATERIAL LIST: 4"X2" P.R.V.	
			52	E-101	DILKON PASS PUMP STATION PLAN	WS-10	AIR RELEASE VALVE DETAIL	
SURVEY			53	E-102	DILKON PASS PUMP STATION ONE-LINE DIAGRAM	WS-11	2" FLUSH VALVE DETAIL	
SHEET NO.	DWG NO.	DWG TITLE	54	E-110	DILKON PASS TANK SITE PLAN	WS-13	MARKER POST DETAIL	
6	V-001	RESULTS OF SURVEY	INSTRUMENTATION			WS-14	WATER MAIN VALVE INSTALLATION	
7	V-002	RESULTS OF SURVEY	SHEET NO.	DWG NO.	DWG TITLE	WS-19	GRAVITY/THRUST BLOCK DETAILS	
8	V-003	RESULTS OF SURVEY				WS-19A	GRAVITY/THRUST BLOCK CHART	
9	V-004	RESULTS OF SURVEY	55	I-001	DILKON PASS COMMUNICATIONS BLOCK DIAGRAM	IHS STANDARD DETAILS		
DEMOLITION			HVAC			DWG NO.	DWG TITLE	
SHEET NO.	DWG NO.	DWG TITLE	SHEET NO.	DWG NO.	DWG TITLE	W-33	HDPE WASH CROSSING DETAIL	
10	CD-100	PUMP STATION DEMOLITION SITE PLAN	56	H-001	HVAC LEGEND AND GENERAL NOTES	W-34	FENCE DETAIL FOR STORAGE TANK AND PUMPHOUSE	
CIVIL			57	H-101	DILKON PASS PUMP STATION HVAC PLAN AND SECTION	W-39	SILT FENCE	
SHEET NO.	DWG NO.	DWG TITLE	58	H-102	HVAC DETAILS	W-40	STRAW BALES	
11	C-001	GENERAL CIVIL NOTES AND SYMBOLS	59	H-501	HVAC SCHEDULES	NTUA TECHNICAL PROVISIONS		
12	C-002	MISCELLANEOUS DETAILS - 1				DWG NO.	DWG TITLE	
13	C-003	MISCELLANEOUS DETAILS - 2				1 OF 6	AC TANK PANEL COVER SHEET	
14	C-100	DILKON PASS PUMP STATION GRADING PLAN				2 OF 6	AC TANK CONTROL PANEL DISCRETE IO	
15	C-101	DILKON PASS PUMP STATION YARD PIPING PLAN				3 OF 6	AC TANK CONTROL PANEL ANALOG IO	
16	C-110	CHECK VALVE SITE PLAN				4 OF 6	AC TANK CONTROL PANEL POWER DISTRIBUTION	
17	C-200	KEY MAP				5 OF 6	AC TANK CONTROL PANEL BACKPLANE	
18	C-201	PLAN AND PROFILE STA 10+00 TO 18+00				6 OF 6	AC TANK CONTROL PANEL CABLE PINOUT	
19	C-202	PLAN AND PROFILE STA 18+00 TO 26+00				1 OF 6	PLC CONTROL PANEL COVER SHEET	
20	C-203	PLAN AND PROFILE STA 26+00 TO 34+00				2 OF 6	PLC CONTROL PANEL DISCRETE I/O (BOOSTER WITH BOOSTERPAQ)	
21	C-204	PLAN AND PROFILE STA 34+00 TO 42+00				3 OF 6	PLC CONTROL PANEL ANALOG I/O (BOOSTER WITH BOOSTERPAQ)	
22	C-205	PLAN AND PROFILE STA 42+00 TO 49+45				4 OF 6	PLC CONTROL PANEL POWER DISTRIBUTION	
23	C-206	PLAN AND PROFILE STA 49+50 TO 57+50				5 OF 6	PLC CONTROL PANEL BACKPLANE	
24	C-207	PLAN AND PROFILE STA 57+50 TO 65+50				5A OF 6	PLC CONTROL PANEL WITH SWING OUT PANEL BACKPLANE	
25	C-208	PLAN AND PROFILE STA 65+50 TO 73+50				6 OF 6	PLC CONTROL PANEL CABLE PINOUT	
26	C-209	PLAN AND PROFILE STA 73+50 TO 81+50						
27	C-210	PLAN AND PROFILE STA 81+50 TO 86+79						
28	C-211	PLAN AND PROFILE COYOTE WASH						
MECHANICAL								
SHEET NO.	DWG NO.	DWG TITLE						
29	M-001	STANDARD DETAILS						
30	M-100	DILKON PASS PUMP STATION BUILDING PLAN						
31	M-101	DILKON PASS PUMP STATION BUILDING SECTION						
STRUCTURAL								
SHEET NO.	DWG NO.	DWG TITLE						
32	S-001	GENERAL STRUCTURAL NOTES						
33	S-002	SPECIAL INSPECTIONS - 1						
32	S-003	SPECIAL INSPECTIONS - 2						
35	S-004	STANDARD DETAILS - 1						
36	S-005	STANDARD DETAILS - 2						
37	S-006	STANDARD DETAILS - 3						
38	S-100	DILKON PASS PUMP STATION BUILDING FOUNDATION PLAN						
39	S-101	DILKON PASS PUMP STATION BUILDING ROOF FRAMING PLAN						
40	S-102	DILKON PASS PUMP STATION BUILDING SECTION AND DETAILS						
ARCHITECTURAL								
SHEET NO.	DWG NO.	DWG TITLE						
41	A-101	DILKON PASS PUMP STATION CODE & FLOOR PLAN						
42	A-102	DILKON PASS PUMP STATION ROOF PLAN						
43	A-201	DILKON PASS PUMP STATION BUILDING ELEVATION						
44	A-202	DILKON PASS PUMP STATION BUILDING SECTIONS						
45	A-301	DILKON PASS PUMP STATION DOOR SCHEDULE AND DETAILS						



SALT LAKE CITY, UT



CONSTRUCTION ISSUE



DILKON PASS PIPELINE AND PUMP STATION

REVISIONS

REV	DATE	DESCRIPTION

LINE IS 2 INCHES AT FULL SIZE

DESIGNED: WILLMORE
DRAWN: T. PRIDEMORE
CHECKED: C. WILLMORE
CHECKED: - -
APPROVED: S. BRENCHELEY
FILENAME G-001.dwg
BC PROJECT NUMBER 157520
CLIENT PROJECT NUMBER

GENERAL

DRAWING INDEX

DRAWING NUMBER

G-001

SHEET NUMBER OF 59

2

Path: C:\USERS\TPRIDEMORE\ONE\DRIVE - BROWN AND CALDWELL\DOCUMENTS\WORK\TEMP. CAD\NAVAJO NATION\DILKON PASS\EXPORT FILENAME: G-003.DWG PLOT DATE: 2/23/2022 4:55 PM CAD USER: TYLER PRIDEMORE

A AMPERE
AC ASPHALTIC CONCRETE
A/C AIR CONDITIONING
ACC AREA CONTROL CENTER
ACP ASBESTOS CEMENT PIPE
ACST ACOUSTIC
ACU AIR CONDITIONING UNIT
AF AIR FILTER
AHU AIR HANDLING UNIT
AMD AIR MONITORING DEVICE
ANC ANCHOR
AR AIR RETURN
ARV AIR RELEASE VALVE
AS AIR SUPPLY
ATP VERTICAL TURBINE PUMP AIR RELEASE VALVE
ATS AUTOMATIC TRANSFER SWITCH
AV ANGLE VALVE

BAC BACTERIOLOGICAL
BAV BALL VALVE
BC BEGINNING OF CURVE
BCR BEGINNING OF CURVE RETURN
BCOP BARE COPPER
BFP BACK FLOW PREVENTER
BFV BUTTERFLY VALVE
BGAT BOOLEAN GATE
BF BLIND FLANGE
BHP BRAKE HORSEPOWER
BSN BAR SCREEN
BUV BUTTERFLY VALVE

CAB DIRECT BURIAL CABLE
CAF COMBUSTION AIR FAN
CAV COMBO AIR VALVE
CC COOLING COIL
C-C CENTER TO CENTER
CCP CONCRETE CYLINDER PIPE
CCSP CONCRETE LINED AND COATED STEEL PIPE
CD CEILING DIFFUSER
CDR CONDUCTOR
CDU CONDENSING UNIT
CED CEILING EXHAUST DIFFUSER
CER CEILING EXHAUST REGISTER
CF CUBIC FEET
CFH CUBIC FEET PER HOUR
CFR CODE OF FEDERAL REGULATIONS
CHR CHILLER
CIRC CIRCUMFERENCE
CK CHECKER(ED)
CKPL CHECKER PLATE
C CENTERLINE
CL CLEARANCE
CL2 CHLORINE
CM MANUAL CONTROL STATION
CMA MANUAL-AUTO CONTROL STATION
CMC CEMENT MORTAR COATED
CML CEMENT MORTAR LINED
CMPA ASBESTOS PROTECTED CORRUGATED METAL PIPE
CNTL CONTROL
CO2 CARBON DIOXIDE
COD CHEMICAL OXYGEN DEMAND
COF COOLING AIR FAN
COM COMMUNITOR
CON CONVEYOR
COND CONDUCTIVITY
CONN CONNECTION
CJ CONSTRUCTION JOINT
CONT CONTINUED
CP COMPRESSOR
CPVC CHLORINATED POLYVINYL CHLORIDE
CR CONDUIT RACK
CRF CHEMICAL FEEDER
CRN CRANE
CREJ CORRUGATED RUBBER EXPANSION JOINT
CSD CEILING SUPPLY DIFFUSER
CTF CENTRIFUGE
CTR CONTRACTOR, CONTROL UNIT
CV CONTROL VALVE

DB DUCT BANK
DE DENSITY METER
DF DRINKING FOUNTAIN
DFD DUCT FIRE DAMPER
DG DOOR GRILLE
DI DUCTILE IRON
DM DAMPER MOTOR
DR DRAIN ROCK
DT DRAIN TRAP
DU DRIVE UNIT
DWF DRY WEATHER FLOW

EA EXHAUST AIR / ENVIRONMENTAL ASSESSMENT
EAT ENTERING AIR TEMPERATURE
EAU ENGINE ALTERNATOR UNIT
EC END OF CURVE
ECU EVAPORATIVE COOLING UNIT
ED EXTRACTOR DAMPER, EQUIPMENT DRAIN
EE EACH END
EF EXHAUST FAN
EFF EFFLUENT

EG EXHAUST GRILLE
EJ EXPANSION JOINT
EL ELEVATION
ELL ELBOW
EMBD EMBEDDED
ENCL ENCLOSURE
E/P ELECTRIC/PNEUMATIC
EPR EVAPORATOR
EQ EQUAL
EQUIP EQUIPMENT
ES EXISTING SURFACE
EWEF EACH WAY EACH FACE
EWT ENTERING WATER TEMPERATURE
EXG EXHAUST GRILLE
EXIST EXISTING

F FAHRENHEIT, FACE, FUSE(D), FAN
FAI FRESH AIR INTAKE
FB FLAT BAR, FLOOR BEAM
FC FAIL CLOSED
FCL FREE CHLORINE
FCR FINE CRUSHED ROCK
FE FLOWMETER
FF FAR FACE / FINISHED FLOOR
F-F FACE TO FACE
FH FIRE HYDRANT, FLATHEAD
FIN FINISHED
FIT FLOW INDICATING TRANSMITTER
FL FLOW LINE
FLC FLOCCULATOR
FLP FLUID POWER UNIT
FLR FLOOR
FLT FILTER
FM FORCE MAIN , FLOW METER
FMH FLEXIBLE METAL HOSE
FMX FLASH MIXER
FO FAIL OPEN
FP FILTER PRESS
FPC FLEXIBLE PIPE COUPLING
FPC-T FPC TO TAKE TENSION
FRS FREEZESTAT
FS FLOW SWITCH, FIRESTAT
FT FLASH TANK

G POWER ACTUATED GATE
GAC GRANULATING ACTIVATED CARBON
GB GRADE BREAK
GBV GLOBE VALVE
GDR GRINDER
GEN GENERATOR
GFI GROUND FAULT INTERRUPTOR
GPD GALLONS PER DAY
GRDR GRINDER
GRT GROUT
GSP GALVANIZED STEEL PIPE
GT GATE
GV GATE VALVE

H/A HAND AUTO
HC HEATING COIL
HEX HEAT EXCHANGER
HDOT HEAVY DUTY OILTIGHT
HG MERCURY, HAND GRADE
HHV HEAT HOSE VALVE
HOA HAND-OFF-AUTO
HOR HORIZONTAL
HP HIGH PRESSURE, HIGH POINT, HORSEPOWER
HR HANDRAIL, HEAT RESERVOIR
HSS HIGH SIGNAL SELECT
HTV HIGH TEMPERATURE VENT
HV HOSE VALVE
H/V HEATING AND VENTILATING
HVAC HEATING, VENTILATING AND AIR CONDITIONING
HWTR HIGH WATER
HYDT HYDRANT
ICN INCINERATOR

IF INSIDE FACE
IL INDICATING LAMP
INF INFLUENT
INS INSULATE(D)(ION)
INTER INTERMEDIATE
INT INTERIOR
INV INVERT
IT INSTRUMENT TAP

JST JOIST

K KIP (1000 POUNDS)
KV KIOLOVOLT
KVA KIOLOVOLT AMPERE
KVAR KILOVAR
KW KILOWATT

LAT LEAVING AIR TEMPERATURE, LATERAL, LATITUDE
LCP LOCAL CONTROL PANEL
LE LEVEL METER
LEL LOWER EXPLOSIVE LIMIT
LGW LOWER GREASEWOOD
LIT LEVEL INDICATION TRANSMITTER

LOD LIMITS OF DISTURBMENTS
LOS LOCKOUT STOP
LS LIMIT SWITCH

MBH THOUSAND BTU'S PER HOUR
MCC MOTOR CONTROL CENTER
MCM THOUSAND CIRCULAR MILLS
MCU MASTER CONTROL UNIT
MD MOTORIZED DAMPER
MEE MISCELLANEOUS ELECTRICAL EQUIPMENT
MGD MILLION GALLONS PER DAY
MG/I MILLIGRAMS PER LITER
MIE MISCELLANEOUS INSTRUMENTATION EQUIPMENT
MILSPEC MILITARY SPECIFICATION
MIN MINIMUM, MINUTE
MJ MECHANICAL JOINT
ML MILLILITER
MME MISCELLANEOUS MECHANICAL EQUIPMENT
MOP MOTOR OPERATOR
MOV MOTOR OPERATED VALVE
MUL/DIV MULTIPLY/DIVIDE
MV MUD VALVE, MILLIVOLT
MX MIXER

N NEUTRAL
NA NONAUTOMATIC
NAOH SODIUM HYDROXIDE
NEG NEGATIVE
NC NORMALLY CLOSED
NF NONFUSED
NOX NITRATES AND NITRITES
NPSH NET POSITIVE SUCTION HEAD
NRS NONRISING STEM

OA OUTSIDE AIR, OVERALL
OAI OUTSIDE AIR INTAKE
OB OPPOSED BLADE
OL OVERLOAD
O-O OUT TO OUT
ORF ODOR REMOVAL FILTER
ORP OXIDATION REDUCTION POTENTIAL
ORT ODOR REMOVAL TOWER
OSA OUTSIDE AIR
OSC ODOR SCRUBBER

P PUMP
PAR PARALLEL
PC PLAIN CONCRETE, PIPE COUPLING
PCC PLANT CONTROL CENTER
PCHV PINCH VALVE
PCP PLAIN CONCRETE PIPE
PC-T PIPE COUPLING TO TAKE TENSION
PCU PHOTOELECTRIC CONTROL UNIT
P/E PNEUMATIC/ELECTRIC
PF POWER FACTOR
PI PROPORTIONAL PLUS INTEGRAL CONTROL , PRESSURE GAUGE
PID PROPORTIONAL PLUS INTEGRAL PLUS DERIVATIVE CONTROL
PIT PRESSURE INDICATING TRANSMITTER
PIVC POINT OF INTERSECTION ON VERTICAL CURVE
PL PROPERTY LINE, PIPELINE, PLATE
PLV PLUG VALVE
PLYWD PLYWOOD
PMP PUMP
PNL PANEL, PANELBOARD
PO4 PHOSPHATE
POP PNEUMATIC OPERATOR
PP POWER POLE
PRES PRESSURE
PRD PRESSURE RELIEF DAMPER
PRV PRESSURE REGULATING (REDUCING) (RELIEF) VALVE
PRS PRESSURE REDUCING STATION
PS PRESSURE SWITCH, PRESSURE SENSOR , PUMP STATION
PSIA POUND PER SQUARE INCH ABSOLUTE
PSIG POUNDS PER SQUARE INCH GAGE
PV PLUG VALVE, PROCESS VARIABLE
PVL PRESSURE VESSEL
PVT PAVEMENT

Q RATE OF FLOW
QCPLG QUICK COUPLING

R RADIUS
RA RETURN AIR
RAF ROLL TYPE AIR FILTER
RCR RECORDER
REC RECEIVER
RECD RECEIVED
RECP RECEPTACLE
RED REDUCE(R)
REG REGULATOR
REL RELAY
RT RIGHT
RTP REINFORCED THERMOSET PLASTIC
RTU REMOTE TERMINAL UNIT
RGS RIGID GALVANIZED STEEL
RL REDUCED LEVEL
RW RECLAIMED WATER
RWCD RECALIMED WATER CONSERVATION DISTRICT
RWL RAINWATER LEADER

S SOUTH, SILENCER
SB SIGNAL BOX
SBD SWITCHBOARD
SCR SCRUBBER
SD SPLITTER DAMPER, SMOKE DETECTOR
SEP SEPARATOR
SG SUPPLY GRILLE, SLUICE GATE
SI SPEED INCREASER
SIM SIMILAR
SL SLOPE
SLG SLIDE GATE
SLR SILENCER
SN SCREEN
SP SPACE, SET POINT, STATIC PRESSURE
SPG SPACING
SPT SOUND POWERED TELEPHONE
SO2 SULFUR DIOXIDE
SPL SPLICE
SR SPEED REDUCER, SALT RIVER PROJECT
SRV SAFETY RELIEF VALVE
SRG SPLIT-RANGING
SS STAINLESS STEEL, SANITARY SEWER, SPEED SELECTOR
SSC SOLID STATE CONTROLLER
SSFH STAINLESS STEEL FLAT HEAD
SSK SERVICE SINK
ST START
STD STANDARD
STGA STARTING AIR
SUB SUBSTITUTE
SUP SUMP PUMP
SV SOLENOID VALVE
SWB SWITCHBOARD
SWGR SWITCHGEAR
SYM SYMMETRICAL

TP TANGENT POINT
TB TERMINAL BOX
T/B TOP OF BANK
TBN TURBINE
T/C TOP OF CURB
TCL TOTALLY CLOSED
TCP TEMPERATURE CONTROL PANEL
TD TIME DELAY RELAY
TFR TRANSFORMER
TNK TANK
TOA TEST-OFF-AUTO
TOC TOTAL ORGANIC CARBON
TPG TOPPING
TPLX TRIPLEXED
TR TIMING RELAY, STAIR TREAD
TRM TRANSMITTER
TRN TRANSDUCER
TRS TRANSFER SWITCH
TS TEMPERATURE SWITCH
TV THERMOSTATIC VALVE

UG UNDERGROUND
UL ULTIMATE LOAD
UN UNION
UP UTILITY POLE
UPS UNINTERRUPTIBLE POWER SUPPLY
US UTILITY STATION
USS UNIT SUBSTATION

V VALVE, VOLTS
VAC VOLTS ALTERNATING CURRENT
VAR VARIES, VARIABLE
VC VERTICAL CURVE
VCP VITRIFIED CLAY PIPE
VD VOLUME DAMPER
VDC VOLTS DIRECT CURRENT
VEN VENTILATOR
VFD VARIABLE FREQUENCY DRIVE
VFT VACUUM FILTER
VP VAPOR PRESSURE, VACUUM PUMP
VSC VARIABLE SPEED COUPLING
VTR VENT THROUGH ROOF
VV VARIABLE VOLUME BOX

WC WATER CLOSET, WATER COLUMN
WCO WALL CLEANOUT
WEG WALL EXHAUST GRILLE
WER WALL EXHAUST REGISTER
WF WIDE FLANGE
WG WASTE GAS
WM WATER METER
WSR WALL SUPPLY REGISTER, WASHER
WSTP WATERSTOP
WT WATERTIGHT
WTP WATER TREATMENT PLANT
WV WATER VALVE
WWF WELDED WIRE FABRIC, WET WEATHER FLOW

X SPARE CONDUIT
XLP CROSS LINKED POLYETHYLENE
XP EXPLOSION-PROOF


YCO YARD CLEANOUT

ZS POSITION SWITCH

- NOTES:
1. ADDITIONAL ABBREVIATIONS ARE DEFINED IN ANSI Y1.1-1972.
2. ABBREVIATIONS FOR PIPING SYSTEMS ARE SPECIFIED IN SECTION 15050.



SALT LAKE CITY, UT



CONSTRUCTION
ISSUE



DILKON PASS
PIPELINE AND
PUMP STATION

REVISIONS

REV	DATE	DESCRIPTION

LINE IS 2 INCHES
AT FULL SIZE

DESIGNED: C. WILLMORE

DRAWN: T. PRIDEMORE

CHECKED: C. WILLMORE

CHECKED: - -

APPROVED: S. BRENCHELY

FILENAME

G-003.dwg

BC PROJECT NUMBER

157520

CLIENT PROJECT NUMBER

GENERAL

STANDARD
ABBREVIATIONS

DRAWING NUMBER

G-003

SHEET NUMBER
OF

4

59

Path: C:\USERS\TPRIDEMORE\ONE\DRIVE - BROWN AND CALDWELL\DOCUMENTS\WORK\TEMP - CAD\NAVAJO NATION\DILKON PASSEXPORT FILENAME: G-004.DWG PLOT DATE: 2/23/2022 4:55 PM CAD USER: TYLER PRIDEMORE



SALT LAKE CITY, UT



CONSTRUCTION
ISSUE



DILKON PASS
PIPELINE AND
PUMP STATION

REVISIONS

REV	DATE	DESCRIPTION

LINE IS 2 INCHES
AT FULL SIZE

DESIGNED: C. WILLMORE

DRAWN: T. PRIDEMORE

CHECKED: C. WILLMORE

CHECKED: - -

APPROVED: S. BRANCHLEY

FILENAME

G-004.dwg

BC PROJECT NUMBER

157520

CLIENT PROJECT NUMBER

GENERAL

VICINITY MAP

DRAWING NUMBER

G-004

5 SHEET NUMBER
OF 59


Call at least two full working days
before you begin excavation.

ARIZONA 811
Arizona Blue Stake, Inc.

Dial 8-1-1 or 1-800-STAKE-IT (782-5348)
In Maricopa County: (602) 263-1100

Path: E:\21533 DILKON PASS WL.DWG FILENAME: DILKON PASS WATERLINE.DWG PLOT DATE: 3/22/2022 3:46 PM CAD USER: HALBERT GOLDTOOTH

1 2 3 4 5 6



SCALE: 1" = 400'
0 200 400 800

RESULTS OF SURVEY
DILKON PASS WATER SYSTEM
PROPOSED WATERLINE
5.39 ± ACRE
LOCATED IN SECTIONS 23 & 24
T. 23 N., R. 20 E., G.&S.R.M.
DILKON, NAVAJO COUNTY, ARIZONA
DILKON CHAPTER, DISTRICT 17, NAVAJO NATION

LINE TABLE		
LINE	LENGTH	DIRECTION
L1	14.14	N 50°43'14" W
L2	1776.23	S 84°13'16" W
L3	1933.31	S 84°12'46" W
L4	18.36	N 50°34'13" W
L5	64.00	S 84°23'36" W
L6	20.46	N 50°34'19" W
L7	67.24	S 39°25'41" W
L8	3923.38	S 84°12'20" W
L9	10.00	N 05°47'25" W

POINT OF
TERMINUS

PROJECT COORDINATE SYSTEM:
PROJECT ORIGIN: POINT #300
ARIZONA STATE PLANE EAST ZONE 0201
NAD83 (2011)
VERTICAL DATUM NAVD88 GEOID 12B
LATITUDE: N 35°22'44.62687"
LONGITUDE: W 110°12'06.98144"
ELLIPSOID: 1861.716m
ORTHO: 1884.524m
SPC NORTHING: 485,625.369 m
SPC EASTING: 210,155.267 m
COMBINED SCALE FACTOR: 0.99960803

MODIFIED TO GROUND COORDINATES (INTERNATIONAL FEET)
PROJECT PRIMARY POINT #300
MODIFIED NORTHING: 1,593,883.84 FT.
MODIFIED EASTING: 689,756.15 FT.
OORTHO: 6182.823 FT.


REFERENCES:
(R1) BUREAU OF LAND MANAGEMENT SURVEY PLAT 1305-A, DATED JUNE 26, 2006.
(R2) AS-BUILT RIGHT-OF-WAY MAP OF WATER SYSTEM & INDIVIDUAL WASTE DISPOSAL FACILITIES, PROJECT NO. NA-78-206, OFFICE OF ENVIRONMENTAL HEALTH & ENGINEERING, INDIAN HEALTH SERVICE, DATED APRIL 10, 1980.
(R3) STATE PLANE COORDINATES PER NATIONAL GEODETIC SURVEY, O.P.U.S. PROCESSED GPS DATA.

BASIS OF BEARINGS:
THE NORTH SECTION LINE OF SECTION 24, T. 23 N., R. 20 E., WITH A GRID BEARING OF S 89°09'42" W AND A B.L.M. BEARING OF S 89°10'00" W PER B.L.M. PLAT 1305-A. THE ARIZONA STATE PLANE COORDINATE EAST ZONE 0201 GRID BEARING DERIVED FROM GPS OBSERVATIONS AND NATIONAL GEODETIC SURVEY OPUS REPORTS.

SURVEYOR'S NOTE:
1. THE LOCATION OF THE BOUNDARY OF THIS TRACT WAS DETERMINED BY THE LOCATION OF THE EXISTING WATER SYSTEM STRUCTURES. THE PREVIOUS SURVEY DID NOT MATCH THE EXISTING WATER SYSTEM. THIS SURVEY MAKES NO STATEMENT REGARDING RIGHTS TO THIS TRACT OR PRIOR RIGHTS WHICH MAY HAVE EXISTED PRIOR TO THIS SURVEY.

CERTIFICATION:
THIS IS TO CERTIFY THAT THE SURVEY AND SUBDIVISION OF THE PREMISES DESCRIBED AND PLATTED HEREON WERE MADE UNDER MY DIRECTION DURING THE MONTH OF NOVEMBER OF 2021; THAT THE SURVEY IS TRUE AND COMPLETE AS SHOWN; THAT MONUMENTS SHOWN ACTUALLY EXIST OR WILL BE SET AS SHOWN; THAT THEIR POSITIONS ARE CORRECTLY SHOWN, AND THAT SAID MONUMENTS ARE SUFFICIENT TO ENABLE THE SURVEY TO BE RETRACED.

HALBERT O. GOLDTOOTH, AZ RLS 42048



LEGAL DESCRIPTION:

A STRIP OF LAND 30 FEET WIDE SITUATED WITHIN SECTIONS 23 & 24, TOWNSHIP 23 NORTH, RANGE 20 EAST, GILA & SALT RIVER MERIDIAN, DISTRICT 17, NAVAJO NATION, IN DILKON, NAVAJO COUNTY, STATE OF ARIZONA, MORE PARTICULARLY DESCRIBED AS FOLLOWS:

COMMENCING AT THE NORTHEAST CORNER OF SECTION 24, TOWNSHIP 23 NORTH, RANGE 20 EAST, MARKED BY B.L.M. BRASS CAP, FROM WHICH THE NORTH QUARTER CORNER OF SECTION 24 LIES S 89°09'42" W, A DISTANCE OF 2672.20 FEET (BASIS OF BEARINGS, ARIZONA STATE PLANE EAST ZONE GRID BEARING)(S 89°10'00" W, 2672.34 FEET PER B.L.M. SURVEY PLAT 1035-A, DATED JUNE 26, 2006, R2); THENCE S 53°13'57" W, A DISTANCE OF 2206.09 FEET TO THE POINT OF BEGINNING OT THE HEREIN DESCRIBED CENTERLINE;

THENCE N 50°43'14" W, A DISTANCE OF 14.14 FEET;
THENCE S 84°13'16" W, A DISTANCE OF 1776.23 FEET;
THENCE S 84°12'46" W, A DISTANCE OF 1933.31 FEET;
THENCE N 50°34'13" W, A DISTANCE OF 18.36 FEET;
THENCE S 84°23'36" W, A DISTANCE OF 64.00 FEET;
THENCE N 50°34'19" W, A DISTANCE OF 20.46 FEET;
THENCE S 39°25'41" W, A DISTANCE OF 67.24 FEET;
THENCE S 84°12'20" W, A DISTANCE OF 3923.38 FEET;
THENCE N 05°47'25" W, A DISTANCE OF 10.00 TO THE POINT OF TERMINUS OF SAID CENTERLINE.

THE SIDE LINES OF SAID 30-FOOT WIDE EASEMENT LYING 15 FEET ON EACH SIDE OF CENTERLINE TO BE EXTENDED OR SHORTENED TO MEET AT ANGLE.

SAID PARCEL BEING 5.39 ACRES MORE OR LESS AND BEING SUBJECT TO ANY AND ALL EXISTING EASMENTS FOR UTILITIES LOCATED THEREIN.



EXHIBIT "A"

LEGEND:

- FOUND 3" BRASS CAP, B.L.M. SECTION CORNER
- FOUND 3" BRASS CAP, B.L.M. 1/4 CORNER
- SET 5/8" REBAR W/ PLASTIC CAP STAMPED "GPS RLS 42048"
- CALCULATED POINT, NOTHING FOUND OR SET

CONTROL MONUMENTS:

POB: LAT 35°32'58.19948" N; LONG 109°49'25.43144" W
SECTION CORNER: LAT 35°23'14.30128" N; LONG 110°09'38.62143" W
1/4 CORNER: LAT 35°23'13.91510" N; LONG 110°10'10.88103" W



SALT LAKE CITY, UT



CONSTRUCTION
ISSUE



DILKON PASS
PIPELINE AND
PUMP STATION

REVISIONS

REV	DATE	DESCRIPTION

LINE IS 2 INCHES
AT FULL SIZE

DESIGNED:

DRAWN: H.GOLDTOOTH

CHECKED: H.GOLDTOOTH

CHECKED:

APPROVED: H.GOLDTOOTH

FILENAME

BC PROJECT NUMBER

157520

CLIENT PROJECT NUMBER

00357.21

RESULTS OF SURVEY

DRAWING NUMBER

V-001

6

SHEET NUMBER
OF



59

1 2 3 4 5 6

Path: E:\21533 DILKON PASS WL.DWG FILENAME: DILKON BPS TRACT.DWG PLOT DATE: 3/2/2022 3:48 PM CAD USER: HALBERT GOLDTOOTH

PROJECT COORDINATE SYSTEM:
PROJECT ORIGIN: Point #300
ARIZONA STATE PLANE EAST ZONE 0201
NAD83 (2011)
VERTICAL DATUM NAVD88 GEOID 12B
LATITUDE: N 35°22'44.62687"
LONGITUDE: W 110°12'06.98144"
ELLIPSOID: 1861.716m
ORTHO: 1864.524m
SPC NORTHING: 485,625.369 m
SPC EASTING: 210,155.267 m
COMBINED SCALE FACTOR: 0.99960803

MODIFIED TO GROUND COORDINATES (INTERNATIONAL FEET)
PROJECT PRIMARY POINT #300
MODIFIED NORTHING: 1,593,883.84 FT.
MODIFIED EASTING: 689,756.15 FT.
OORTHO: 6182.823 FT.



RESULTS OF SURVEY

DILKON PASS WATER SYSTEM
BOOSTER PUMP STATION TRACT
0.21 ± ACRE
LOCATED IN SECTION 23
T. 23 N., R. 20 E., G.&S.R.M.
DILKON, NAVAJO COUNTY, ARIZONA
DILKON CHAPTER, DISTRICT 17, NAVAJO NATION

LEGAL DESCRIPTION:
A PARCEL OF LAND SITUATED WITHIN SECTION 23, TOWNSHIP 23 NORTH, RANGE 20 EAST, GILA & SALT RIVER MERIDIAN, DISTRICT 17, NAVAJO NATION, IN DILKON, NAVAJO COUNTY, STATE OF ARIZONA, MORE PARTICULARLY DESCRIBED AS FOLLOWS:

COMMENCING AT THE NORTHEAST CORNER OF SECTION 23 MARKED BY A B.L.M. BRASS CAP, FROM WHICH THE EAST QUARTER CORNER OF SECTION 23 LIES S 00°09'19" E, A DISTANCE OF 2652.27 FEET (BASIS OF BEARINGS, ARIZONA STATE PLANE EAST ZONE GRID BEARING)(N 00°10'00" W, 2651.88 FEET PER B.L.M. SURVEY PLAT 1035-A, DATED JUNE 26, 2006, R1); THENCE S 04°56'54" W, A DISTANCE OF 1527.88 FEET TO A 5/8" REBAR WITH PLASTIC CAP STAMPED "GPS RLS 42048"; SAID POINT BEING THE POINT OF BEGINNING OF THE HEREIN DESCRIBED PARCEL OF LAND;

THENCE S 05°37'27" E, A DISTANCE OF 47.47 FEET TO A 5/8" REBAR WITH PLASTIC CAP STAMPED "GPS RLS 42028";
THENCE S 50°34'13" E, A DISTANCE OF 53.86 FEET TO A 5/8" REBAR WITH PLASTIC CAP STAMPED "GPS RLS 42028";
THENCE S 83°58'22" W, A DISTANCE OF 54.71 FEET TO A 5/8" REBAR WITH PLASTIC CAP STAMPED "GPS RLS 42028";
THENCE S 84°13'27" W, A DISTANCE OF 83.34 FEET TO A 5/8" REBAR WITH PLASTIC CAP STAMPED "GPS RLS 42028";
THENCE N 05°37'27" W, A DISTANCE OF 86.20 FEET TO A 5/8" REBAR WITH PLASTIC CAP STAMPED "GPS RLS 42028";
THENCE N 84°22'33" E, A DISTANCE OF 100.00 FEET TO THE POINT OF BEGINNING.

SAID PARCEL BEING 0.21 ACRES MORE OR LESS BEING SUBJECT TO ANY EXISTING EASMENTS FOR UTILITIES LOCATED THEREIN.

EXHIBIT "A"

LEGEND:

- - FOUND 3" BRASS CAP, B.L.M. SECTION CORNER
- - FOUND 3" BRASS CAP, B.L.M. 1/4 CORNER
- ⊙ - SET 5/8" REBAR W/ PLASTIC CAP STAMPED "GPS RLS 42048"
- - CALCULATED POINT, NOTHING FOUND OR SET

CONTROL MONUMENTS:

POB: LAT 35°22'58.48126" N; LONG 110°10'44.73058" W
SECTION CORNER: LAT 35°23'13.53143" N; LONG 110°10'43.14167" W
1/4 CORNER: LAT 35°22'47.30809" N; LONG 110°10'43.05096" W

REFERENCES:

- (R1) BUREAU OF LAND MANAGEMENT SURVEY PLAT 1305-A, DATED JUNE 26, 2006.
- (R2) AS-BUILT RIGHT-OF-WAY MAP OF WATER SYSTEM & INDIVIDUAL WASTE DISPOSAL FACILITIES, PROJECT NO. NA-78-206, OFFICE OF ENVIRONMENTAL HEALTH & ENGINEERING, INDIAN HEALTH SERVICE, DATED APRIL 10, 1980.
- (R3) STATE PLANE COORDINATES PER NATIONAL GEODETIC SURVEY, O.P.U.S. PROCESSED GPS DATA.

BASIS OF BEARINGS:

THE EAST SECTION LINE OF SECTION 23, T. 23 N., R. 20 E., WITH A GPS DERIVED BEARING OF S 00°09'19" E AND A B.L.M. BEARING OF N 00°10'00" W PER B.L.M. PLAT 1305-A. THE ARIZONA STATE PLANE COORDINATE EAST ZONE 0201 GRID BEARING DERIVED FROM GPS OBSERVATIONS AND NATIONAL GEODETIC SURVEY OPUS REPORTS.


SURVEYOR'S NOTE:

- THE LOCATION OF THE BOUNDARY OF THIS TRACT WAS DETERMINED BY THE LOCATION OF THE EXISTING WATER SYSTEM STRUCTURES. THE PREVIOUS SURVEY DID NOT MATCH THE EXISTING WATER SYSTEM. THIS SURVEY MAKES NO STATEMENT REGARDING RIGHTS TO THIS TRACT OR PRIOR RIGHTS WHICH MAY HAVE EXISTED PRIOR TO THIS SURVEY.

CERTIFICATION:

THIS IS TO CERTIFY THAT THE SURVEY AND SUBDIVISION OF THE PREMISES DESCRIBED AND PLATTED HEREON WERE MADE UNDER MY DIRECTION DURING THE MONTH OF NOVEMBER OF 2021; THAT THE SURVEY IS TRUE AND COMPLETE AS SHOWN; THAT MONUMENTS SHOWN ACTUALLY EXIST OR WILL BE SET AS SHOWN; THAT THEIR POSITIONS ARE CORRECTLY SHOWN, AND THAT SAID MONUMENTS ARE SUFFICIENT TO ENABLE THE SURVEY TO BE RETRACED.

HALBERT O. GOLDTOOTH, AZ RLS 42048



SALT LAKE CITY, UT



CONSTRUCTION
ISSUE



DILKON PASS
PIPELINE AND
PUMP STATION

REVISIONS

REV	DATE	DESCRIPTION

LINE IS 2 INCHES
AT FULL SIZE

DESIGNED:

DRAWN: H.GOLDTOOTH

CHECKED: H.GOLDTOOTH

CHECKED:

APPROVED: H.GOLDTOOTH

FILENAME

BC PROJECT NUMBER

157520

CLIENT PROJECT NUMBER

00357.21

RESULTS OF SURVEY

DRAWING NUMBER

V-002

7


SHEET NUMBER
OF

59

Path: E:\21533 DILKON WASH WASH ROW.DWG PLOT DATE: 3/11/2022 2:35 PM CAD USER: HALBERT GOLDTOOTH

PROJECT COORDINATE SYSTEM:
PROJECT ORIGIN: Point #300
ARIZONA STATE PLANE EAST ZONE 0201
NAD83 (2011)
VERTICAL DATUM NAVD88 GEOID 12B
LATITUDE: N 35°22'50.35144"
LONGITUDE: W 110°19'07.39838"
ELLIPSOID: 1780.559 m
ORTHO: 1803.600 m
SPC NORTHING: 485,811.818 m
SPC EASTING: 199,545.132 m
COMBINED SCALE FACTOR: 0.99962298

MODIFIED TO GROUND COORDINATES (INTERNATIONAL FEET)
PROJECT PRIMARY POINT #300
MODIFIED NORTHING: 1,594,471.943 FT.
MODIFIED EASTING: 654,922.551 FT.
OORTHO: 5917.324 FT.



RESULTS OF SURVEY

DILKON PASS WATER SYSTEM
DILKON WASH CROSSING
0.54 ± ACRE
LOCATED IN SECTION 20
T. 23 N., R. 19 E., G.&S.R.M.
DILKON, NAVAJO COUNTY, ARIZONA
DILKON CHAPTER, DISTRICT 17, NAVAJO NATION

LEGAL DESCRIPTION:
A STRIP OF LAND 30 FEET WIDE SITUATED WITHIN SECTION 20, TOWNSHIP 23 NORTH, RANGE 19 EAST, GILA & SALT RIVER MERIDIAN, DISTRICT 17, NAVAJO NATION, IN DILKON, NAVAJO COUNTY, STATE OF ARIZONA, MORE PARTICULARLY DESCRIBED AS FOLLOWS:

COMMENCING AT THE SOUTHEAST CORNER OF SECTION 20, TOWNSHIP 23 NORTH, RANGE 20 EAST, MARKED BY B.L.M. BRASS CAP, FROM WHICH THE NORTH QUARTER CORNER OF SECTION 24 LIES N 01°05'59" W, A DISTANCE OF 2613.32 FEET (BASIS OF BEARINGS, ARIZONA STATE PLANE EAST ZONE GRID BEARING) N 01°00'00" E, 2613.60 FEET PER B.L.M. SURVEY PLAT 1035-B, DATED JULY 20, 2005, R2); THENCE N 09°48'05" W, A DISTANCE OF 799.20 FEET TO THE POINT OF BEGINNING OT THE HEREIN DESCRIBED CENTERLINE;

THENCE N 00°30'33" E, A DISTANCE OF 14.14 FEET;
THENCE N 44°29'26" W, A DISTANCE OF 760.86 FEET;
THENCE N 89°29'26" W, A DISTANCE OF 14.14 TO THE POINT OF TERMINUS OF SAID CENTERLINE.

THE SIDE LINES OF SAID 30-FOOT WIDE EASEMENT LYING 15 FEET ON EACH SIDE OF CENTERLINE TO BE EXTENDED OR SHORTENED TO MEET AT ANGLE.

SAID PARCEL BEING 0.54 ACRES MORE OR LESS AND BEING SUBJECT TO ANY AND ALL EXISTING EASMENTS FOR UTILITIES LOCATED THEREIN.

EXHIBIT "A"

LEGEND:

- FOUND 3" BRASS CAP, B.L.M. SECTION CORNER
- FOUND 3" BRASS CAP, B.L.M. 1/4 CORNER
- SET 5/8" REBAR W/ PLASTIC CAP STAMPED "GPS RLS 42048"
- CALCULATED POINT, NOTHING FOUND OR SET

CONTROL MONUMENTS:

POB: LAT 35°22'32.11158" N; LONG 110°20'10.67172" W
SE CORNER SECTION 20: LAT 35°22'24.10995" N; LONG 110°20'08.75160" W
E 1/4 CORNER SECTION 20: LAT 35°22'49.94473" N; LONG 110°20'08.19994" W

REFERENCES:

- (R1) BUREAU OF LAND MANAGEMENT SURVEY PLAT 1305-B, DATED JULY 20, 2005.
- (R2) AS-BUILT RIGHT-OF-WAY MAP OF WATER SYSTEM & INDIVIDUAL WASTE DISPOSAL FACILITIES, PROJECT NO. NA-78-206, OFFICE OF ENVIRONMENTAL HEALTH & ENGINEERING, INDIAN HEALTH SERVICE, DATED APRIL 10, 1980.
- (R3) STATE PLANE COORDINATES PER NATIONAL GEODETIC SURVEY, O.P.U.S. PROCESSED GPS DATA.

BASIS OF BEARINGS:

THE EAST SECTION LINE OF SECTION 20, T. 23 N., R. 19 E., WITH A GPS DERIVED BEARING OF N 01°05'59" E AND A B.L.M. BEARING OF N 01°00'00" E PER B.L.M. PLAT 1305-B. THE ARIZONA STATE PLANE COORDINATE EAST ZONE 0201 GRID BEARING DERIVED FROM GPS OBSERVATIONS AND NATIONAL GEODETIC SURVEY OPUS REPORTS.


SURVEYOR'S NOTE:

- THE LOCATION OF THE BOUNDARY OF THIS TRACT WAS DETERMINED BY THE LOCATION OF THE EXISTING WATER SYSTEM STRUCTURES. THE PREVIOUS SURVEY DID NOT MATCH THE EXISTING WATER SYSTEM. THIS SURVEY MAKES NO STATEMENT REGARDING RIGHTS TO THIS TRACT OR PRIOR RIGHTS WHICH MAY HAVE EXISTED PRIOR TO THIS SURVEY.


CERTIFICATION:

THIS IS TO CERTIFY THAT THE SURVEY AND SUBDIVISION OF THE PREMISES DESCRIBED AND PLATTED HEREON WERE MADE UNDER MY DIRECTION DURING THE MONTH OF NOVEMBER OF 2021; THAT THE SURVEY IS TRUE AND COMPLETE AS SHOWN; THAT MONUMENTS SHOWN ACTUALLY EXIST OR WILL BE SET AS SHOWN; THAT THEIR POSITIONS ARE CORRECTLY SHOWN, AND THAT SAID MONUMENTS ARE SUFFICIENT TO ENABLE THE SURVEY TO BE RETRACED.

Halbert O. Goldtooth
HALBERT O. GOLDTOOTH, AZ RLS 42048



SALT LAKE CITY, UT



CONSTRUCTION ISSUE



DILKON PASS PIPELINE AND PUMP STATION

REVISIONS

REV	DATE	DESCRIPTION

LINE IS 2 INCHES
AT FULL SIZE

DESIGNED:
DRAWN: H.GOLDTOOTH
CHECKED: H.GOLDTOOTH
CHECKED:
APPROVED: H.GOLDTOOTH
FILENAME


BC PROJECT NUMBER
157520
CLIENT PROJECT NUMBER
00357.21

RESULTS OF SURVEY

DRAWING NUMBER
V-003

8 SHEET NUMBER
OF 59

Path: E:\21533 DILKON PASS WLDWG FILENAME: DILKON PASS CHECK VALVE ROW.DWG PLOT DATE: 2/24/2022 12:34 PM CAD USER: HALBERT GOLDTOOTH



PROJECT COORDINATE SYSTEM:
PROJECT ORIGIN: Point #300
ARIAONA STATE PLANE EAST ZONE 0201
NAD83 (2011)
VERTICAL DATUM NAVD88 GEOID 12B
LATITUDE: N 35°22'44.62687"
LONGITUDE: W 110°12'06.98144"
ELLIPSOID: 1861.716m
ORTHO: 1884.524m
SPC NORTHING: 485,625.369 m
SPC EASTING: 210,155.267 m
COMBINED SCALE FACTOR: 0.99960803

MODIFIED TO GEOUND COORDINATES (INTERNATIONAL FEET)
PROJECT PRIMARY POINT #300
MODIFIED NORTHING: 1,593,883.84 FT.
MODIFIED EASTING: 689,756.15 FT.
OORTHO: 6182.823 FT.

RESULTS OF SURVEY

DILKON PASS WATER SYSTEM
CHECK VALVE PROPOSED WATERLINE

0.02 ± ACRE

LOCATED IN SECTION 19

T. 23 N., R. 21 E., G.&S.R.M.

DILKON, NAVAJO COUNTY, ARIZONA

DILKON CHAPTER, DISTRICT 17, NAVAJO NATION

LEGAL DESCRIPTION:

A STRIP OF LAND 30 FEET WIDE SITUATED WITHIN SECTION 19, TOWNSHIP 23 NORTH, RANGE 21 EAST, GILA & SALT RIVER MERIDIAN, DISTRICT 17, NAVAJO NATION, IN DILKON, NAVAJO COUNTY, STATE OF ARIZONA, MORE PARTICULARLY DESCRIBED AS FOLLOWS:

COMMENCING AT THE NORTHWEST CORNER OF SECTION 19, TOWNSHIP 23 NORTH, RANGE 21 EAST, MARKED BY B.L.M. BRASS CAP, FROM WHICH THE NORTH QUARTER CORNER OF SECTION 19 LIES N 87°23'57" E, A DISTANCE OF 2470.25 FEET (BASIS OF BEARINGS, ARIZONA STATE PLANE EAST ZONE GRID BEARING)(S 87°24'00" W, 2470.38 FEET PER B.L.M. SURVEY PLAT 1036-A, DATED JANUARY 9, 2006, R1); THENCE S 09°59'07" E, A DISTANCE OF 698.68 FEET TO THE POINT OF BEGINNING OT THE HEREIN DESCRIBED CENTERLINE;

THENCE N 70°18'40" E, A DISTANCE OF 8.63 FEET;
THENCE S 19°41'20" E, A DISTANCE OF 16.00 FEET;
THENCE S 70°18'40" W, A DISTANCE OF 8.63 TO THE POINT OF TERMINUS OF SAID CENTERLINE.

THE SIDE LINES OF SAID 30-FOOT WIDE EASEMENT LYING 15 FEET ON EACH SIDE OF CENTERLINE TO BE EXTENDED OR SHORTENED TO MEET AT ANGLE.

SAID PARCEL BEING 0.02 ACRES MORE OR LESS AND BEING SUBJECT TO ANY AND ALL EXISTING EASMENTS FOR UTILITIES LOCATED THEREIN.

EXHIBIT "A"

LEGEND:

- FOUND 3" BRASS CAP, B.L.M. SECTION CORNER
- FOUND 3" BRASS CAP, B.L.M. 1/4 CORNER
- SET 5/8" REBAR W/ PLASTIC CAP STAMPED "GPS RLS 42048"
- CALCULATED POINT, NOTHING FOUND OR SET

CONTROL MONUMENTS:

POB: LAT 35°23'07.49796" N; LONG 110°09'37.15928" W
SECTION CORNER: LAT 35°23'14.30128" N; LONG 110°09'38.62133" W
1/4 CORNER: LAT 35°23'15.40406" N; LONG 110°09'08.82705" W

REFERENCES:

- (R1) BUREAU OF LAND MANAGEMENT SURVEY PLAT 1305-A, DATED JUNE 26, 2006.
- (R2) AS-BUILT RIGHT-OF-WAY MAP OF WATER SYSTEM & INDIVIDUAL WASTE DISPOSAL FACILITIES, PROJECT NO. NA-78-206, OFFICE OF ENVIRONMENTAL HEALTH & ENGINEERING, INDIAN HEALTH SERVICE, DATED APRIL 10, 1980.
- (R3) STATE PLANE COORDINATES PER NATIONAL GEODETIC SURVEY, O.P.U.S. PROCESSED GPS DATA.

BASIS OF BEARINGS:

THE EAST SECTION LINE OF SECTION 23, T. 23 N., R. 20 E., WITH A GPS DERIVED BEARING OF S 00°09'19" E AND A B.L.M. BEARING OF N 00°10'00" W PER B.L.M. PLAT 1305-A. THE ARIZONA STATE PLANE COORDINATE EAST ZONE 0201 GRID BEARING DERIVED FROM GPS OBSERVATIONS AND NATIONAL GEODETIC SURVEY OPUS REPORTS.

SURVEYOR'S NOTE:

- THE LOCATION OF THE BOUNDARY OF THIS TRACT WAS DETERMINED BY THE LOCATION OF THE EXISTING WATER SYSTEM STRUCTURES. THE PREVIOUS SURVEY DID NOT MATCH THE EXISTING WATER SYSTEM. THIS SURVEY MAKES NO STATEMENT REGARDING RIGHTS TO THIS TRACT OR PRIOR RIGHTS WHICH MAY HAVE EXISTED PRIOR TO THIS SURVEY.


CERTIFICATION:

THIS IS TO CERTIFY THAT THE SURVEY AND SUBDIVISION OF THE PREMISES DESCRIBED AND PLATTED HEREON WERE MADE UNDER MY DIRECTION DURING THE MONTH OF NOVEMBER OF 2021; THAT THE SURVEY IS TRUE AND COMPLETE AS SHOWN; THAT MONUMENTS SHOWN ACTUALLY EXIST OR WILL BE SET AS SHOWN; THAT THEIR POSITIONS ARE CORRECTLY SHOWN, AND THAT SAID MONUMENTS ARE SUFFICIENT TO ENABLE THE SURVEY TO BE RETRACED.

HALBERT O. GOLDTOOTH, AZ RLS 42048

BASIS OF BEARINGS:

THE NORTH SECTION LINE OF SECTION 19, T. 23 N., R. 21 E., WITH A GRID BEARING OF N 87°23'57" E AND A B.L.M. BEARING OF S 87°24'00" W PER B.L.M. PLAT 1306-A. THE ARIZONA STATE PLANE COORDINATE EAST ZONE 0201 GRID BEARING DERIVED FROM GPS OBSERVATIONS AND NATIONAL GEODETIC SURVEY OPUS REPORTS.



SALT LAKE CITY, UT



CONSTRUCTION ISSUE



DILKON PASS PIPELINE AND PUMP STATION

REVISIONS

REV	DATE	DESCRIPTION

LINE IS 2 INCHES
AT FULL SIZE

DESIGNED:

DRAWN: H.GOLDTOOTH

CHECKED: H.GOLDTOOTH

CHECKED:

APPROVED: H.GOLDTOOTH

FILENAME

BC PROJECT NUMBER

157520

CLIENT PROJECT NUMBER

00357.21

RESULTS OF SURVEY

DRAWING NUMBER


V-004

9

SHEET NUMBER
OF

59

Path: C:\BCP\MD2344906 FILENAME: CD-100.DWG PLOT DATE: 3/4/2022 4:18 PM CAD USER: TYLER PRIDEMORE



GENERAL NOTES


1. ALL LOCATIONS OF UTILITIES SHOWN ARE APPROXIMATE. CONTRACTOR TO FIELD VERIFY AND POTHOLE AS REQUIRED TO COMPLETE THE WORK.
2. CONTRACTOR TO FIELD VERIFY LOCATION, ELEVATIONS, INVERTS, MATERIAL, DIMENSIONS AND CONDITION OF EXISTING UTILITIES.

KEY NOTES

- 1 EXISTING PUMP HOUSE TO BE DEMOLISHED. REMOVE EXISTING EQUIPMENT AND RETURN TO OWNER PRIOR TO DEMOLITION.
- 2 EXISTING WATERLINE TO BE ABANDONED. CUT AND CAP EXISTING LINE, AS REQUIRED.
- 3 EXISTING SUBMERSIBLE PUMP MANHOLE. REMOVE EXISTING EQUIPMENT AND RETURN TO OWNER. REMAINING MANHOLE TO BE ABANDONED AND FILLED WITH TYPE 'K' MATERIAL..
- 4 EXISTING FENCE TO BE REMOVED.
- 5 EXISTING CONCRETE SIDEWALK TO BE REMOVED.
- 6 EXISTING VALVE TO BE ABANDONED IN PLACE.
- 7 EXISTING PRV MANHOLE. REMOVE EXISTING EQUIPMENT AND RETURN TO OWNER. REMAINING MANHOLE TO BE ABANDONED AND FILLED WITH TYPE 'K' MATERIAL.



SALT LAKE CITY, UT



CONSTRUCTION
ISSUE



DILKON PASS
PIPELINE AND
PUMP STATION

REVISIONS

REV	DATE	DESCRIPTION

LINE IS 2 INCHES
AT FULL SIZE

DESIGNED: C. WILLMORE

DRAWN: T. PRIDEMORE

CHECKED: C. WILLMORE

CHECKED: --

APPROVED: S. BRANCHLEY

FILENAME

CD-100.dwg

BC PROJECT NUMBER

157520

CLIENT PROJECT NUMBER

CIVIL DEMOLITION

PUMP STATION
DEMOLITION SITE
PLAN

DRAWING NUMBER

CD-100


10 SHEET NUMBER
OF 59

Call at least two full working days
before you begin excavation.


ARIZONA 811
Arizona Blue Stake, Inc.

Dial 8-1-1 or 1-800-STAKE-IT (782-5348)
In Maricopa County: (602) 263-1100

Path: C:\BCP\DWG C-002.DWG PLOT DATE: 3/4/2022 4:18 PM CAD USER: TYLER PRIDEMORE



SALT LAKE CITY, UT



CONSTRUCTION
ISSUE



DILKON PASS
PIPELINE AND
PUMP STATION

REVISIONS

REV	DATE	DESCRIPTION

LINE IS 2 INCHES
AT FULL SIZE

DESIGNED: C. WILLMORE

DRAWN: T. PRIDEMORE

CHECKED: C. WILLMORE

CHECKED: --

APPROVED: S. BRANCHLEY

FILENAME

C-002.dwg

BC PROJECT NUMBER

157520

CLIENT PROJECT NUMBER

CIVIL

MISCELLANEOUS
DETAILS -1

DRAWING NUMBER

C-002

12

SHEET NUMBER
OF

59

Path: C:\BCP\MD2344906 FILENAME: C-100.DWG PLOT DATE: 3/4/2022 4:20 PM CAD USER: TYLER PRIDEMORE




- KEY NOTES**
- GRAVEL SURFACE, SEE DETAIL D / SHEET C-003. APPROX 5655 SF.
 - ELECTRICAL CABINET, REFERENCE ELECTRICAL PLANS
 - 12.0' DOUBLE-WIDE SWING GATE. SEE IHS STD DWG W-34
 - CHAINLINK FENCING. SEE IHS STD DWG W-34
 - CMU PUMPHOUSE, REFERENCE ARCHITECTURAL AND STRUCTURAL PLANS
 - 6' X 9' PRV ASSEMBLY PER IHS STANDARD DETAIL WS-4B AND WS-4C.
 - CONCRETE PAD

SITE GRADING

MARK	NORTHING	EASTING	ELEVATION	DESCRIPTION
1	1595250.35	696477.96	5964.46	FENCE CORNER
2	1595258.95	696566.22	5962.20	FENCE CORNER
3	1595197.52	696572.20	5962.21	FENCE CORNER
4	1595188.92	696483.94	5963.78	FENCE CORNER
5	1595192.18	696517.40	5963.46	FENCE GATE
6	1595193.34	696529.35	5963.27	FENCE GATE
7	1595145.98	696521.20	5963.46	EDGE OF DRIVE
8	1595147.30	696534.63	5963.46	EDGE OF DRIVE



SALT LAKE CITY, UT



CONSTRUCTION
ISSUE



DILKON PASS
PIPELINE AND
PUMP STATION

REVISIONS

REV	DATE	DESCRIPTION

LINE IS 2 INCHES
AT FULL SIZE

DESIGNED: C. WILLMORE
DRAWN: T. PRIDEMORE
CHECKED: C. WILLMORE
CHECKED: --
APPROVED: S. BRANCHLEY
FILENAME: C-100.dwg
BC PROJECT NUMBER: 157520
CLIENT PROJECT NUMBER

CIVIL

DILKON PASS PUMP
STATION GRADING
PLAN

DRAWING NUMBER
C-100


SHEET NUMBER
14 OF 59

Call at least two full working days
before you begin excavation.

ARIZONA 811
Arizona Blue Stake, Inc.

Dial 8-1-1 or 1-800-STAKE-IT (782-5348)
In Maricopa County: (602) 263-1100

Path: C:\BCP\MD2344906 FILENAME: C-101.DWG PLOT DATE: 3/4/2022 4:21 PM CAD USER: TYLER PRIDEMORE



GENERAL NOTES

- ALL LOCATIONS OF UTILITIES SHOWN ARE APPROXIMATE. CONTRACTOR TO FIELD VERIFY AND POT HOLE AS REQUIRED TO COMPLETE THE WORK.
- CONTRACTOR TO FIELD VERIFY LOCATION, ELEVATIONS, INVERTS, MATERIAL, DIMENSIONS AND CONDITION OF EXISTING UTILITIES.
- CONTRACTOR TO PROVIDE THRUST BLOCKS AT ALL ELBOWS, TEES, CROSSES PER NTUA STD DWG WS-19. MECHANICAL JOINT RESTRAINTS CAN BE UTILIZED IN PLACE OF THRUST BLOCKS. EBA IRON MEGALUG SERIES 2000 PV FOR FITTINGS AND SERIES 2500 FOR PIPE JOINTS - INSTALL PER MANUFACTURE'S RECOMMENDATIONS.
- CONTRACTOR TO INSTALL PIPE IN TRENCH PER DETAIL C / SHEET C-003.
- CONTRACTOR TO INSTALL MARKER POST PER NTUA STD DWG WS-13.
- EASEMENT DIMENSIONS AND PIPELINE OFFSETS ARE SHOWN IN DETAIL B/C-002.
- SEE V-001 FOR COORDINATE CONTROL INFORMATION.
- ALL YARD PIPING TO HAVE MJ X MJ FITTINGS UNLESS NOTED OR OTHERWISE SHOWN IN DETAILS.

KEY NOTES


- 8" X 8" DI TEE
- 8" DIA GATE VALVE
- 8" DI 45D FITTING
- 6" DIA 45D VALVE
- 2" DIA FLUSH LINE, SEE NTUA STD DWG WS-11
- 8" X 6" REDUCER
- 6" DIA ROMAC STYLE 501 FLEXIBLE COUPLING
- 6" DIA DIP PC 350
- 4" DIA HDPE DRAIN LINE
- CMU PUMPHOUSE, REFERENCE ARCHITECTURAL AND STRUCTURAL PLANS
- DRAINAGE INFILTRATORS, SEE DETAIL B / SHEET C-003
- 4" 45D FITTING
- 6" 45D FITTING
- 6" X 9" ANTI-CAVITATION PRV ASSEMBLY PER IHS STANDARD DETAIL WS-4B AND WS-4C. SET DOWNSTREAM PRV PRESSURE SETTING TO 60 PSI.
- COMBO AIR VALVE, SEE NTUA STD DETAL WS-10
- 4" SCHEDULE 200 PVC CONDUIT FOR ELECTRICAL POWER LINE
- CUT & CAP EXISTING PIPE ONCE NEW BOOSTER PUMP STATION HAS BEEN COMPLETED AND BROUGHT ONLINE

SITE PIPING

MARK	DESCRIPTION	NORTHING	EASTING
1	8" X 8" TEE	1595217.73	696481.01
2	8" 45D FITTING	1595228.80	696490.11
3	8" X 8" X 2" TEE	1595229.19	696494.09
4	6" 45D FITTING	1595203.39	696498.45
5	6" X 6" X 2" TEE	1595203.69	696501.44
6	6" X 6" X 2" TEE	1595209.06	696556.17
7	6" 45D FITTING	1595209.65	696562.14
8	8" X 8" X 2" TEE	1595231.55	696552.81
9	8" 45D FITTING	1595232.13	696558.77
10	8" 45D FITTING	1595210.57	696585.00
11	8" 90D FITTING	1595175.40	696588.43



SALT LAKE CITY, UT



CONSTRUCTION ISSUE



DILKON PASS PIPELINE AND PUMP STATION

REVISIONS

REV	DATE	DESCRIPTION

LINE IS 2 INCHES
AT FULL SIZE

DESIGNED: C. WILLMORE

DRAWN: T. PRIDEMORE

CHECKED: C. WILLMORE

CHECKED: --

APPROVED: S. BRENCLEY

FILENAME

C-101.dwg

BC PROJECT NUMBER

157520

CLIENT PROJECT NUMBER

CIVIL

DILKON PASS PUMP STATION YARD PIPING PLAN

DRAWING NUMBER

C-101

SHEET NUMBER
OF

15


59

Call at least two full working days
before you begin excavation.



Dial 8-1-1 or 1-800-STAKE-IT (782-5348)
In Maricopa County: (602) 263-1100

Path: C:\BCP\MD2344906 FILENAME: C-110.DWG PLOT DATE: 3/4/2022 4:22 PM CAD USER: TYLER PRIDEMORE



GENERAL NOTES


1. ALL LOCATIONS OF UTILITIES SHOWN ARE APPROXIMATE. CONTRACTOR TO FIELD VERIFY AND POTHOLE AS REQUIRED TO COMPLETE THE WORK.
2. CONTRACTOR TO FIELD VERIFY LOCATION, ELEVATIONS, INVERTS, MATERIAL, DIMENSIONS AND CONDITION OF EXISTING UTILITIES.
3. CONTRACTOR TO PROVIDE THRUST BLOCKS AT ALL ELBOWS, TEES, CROSSES PER NTUA STD DWG WS-19. MECHANICAL JOINT RESTRAINTS CAN BE UTILIZED IN PLACE OF THRUST BLOCKS. EBA IRON MEGALUG SERIES 2000 PV FOR FITTINGS AND SERIES 2500 FOR PIPE JOINTS - INSTALL PER MANUFACTURE'S RECOMMENDATIONS.
4. CONTRACTOR TO INSTALL PIPE IN TRENCH PER DETAIL C / SHEET C-003.
5. CONTRACTOR TO INSTALL MARKER POST PER NTUA STD DWG WS-13.
6. EASEMENT DIMENSIONS AND PIPELINE OFFSETS ARE SHOWN IN DETAIL B/C-002.
7. SEE V-001 FOR COORDINATE CONTROL INFORMATION.
8. ALL YARD PIPING TO HAVE MJ X MJ FITTINGS UNLESS NOTED OR OTHERWISE SHOWN IN DETAILS.

KEY NOTES

- 1 6" 90d BEND
- 2 CUT EXISTING WATER MAIN
- 3 6" DIA GATE VALVE PER NTUA STD DWG WS-14 AND SECTION 15102
- 4 5' MANHOLE W/ 4" CHECK VALVE AND TWO (2) REDUCERS. SEE DETAIL A / SHEET C-002
- 5 2" DIA DI PC 350 FLUSH LINE, SEE NTUA STD DWG WS-11
- 6 REMOVE EXISTING 6" PVC PIPE



SALT LAKE CITY, UT



CONSTRUCTION ISSUE



DILKON PASS PIPELINE AND PUMP STATION

REVISIONS

REV	DATE	DESCRIPTION

LINE IS 2 INCHES
AT FULL SIZE

DESIGNED: C. WILLMORE

DRAWN: T. PRIDEMORE

CHECKED: C. WILLMORE

CHECKED: --

APPROVED: S. BRENCHELY

FILENAME

C-110.dwg

BC PROJECT NUMBER

157520

CLIENT PROJECT NUMBER

CIVIL

CHECK VALVE SITE PLAN

DRAWING NUMBER

C-110

16 SHEET NUMBER
OF 59

Call at least two full working days
before you begin excavation.



Dial 8-1-1 or 1-800-STAKE-IT (782-5348)
In Maricopa County: (602) 263-1100

Path: C:\USERS\TPRIDEMORE\ONE\DRIVE - BROWN AND CALDWELL\DOCUMENTS\WORK\TEMP CAD\NAVAJO NATION\DILKON PASSE\EXPORT FILENAME: C-200.DWG PLOT DATE: 2/23/2022 5:48 PM CAD USER: TYLER PRIDEMORE



STA 10+00 TO 18+00
SHEET C-201

STA 18+00 TO 26+00
SHEET C-202

STA 26+00 TO 34+00
SHEET C-203

STA 34+00 TO 42+00
SHEET C-204

STA 42+00 TO 49+45
SHEET C-205

STA 49+50 TO 57+50
SHEET C-206

STA 57+50 TO 65+50
SHEET C-207

STA 65+50 TO 73+50
SHEET C-208


STA 73+50 TO 81+50
SHEET C-209

STA 81+50 TO 86+79
SHEET C-210

NEW PUMP STATION

NEW CHECK VALVE MANHOLE

INDIAN ROUTE 15



SALT LAKE CITY, UT



CONSTRUCTION
ISSUE



DILKON PASS
PIPELINE AND
PUMP STATION

REVISIONS

REV	DATE	DESCRIPTION

LINE IS 2 INCHES
AT FULL SIZE

DESIGNED: C. WILLMORE

DRAWN: T. PRIDEMORE

CHECKED: C. WILLMORE

CHECKED: - -

APPROVED: S. BRANCHLEY

FILENAME

C-200.dwg

BC PROJECT NUMBER

157520

CLIENT PROJECT NUMBER

CIVIL

KEY MAP

DRAWING NUMBER

C-200




17 SHEET NUMBER
OF 59

Call at least two full working days
before you begin excavation.

ARIZONA 811
Arizona Blue Stake, Inc.

Dial 8-1-1 or 1-800-STAKE-IT (782-5348)
In Maricopa County: (602) 263-1100

Path: C:\BCP\W\201\DWG FILENAME: C-201.DWG PLOT DATE: 2/24/2022 12:26 PM CAD USER: TYLER PRIDEMORE



PROFILE
SCALE H: 1" = 40'
V: 1" = 4'

GENERAL NOTES


- ALL LOCATIONS OF UTILITIES SHOWN ARE APPROXIMATE, CONTRACTOR TO FIELD VERIFY AND POT HOLE AS REQUIRED TO COMPLETE THE WORK.
- CONTRACTOR TO FIELD VERIFY PHYSICAL LOCATION, ELEVATIONS AND INVERTS. ELEVATIONS ARE BASED ON NAVD 88 EXPRESSED IN INTERNATIONAL FEET.
- CONTRACTOR TO PROVIDE THRUST BLOCKS AT ALL ELBOWS, TEES, CROSSES PER NTUA STD DWG WS-19. MECHANICAL JOINT RESTRAINTS CAN BE UTILIZED IN PLACE OF THRUST BLOCKS. EBA IRON MEGALUG SERIES 2000 PV FOR FITTINGS AND SERIES 2500 FOR PIPE JOINTS - INSTALL PER MANUFACTURE'S RECOMMENDATIONS.
- CONTRACTOR TO INSTALL PIPE IN TRENCH PER DETAIL C / SHEET C-003.
- CONTRACTOR TO INSTALL MARKER POSTS PER NTUA STD DWG WS-13.
- EASEMENT DIMENSIONS AND PIPELINE OFFSETS ARE PROVIDED ON DETAIL B / SHEET C-002.
- DEFLECT PIPE IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS AS NECESSARY.
- ALL YARD PIPING TO HAVE MJ x MJ DI FITTINGS UNLESS NOTED OR OTHERWISE SHOWN IN DETAILS.

KEY NOTES

- CAP EXISTING 6" WATERLINE EAST ONCE NEW 8" LINE AND PUMPHOUSE ARE APPROVED AND IN OPERATION.



SALT LAKE CITY, UT



CONSTRUCTION ISSUE



DILKON PASS PIPELINE AND PUMP STATION

REVISIONS

REV	DATE	DESCRIPTION

LINE IS 2 INCHES
AT FULL SIZE

DESIGNED: C. WILLMORE

DRAWN: T. PRIDEMORE

CHECKED: C. WILLMORE

CHECKED: --

APPROVED: S. BRANCHLEY

FILENAME

C-201.dwg

BC PROJECT NUMBER

157520

CLIENT PROJECT NUMBER

CIVIL

PLAN AND PROFILE - STA 10+00 TO 18+00

DRAWING NUMBER

C-201

18

SHEET NUMBER
OF


59

Call at least two full working days
before you begin excavation.


ARIZONA 811
Arizona Blue Stake, Inc.

Dial 8-1-1 or 1-800-STAKE-IT (782-5348)
In Maricopa County: (602) 263-1100

Path: C:\USERS\TPRIDEMORE\ONE\DRIVE - BROWN AND CALDWELL\DOCUMENTS\WORK\TEMP CAD\NAVAJO NATION\DILKON PASS\EXPORT FILENAME: C-202.DWG PLOT DATE: 2/23/2022 5:48 PM CAD USER: TYLER PRIDEMORE



STA 18+00 - STA 26+00
PLAN
0 40 80
SCALE IN FEET
NORTH




PROFILE
SCALE H: 1" = 40'
V: 1" = 4'

GENERAL NOTES

- ALL LOCATIONS OF UTILITIES SHOWN ARE APPROXIMATE, CONTRACTOR TO FIELD VERIFY AND POT HOLE AS REQUIRED TO COMPLETE THE WORK.
- CONTRACTOR TO FIELD VERIFY PHYSICAL LOCATION, ELEVATIONS AND INVERTS. ELEVATIONS ARE BASED ON NAVD 88 EXPRESSED IN INTERNATIONAL FEET.
- CONTRACTOR TO PROVIDE THRUST BLOCKS AT ALL ELBOWS, TEES, CROSSES PER NTUA STD DWG WS-19. MECHANICAL JOINT RESTRAINTS CAN BE UTILIZED IN PLACE OF THRUST BLOCKS. EBA IRON MEGALUG SERIES 2000 PV FOR FITTINGS AND SERIES 2500 FOR PIPE JOINTS - INSTALL PER MANUFACTURE'S RECOMMENDATIONS.
- CONTRACTOR TO INSTALL PIPE IN TRENCH PER DETAIL C / SHEET C-003.
- CONTRACTOR TO INSTALL MARKER POSTS PER NTUA STD DWG WS-13.
- EASEMENT DIMENSIONS AND PIPELINE OFFSETS ARE PROVIDED ON DETAIL B / SHEET C-002.
- DEFLECT PIPE IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS AS NECESSARY.
- ALL YARD PIPING TO HAVE MJ x MJ DI FITTINGS UNLESS NOTED OR OTHERWISE SHOWN IN DETAILS.



SALT LAKE CITY, UT



CONSTRUCTION
ISSUE



DILKON PASS
PIPELINE AND
PUMP STATION

REVISIONS

REV	DATE	DESCRIPTION

LINE IS 2 INCHES
AT FULL SIZE

DESIGNED: C. WILLMORE

DRAWN: T. PRIDEMORE

CHECKED: C. WILLMORE

CHECKED: - -

APPROVED: S. BRENCCHLEY

FILENAME

C-202.dwg

BC PROJECT NUMBER

157520

CLIENT PROJECT NUMBER

CIVIL

PLAN AND PROFILE
- STA 18+00 TO
26+00

DRAWING NUMBER




C-202

19 SHEET NUMBER
OF 59

Call at least two full working days
before you begin excavation.

ARIZONA 811
Arizona Blue Stake, Inc.

Dial 8-1-1 or 1-800-STAKE-IT (782-5348)
In Maricopa County: (602) 263-1100




PROFILE
SCALE H: 1" = 40'
V: 1" = 4'

GENERAL NOTES

1. ALL LOCATIONS OF UTILITIES SHOWN ARE APPROXIMATE, CONTRACTOR TO FIELD VERIFY AND POTHOLE AS REQUIRED TO COMPLETE THE WORK.
2. CONTRACTOR TO FIELD VERIFY PHYSICAL LOCATION, ELEVATIONS AND INVERTS. ELEVATIONS ARE BASED ON NAVD 88 EXPRESSED IN INTERNATIONAL FEET.
3. CONTRACTOR TO PROVIDE THRUST BLOCKS AT ALL ELBOWS, TEES, CROSSES PER NTUA STD DWG WS-19. MECHANICAL JOINT RESTRAINTS CAN BE UTILIZED IN PLACE OF THRUST BLOCKS. EBA IRON MEGALUG SERIES 2000 PV FOR FITTINGS AND SERIES 2500 FOR PIPE JOINTS - INSTALL PER MANUFACTURE'S RECOMMENDATIONS.
4. CONTRACTOR TO INSTALL PIPE IN TRENCH PER DETAIL C / SHEET C-003.
5. CONTRACTOR TO INSTALL MARKER POSTS PER NTUA STD DWG WS-13.
6. EASEMENT DIMENSIONS AND PIPELINE OFFSETS ARE PROVIDED ON DETAIL B / SHEET C-002.
7. DEFLECT PIPE IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS AS NECESSARY.
8. ALL YARD PIPING TO HAVE MJ x MJ DI FITTINGS UNLESS NOTED OR OTHERWISE SHOWN IN DETAILS.



SALT LAKE CITY, UT



CONSTRUCTION ISSUE



DILKON PASS PIPELINE AND PUMP STATION

REVISIONS

[illegible]

LINE IS 2 INCHES
AT FULL SIZE

DESIGNED: C. WILLMORE

DRAWN: T. PRIDEMORE

CHECKED: C. WILLMORE

CHECKED: - -

APPROVED: S. BRENCHLEY

FILENAME

C-203.dwg

BC PROJECT NUMBER
157520

137520
PROJECT NUMBER

CIVIL

PLAN AND PROFILE
- STA 26+00 TO
34+00

DRAWING NUMBER

C-203




20

SHEET NUMBER 59
OF

59

Path: C:\USERS\TPRIDE\MORE\ONE\DRIVE - BROWN AND CALDWELL\DOCUMENTS\WORK\TEMP CAD\NAVAJO NATION\DKLON PASS\EXPORT FILENAME: C-203.DWG PLOT DATE: 2/23/2022 5:48 PM CAD USER: TYLER PRIDE\MORE

Path: C:\USERS\TPRIDEMORE\ONE\DRIVE - BROWN AND CALDWELL\DOCUMENTS\WORK\TEMP CAD\NAVAJO NATION\DILKON PASS\EXPORT FILENAME: C-204.DWG PLOT DATE: 2/23/2022 5:48 PM CAD USER: TYLER PRIDEMORE



PROFILE
SCALE H: 1" = 40'
V: 1" = 4'

GENERAL NOTES

- ALL LOCATIONS OF UTILITIES SHOWN ARE APPROXIMATE, CONTRACTOR TO FIELD VERIFY AND POT HOLE AS REQUIRED TO COMPLETE THE WORK.
- CONTRACTOR TO FIELD VERIFY PHYSICAL LOCATION, ELEVATIONS AND INVERTS. ELEVATIONS ARE BASED ON NAVD 88 EXPRESSED IN INTERNATIONAL FEET.
- CONTRACTOR TO PROVIDE THRUST BLOCKS AT ALL ELBOWS, TEES, CROSSES PER NTUA STD DWG WS-19. MECHANICAL JOINT RESTRAINTS CAN BE UTILIZED IN PLACE OF THRUST BLOCKS. EBA IRON MEGALUG SERIES 2000 PV FOR FITTINGS AND SERIES 2500 FOR PIPE JOINTS - INSTALL PER MANUFACTURE'S RECOMMENDATIONS.
- CONTRACTOR TO INSTALL PIPE IN TRENCH PER DETAIL C / SHEET C-003.
- CONTRACTOR TO INSTALL MARKER POSTS PER NTUA STD DWG WS-13.
- EASEMENT DIMENSIONS AND PIPELINE OFFSETS ARE PROVIDED ON DETAIL B / SHEET C-002.
- DEFLECT PIPE IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS AS NECESSARY.
- ALL YARD PIPING TO HAVE MJ x MJ DI FITTINGS UNLESS NOTED OR OTHERWISE SHOWN IN DETAILS.



SALT LAKE CITY, UT



**CONSTRUCTION
ISSUE**



**DILKON PASS
PIPELINE AND
PUMP STATION**

REVISIONS

REV	DATE	DESCRIPTION

LINE IS 2 INCHES
AT FULL SIZE

DESIGNED: C. WILLMORE

DRAWN: T. PRIDEMORE

CHECKED: C. WILLMORE

CHECKED: - -

APPROVED: S. BRENCCHLEY

FILENAME

C-204.dwg

BC PROJECT NUMBER

157520

CLIENT PROJECT NUMBER

CIVIL

**PLAN AND PROFILE
- STA 34+00 TO
42+00**

DRAWING NUMBER

C-204


21 SHEET NUMBER
OF 59

Call at least two full working days
before you begin excavation.

ARIZONA 811
Arizona Blue Stake, Inc.


Dial 8-1-1 or 1-800-STAKE-IT (782-5348)
In Maricopa County: (602) 263-1100

Path: C:\USERS\TPRIDEMORE\ONE\DRIVE - BROWN AND CALDWELL\DOCUMENTS\WORK\TEMP CAD\NAVAJO NATION\DILKON PASS\EXPORT FILENAME: C-205.DWG PLOT DATE: 2/23/2022 5:49 PM CAD USER: TYLER PRIDEMORE



STA 42+00 - STA 49+45

PLAN



PROFILE


SCALE H: 1" = 40'
V: 1" = 4'

GENERAL NOTES

- ALL LOCATIONS OF UTILITIES SHOWN ARE APPROXIMATE, CONTRACTOR TO FIELD VERIFY AND POTHOLE AS REQUIRED TO COMPLETE THE WORK.
- CONTRACTOR TO FIELD VERIFY PHYSICAL LOCATION, ELEVATIONS AND INVERTS. ELEVATIONS ARE BASED ON NAVD 88 EXPRESSED IN INTERNATIONAL FEET.
- CONTRACTOR TO PROVIDE THRUST BLOCKS AT ALL ELBOWS, TEES, CROSSES PER NTUA STD DWG WS-19. MECHANICAL JOINT RESTRAINTS CAN BE UTILIZED IN PLACE OF THRUST BLOCKS. EBA IRON MEGALUG SERIES 2000 PV FOR FITTINGS AND SERIES 2500 FOR PIPE JOINTS - INSTALL PER MANUFACTURE'S RECOMMENDATIONS.
- CONTRACTOR TO INSTALL PIPE IN TRENCH PER DETAIL C / SHEET C-003.
- CONTRACTOR TO INSTALL MARKER POSTS PER NTUA STD DWG WS-13.
- EASEMENT DIMENSIONS AND PIPELINE OFFSETS ARE PROVIDED ON DETAIL B / SHEET C-002.
- DEFLECT PIPE IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS AS NECESSARY.
- ALL YARD PIPING TO HAVE MJ x MJ DI FITTINGS UNLESS NOTED OR OTHERWISE SHOWN IN DETAILS.



SALT LAKE CITY, UT



CONSTRUCTION ISSUE



DILKON PASS PIPELINE AND PUMP STATION

REVISIONS

REV	DATE	DESCRIPTION

LINE IS 2 INCHES
AT FULL SIZE

DESIGNED: C. WILLMORE

DRAWN: T. PRIDEMORE

CHECKED: C. WILLMORE

CHECKED: --

APPROVED: S. BRECHLEY

FILENAME

C-205.dwg

BC PROJECT NUMBER

157520

CLIENT PROJECT NUMBER

CIVIL

PLAN AND PROFILE - STA 42+00 TO 49+45

DRAWING NUMBER

C-205

22

SHEET NUMBER
OF


59

Call at least two full working days
before you begin excavation.


ARIZONA 811
Arizona Blue Stake, Inc.

Dial 8-1-1 or 1-800-STAKE-IT (782-5348)
In Maricopa County: (602) 263-1100

Path: C:\BCP\DWG FILENAME: C-206.DWG PLOT DATE: 2/24/2022 12:30 PM CAD USER: TYLER PRIDEMORE



STA 49+50 - STA 57+50
PLAN



PROFILE
SCALE H: 1" = 40'
V: 1" = 4'

GENERAL NOTES

- ALL LOCATIONS OF UTILITIES SHOWN ARE APPROXIMATE. CONTRACTOR TO FIELD VERIFY AND POTHOLE AS REQUIRED TO COMPLETE THE WORK.
- CONTRACTOR TO FIELD VERIFY PHYSICAL LOCATION, ELEVATIONS AND INVERTS. ELEVATIONS ARE BASED ON NAVD 88 EXPRESSED IN INTERNATIONAL FEET.
- CONTRACTOR TO PROVIDE THRUST BLOCKS AT ALL ELBOWS, TEES, CROSSES PER NTUA STD DWG WS-19. MECHANICAL JOINT RESTRAINTS CAN BE UTILIZED IN PLACE OF THRUST BLOCKS. EBA IRON MEGALUG SERIES 2000 PV FOR FITTINGS AND SERIES 2500 FOR PIPE JOINTS - INSTALL PER MANUFACTURE'S RECOMMENDATIONS.
- CONTRACTOR TO INSTALL PIPE IN TRENCH PER DETAIL C / SHEET C-003.
- CONTRACTOR TO INSTALL MARKER POSTS PER NTUA STD DWG WS-13.
- EASEMENT DIMENSIONS AND PIPELINE OFFSETS ARE PROVIDED ON DETAIL B / SHEET C-002.
- DEFLECT PIPE IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS AS NECESSARY.
- ALL YARD PIPING TO HAVE MJ x MJ DI FITTINGS UNLESS NOTED OR OTHERWISE SHOWN IN DETAILS.



SALT LAKE CITY, UT



CONSTRUCTION ISSUE



DILKON PASS PIPELINE AND PUMP STATION

REVISIONS

REV	DATE	DESCRIPTION

LINE IS 2 INCHES
AT FULL SIZE

DESIGNED: C. WILLMORE

DRAWN: T. PRIDEMORE

CHECKED: C. WILLMORE

CHECKED: --

APPROVED: S. BRENCLEY

FILENAME

C-206.dwg

BC PROJECT NUMBER

157520

CLIENT PROJECT NUMBER

CIVIL

PLAN AND PROFILE - STA 49+50 TO 57+50

DRAWING NUMBER

C-206


23 SHEET NUMBER
OF 59

Call at least two full working days
before you begin excavation.


ARIZONA811
Arizona Blue Stake, Inc.

Dial 8-1-1 or 1-800-STAKE-IT (782-5348)
In Maricopa County: (602) 263-1100

Path: C:\USERS\TPRIDEMORE\ONE\DRIVE - BROWN AND CALDWELL\DOCUMENTS\WORK\TEMP CAD\NAVAJO NATION\DILKON PASS\EXPORT FILENAME: C-207.DWG PLOT DATE: 2/23/2022 5:49 PM CAD USER: TYLER PRIDEMORE



STA 57+50 - STA 65+50
PLAN



PROFILE
SCALE H: 1" = 40'
V: 1" = 4'

GENERAL NOTES

- ALL LOCATIONS OF UTILITIES SHOWN ARE APPROXIMATE. CONTRACTOR TO FIELD VERIFY AND POT HOLE AS REQUIRED TO COMPLETE THE WORK.
- CONTRACTOR TO FIELD VERIFY PHYSICAL LOCATION, ELEVATIONS AND INVERTS. ELEVATIONS ARE BASED ON NAVD 88 EXPRESSED IN INTERNATIONAL FEET.
- CONTRACTOR TO PROVIDE THRUST BLOCKS AT ALL ELBOWS, TEES, CROSSES PER NTUA STD DWG WS-19. MECHANICAL JOINT RESTRAINTS CAN BE UTILIZED IN PLACE OF THRUST BLOCKS. EBA IRON MEGALUG SERIES 2000 PV FOR FITTINGS AND SERIES 2500 FOR PIPE JOINTS - INSTALL PER MANUFACTURE'S RECOMMENDATIONS.
- CONTRACTOR TO INSTALL PIPE IN TRENCH PER DETAIL C / SHEET C-003.
- CONTRACTOR TO INSTALL MARKER POSTS PER NTUA STD DWG WS-13.
- EASEMENT DIMENSIONS AND PIPELINE OFFSETS ARE PROVIDED ON DETAIL B / SHEET C-002.
- DEFLECT PIPE IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS AS NECESSARY.
- ALL YARD PIPING TO HAVE MJ x MJ DI FITTINGS UNLESS NOTED OR OTHERWISE SHOWN IN DETAILS.



SALT LAKE CITY, UT



CONSTRUCTION ISSUE



DILKON PASS PIPELINE AND PUMP STATION

REVISIONS

REV	DATE	DESCRIPTION

LINE IS 2 INCHES
AT FULL SIZE

DESIGNED: C. WILLMORE

DRAWN: T. PRIDEMORE

CHECKED: C. WILLMORE

CHECKED: - -

APPROVED: S. BRENCCHLEY

FILENAME

C-207.dwg

BC PROJECT NUMBER

157520

CLIENT PROJECT NUMBER

CIVIL

PLAN AND PROFILE - STA 57+50 TO 65+50

DRAWING NUMBER

C-207

24

SHEET NUMBER
OF


59

Call at least two full working days
before you begin excavation.


ARIZONA 811
Arizona Blue Stake, Inc.

Dial 8-1-1 or 1-800-STAKE-IT (782-5348)
In Maricopa County: (602) 263-1100

Path: C:\BCP\W\2024\4906 FILENAME: C-208.DWG PLOT DATE: 2/24/2022 12:34 PM CAD USER: TYLER PRIDEMORE



STA 65+50 - STA 73+50
PLAN



PROFILE
SCALE H: 1" = 40'
V: 1" = 4'

GENERAL NOTES

- ALL LOCATIONS OF UTILITIES SHOWN ARE APPROXIMATE. CONTRACTOR TO FIELD VERIFY AND POTHOLE AS REQUIRED TO COMPLETE THE WORK.
- CONTRACTOR TO FIELD VERIFY PHYSICAL LOCATION, ELEVATIONS AND INVERTS. ELEVATIONS ARE BASED ON NAVD 88 EXPRESSED IN INTERNATIONAL FEET.
- CONTRACTOR TO PROVIDE THRUST BLOCKS AT ALL ELBOWS, TEES, CROSSES PER NTUA STD DWG WS-19. MECHANICAL JOINT RESTRAINTS CAN BE UTILIZED IN PLACE OF THRUST BLOCKS. EBA IRON MEGALUG SERIES 2000 PV FOR FITTINGS AND SERIES 2500 FOR PIPE JOINTS - INSTALL PER MANUFACTURE'S RECOMMENDATIONS.
- CONTRACTOR TO INSTALL PIPE IN TRENCH PER DETAIL C / SHEET C-003.
- CONTRACTOR TO INSTALL MARKER POSTS PER NTUA STD DWG WS-13.
- EASEMENT DIMENSIONS AND PIPELINE OFFSETS ARE PROVIDED ON DETAIL B / SHEET C-002.
- DEFLECT PIPE IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS AS NECESSARY.
- ALL YARD PIPING TO HAVE MJ x MJ DI FITTINGS UNLESS NOTED OR OTHERWISE SHOWN IN DETAILS.



SALT LAKE CITY, UT



CONSTRUCTION ISSUE



DILKON PASS PIPELINE AND PUMP STATION

REVISIONS

REV	DATE	DESCRIPTION

LINE IS 2 INCHES
AT FULL SIZE

DESIGNED: C. WILLMORE

DRAWN: T. PRIDEMORE

CHECKED: C. WILLMORE

CHECKED: --

APPROVED: S. BRECHLEY

FILENAME

C-208.dwg

BC PROJECT NUMBER

157520

CLIENT PROJECT NUMBER

CIVIL

PLAN AND PROFILE - STA 65+50 TO 73+50

DRAWING NUMBER

C-208

25

SHEET NUMBER
OF


59

Call at least two full working days
before you begin excavation.


ARIZONA 811
Arizona Blue Stake, Inc.

Dial 8-1-1 or 1-800-STAKE-IT (782-5348)
In Maricopa County: (602) 263-1100

Path: C:\BPC\W\02344906 FILENAME: C-209.DWG PLOT DATE: 2/24/2022 12:40 PM CAD USER: TYLER PRIDEMORE



STA 73+50 - STA 81+50
PLAN



PROFILE
SCALE H: 1" = 40'
V: 1" = 4'

GENERAL NOTES

- ALL LOCATIONS OF UTILITIES SHOWN ARE APPROXIMATE, CONTRACTOR TO FIELD VERIFY AND POT HOLE AS REQUIRED TO COMPLETE THE WORK.
- CONTRACTOR TO FIELD VERIFY PHYSICAL LOCATION, ELEVATIONS AND INVERTS. ELEVATIONS ARE BASED ON NAVD 88 EXPRESSED IN INTERNATIONAL FEET.
- CONTRACTOR TO PROVIDE THRUST BLOCKS AT ALL ELBOWS, TEES, CROSSES PER NTUA STD DWG WS-19. MECHANICAL JOINT RESTRAINTS CAN BE UTILIZED IN PLACE OF THRUST BLOCKS. EBA IRON MEGALUG SERIES 2000 PV FOR FITTINGS AND SERIES 2500 FOR PIPE JOINTS - INSTALL PER MANUFACTURE'S RECOMMENDATIONS.
- CONTRACTOR TO INSTALL PIPE IN TRENCH PER DETAIL C / SHEET C-003.
- CONTRACTOR TO INSTALL MARKER POSTS PER NTUA STD DWG WS-13.
- EASEMENT DIMENSIONS AND PIPELINE OFFSETS ARE PROVIDED ON DETAIL B / SHEET C-002.
- DEFLECT PIPE IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS AS NECESSARY.
- ALL YARD PIPING TO HAVE MJ x MJ DI FITTINGS UNLESS NOTED OR OTHERWISE SHOWN IN DETAILS.



SALT LAKE CITY, UT



CONSTRUCTION ISSUE



DILKON PASS PIPELINE AND PUMP STATION

REVISIONS

REV	DATE	DESCRIPTION

LINE IS 2 INCHES
AT FULL SIZE

DESIGNED: C. WILLMORE
DRAWN: T. PRIDEMORE
CHECKED: C. WILLMORE
CHECKED: --
APPROVED: S. BRANCHLEY
FILENAME
C-209.dwg
BC PROJECT NUMBER
157520
CLIENT PROJECT NUMBER

CIVIL

PLAN AND PROFILE - STA 73+50 TO 81+50

DRAWING NUMBER
C-209


26 SHEET NUMBER
OF 59

Call at least two full working days
before you begin excavation.

ARIZONA 811
Arizona Blue Stake, Inc.


Dial 8-1-1 or 1-800-STAKE-IT (782-5348)
In Maricopa County: (602) 263-1100

Path: C:\BCP\W\2024\4906 FILENAME: C-210.DWG PLOT DATE: 2/24/2022 1:05 PM CAD USER: TYLER PRIDEMORE



STA 81+50 - STA 86+79

PLAN



PROFILE

SCALE H: 1" = 40'
V: 1" = 4'


GENERAL NOTES

- ALL LOCATIONS OF UTILITIES SHOWN ARE APPROXIMATE. CONTRACTOR TO FIELD VERIFY AND POTHOLE AS REQUIRED TO COMPLETE THE WORK.
- CONTRACTOR TO FIELD VERIFY PHYSICAL LOCATION, ELEVATIONS AND INVERTS. ELEVATIONS ARE BASED ON NAVD 88 EXPRESSED IN INTERNATIONAL FEET.
- CONTRACTOR TO PROVIDE THRUST BLOCKS AT ALL ELBOWS, TEES, CROSSES PER NTUA STD DWG WS-19. MECHANICAL JOINT RESTRAINTS CAN BE UTILIZED IN PLACE OF THRUST BLOCKS. EBA IRON MEGALUG SERIES 2000 PV FOR FITTINGS AND SERIES 2500 FOR PIPE JOINTS - INSTALL PER MANUFACTURE'S RECOMMENDATIONS.
- CONTRACTOR TO INSTALL PIPE IN TRENCH PER DETAIL C / SHEET C-003.
- CONTRACTOR TO INSTALL MARKER POSTS PER NTUA STD DWG WS-13.
- EASEMENT DIMENSIONS AND PIPELINE OFFSETS ARE PROVIDED ON DETAIL B / SHEET C-002.
- DEFLECT PIPE IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS AS NECESSARY.
- ALL YARD PIPING TO HAVE MJ x MJ DI FITTINGS UNLESS NOTED OR OTHERWISE SHOWN IN DETAILS.

KEY NOTES



SALT LAKE CITY, UT



CONSTRUCTION ISSUE



DILKON PASS PIPELINE AND PUMP STATION

REVISIONS

REV	DATE	DESCRIPTION

LINE IS 2 INCHES
AT FULL SIZE

DESIGNED: C. WILLMORE

DRAWN: T. PRIDEMORE

CHECKED: C. WILLMORE

CHECKED: --

APPROVED: S. BRENCCHLEY

FILENAME

C-210.dwg

BC PROJECT NUMBER

157520

CLIENT PROJECT NUMBER

CIVIL

PLAN AND PROFILE - STA 81+50 TO 89+79

DRAWING NUMBER

C-210




27 SHEET NUMBER
OF 59

Call at least two full working days
before you begin excavation.



Dial 8-1-1 or 1-800-STAKE-IT (782-5348)
In Maricopa County: (602) 263-1100

Path: C:\BCP\DWG FILENAME: C-211.DWG PLOT DATE: 3/8/2022 9:30 AM CAD USER: TYLER PRIDEMORE




PROFILE
SCALE H: 1" = 40'
V: 1" = 4'

GENERAL NOTES

- ALL LOCATIONS OF UTILITIES SHOWN ARE APPROXIMATE. CONTRACTOR TO FIELD VERIFY AND POTHOLE AS REQUIRED TO COMPLETE THE WORK.
- CONTRACTOR TO FIELD VERIFY PHYSICAL LOCATION, ELEVATIONS AND INVERTS. ELEVATIONS ARE BASED ON NAVD 88 EXPRESSED IN INTERNATIONAL FEET.
- CONTRACTOR TO PROVIDE THRUST BLOCKS AT ALL ELBOWS, TEES, CROSSES PER NTUA STD DWG WS-19. MECHANICAL JOINT RESTRAINTS CAN BE UTILIZED IN PLACE OF THRUST BLOCKS. EBA IRON MEGALUG SERIES 2000 PV FOR FITTINGS AND SERIES 2500 FOR PIPE JOINTS - INSTALL PER MANUFACTURE'S RECOMMENDATIONS.
- CONTRACTOR TO INSTALL PIPE IN TRENCH PER DETAIL C / SHEET C-003.
- CONTRACTOR TO INSTALL MARKER POSTS PER NTUA STD DWG WS-13.
- EASEMENT DIMENSIONS AND PIPELINE OFFSETS ARE PROVIDED ON SHEET C-002.
- DEFLECT PIPE IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS AS NECESSARY.
- ALL YARD PIPING TO HAVE MJ x MJ DI FITTINGS UNLESS NOTED OR OTHERWISE SHOWN IN DETAILS.



SALT LAKE CITY, UT



CONSTRUCTION ISSUE



DILKON PASS PIPELINE AND PUMP STATION

REVISIONS

REV	DATE	DESCRIPTION

LINE IS 2 INCHES
AT FULL SIZE

DESIGNED: WILLMORE

DRAWN: T. PRIDEMORE

CHECKED: C. WILLMORE

CHECKED: --

APPROVED: S. BRANCHLEY

FILENAME

C-211.dwg

BC PROJECT NUMBER

157520

CLIENT PROJECT NUMBER

CIVIL

PLAN AND PROFILE - COYOTE WASH

DRAWING NUMBER

C-211

28 SHEET NUMBER
OF 59

Call at least two full working days
before you begin excavation.

ARIZONA811
Arizona Blue Stake, Inc.



Dial 8-1-1 or 1-800-STAKE-IT (782-5348)
In Maricopa County: (602) 263-1100

Path: C:\USERS\TPRIDEMORE\ONE\DRIVE - BROWN AND CALDWELL\DOCUMENTS\WORK\TEMP. CAD\NAVAJO NATION\DILKON PASS\EXPORT FILENAME: M-003.DWG PLOT DATE: 2/23/2022 4:55 PM CAD USER: TYLER PRIDEMORE

PIPE PENETRATION NOTES:

- WHERE PIPES PASS THROUGH WALLS, FLOORS, OR CEILINGS, PENETRATIONS SHALL CONFORM TO TABLE, EXCEPT AS OTHERWISE SPECIFIED.
- IN TABLE, "TANK" SHALL MEAN ANY PART OF A STRUCTURE CONTAINING LIQUID, OR IN CONTACT WITH THE EARTH.
- IN TABLE, "PASSAGE" SHALL MEAN ANY ROOM, GALLERY, TUNNEL, OR SIMILAR ENCLOSURE.
- IN TABLE, WATER SURFACE "WS" SHALL MEAN AN ELEVATION 9-INCHES ABOVE MAXIMUM WATER SURFACE SHOWN.
- ALL STEEL SLEEVES SHALL BE HOT DIPPED GALVANIZED AFTER FABRICATION.
- IN CONDITION 5, PENETRATION TYPE E,H,J, OR K SHALL BE USED WHERE ONE SIDE IS DESIGNATED AS HAZARDOUS (CLASSIFIED), WHERE FLOODING IS POSSIBLE, OR WHERE SPECIFIED.
- SEAL FLANGES SHALL BE FACED AND DRILLED TO 150 POUND STANDARD. EACH JOINT SHALL BE FULL FACE GASKETED.
- WHERE SPECIFIED, CAST IRON FLANGES MAY BE INSTALLED FLUSH WITH WALL AND TAPPED FOR STUDS.
- PROVIDE CURB WHERE PENETRATING FLOOR, EXCEPT FOR PENETRATION TYPES A AND C. CURB SHALL BE 4" HIGH BY 3" WIDE.
- PROVIDE A MINIMUM OF 3" CLEARANCE BETWEEN REINFORCING STEEL AND FERROUS METAL PENETRATIONS.
- FLEXIBLE JOINTS SHALL BE PROVIDED FOR UNDERGROUND PIPING AS SPECIFIED.
- RESTRAINED FLEXIBLE COUPLINGS FOR STEEL PIPE SHALL BE DESIGNED FOR 100 PSI LINE PRESSURE IN ACCORDANCE WITH AWWA MANUAL M11, FIGURES 19.15 AND 19.16. AWWA MANUAL M11, TABLE 19.7 SHALL BE UTILIZED.
- UNLESS OTHERWISE SPECIFIED, INSULATION SHALL NOT EXTEND THROUGH SLEEVES. CHILLED WATER MUST PENETRATE WITH INSULATION.
- WHERE CAST IRON PIPE IS EMBEDDED IN CONCRETE AT AN EXPANSION JOINT, USE TYPE L PENETRATION.
- WEEP RINGS SHALL HAVE A MINIMUM DIAMETER 3-INCHES GREATER THAN THE OUTSIDE PIPE DIAMETER.
- "TANK SIDE OF WALL" SHALL MEAN SIDE OF WALL NORMALLY EXPOSED TO LIQUID, EARTH, OR OUTSIDE ATMOSPHERE.
- SEAL WITH MASTIC SEALANT WHERE WALL IS EXPOSED TO LIQUID, EARTH, OR A HAZARDOUS (CLASSIFIED) AREA.

PIPE PENETRATION TYPES					
CONDITION			TYPE		
	FROM	TO	STEEL PIPE	CAST IRON	PLASTIC PIPE
1	TANK	TANK BELOW W.S.	E, H OR K	E, F, G OR J	E
2	TANK	TANK ABOVE W.S.	D OR E	D OR E	D OR E
3	PASSAGE	TANK BELOW W.S.	E, H OR K	E, F, G OR J	E
4	PASSAGE	TANK ABOVE W.S.	A, C, D OR E	A, C, D OR E	A, C, D OR E
5	PASSAGE	PASSAGE	B OR C SEE NOTE 6	B OR C SEE NOTE 6	B OR C SEE NOTE 6
6	PASSAGE	OUTSIDE WALL	D OR E	D OR E	D OR E
7	PASSAGE	ROOF	AS SHOWN		
8	TANK	OUTSIDE WALL	E OR F	E, F OR G	E



TYPE II FLOOR DRAIN
TYPICAL
DETAIL (M4202)
NO SCALE



SALT LAKE CITY, UT



CONSTRUCTION
ISSUE



DILKON PASS
PIPELINE AND
PUMP STATION

REVISIONS

REV	DATE	DESCRIPTION

LINE IS 2 INCHES
AT FULL SIZE

DESIGNED: C. WILLMORE

DRAWN: T. PRIDEMORE

CHECKED: C. WILLMORE

CHECKED: - -

APPROVED: S. BRENCHLEY

FILENAME

M-003.dwg

BC PROJECT NUMBER

157520

CLIENT PROJECT NUMBER

PROCESS

STANDARD DETAILS

DRAWING NUMBER


M-001

29

SHEET NUMBER
OF

59

Path: C:\BOPM\02344910 FILENAME: M-100.DWG PLOT DATE: 3/4/2022 4:24 PM CAD USER: TYLER PRIDEMORE



PLAN
SCALE: 1/2" = 1'-0"

GENERAL NOTES


- BOOSTER STATION PIPING DIAMETER VARIES TO FACILITATE: 1) MATCHING MANIFOLD DIAMETER SIZE; 2) DESIGN FLOW OF BOOSTER STATION; 3) AND MAXIMUM ELECTROMAGNETIC METER VELOCITY LIMITS.

KEY NOTES

- 6" FLG X FLG DUCTILE IRON PIPE. PC-350 (TYP.)
- 3/4" HOSE BIB MIPT BRASS
- COATED STEEL PIPE SUPPORT W/ ADJUSTABLE NUT (TYP.)
- GRUNDFOS HYDRO MPC E 3CRE45-4
- SADDLE, 6" x 1" IPT
- SADDLE, 6" x 1" IPT, W/ 1" x 1/4" BUSHING
- GATE VALVE, 1" BRASS, FIPT
- STRAINER, 1" x 1" FIPT G.I.P.
- FRANKLIN ELECTRIC SINGLE PHASE 115/230 VOLTS 3/4 HP BOOSTER PUMP MODEL 5FBT07S4
- BOOSTER PUMP BRACKET
- UNION 1" SLIP SCH. 80 PVC
- WALLACE AND TIERNAN 300 99-C CHLORINE INJECTOR (10LB/DAY)
- COUPLING, 1" SLIP SCH. 80 PVC
- GAUGE GLYCER 1/4" O-350
- CHLORINE SCALE
- GAS CHLORINE CYLINDER
- PIPE 1" CUT AND THREADED TO FIT, G.I.P. (TYP.)
- ELBOW 90° 1" FIPT G.I.P.
- PIPE 1" CUT TO FIT SCH. 80 PVC (TYP.)
- BALL VALVE 1" SLIP SCH. 80 PVC
- 6" DUCTILE IRON FLG'D X PE SPOOL (TYP.)



SALT LAKE CITY, UT



CONSTRUCTION ISSUE



DILKON PASS PIPELINE AND PUMP STATION

REVISIONS

REV	DATE	DESCRIPTION

LINE IS 2 INCHES
AT FULL SIZE

DESIGNED: C.WILLMORE
DRAWN: T. PRIDEMORE
CHECKED: C.WILLMORE
CHECKED: ---
APPROVED: S. BRENCHELEY
FILENAME: M-100.dwg
BC PROJECT NUMBER: 157520
CLIENT PROJECT NUMBER

PROCESS


DILKON PASS PUMP STATION BUILDING PLAN

DRAWING NUMBER

M-100

30 SHEET NUMBER OF 59

Path: C:\BCP\W\023449\0 FILENAME: M-101.DWG PLOT DATE: 3/4/2022 4:40 PM CAD USER: TYLER PRIDEMORE



GENERAL NOTES


- BOOSTER STATION PIPING DIAMETER VARIES TO FACILITATE: 1) MATCHING MANIFOLD DIAMETER SIZE; 2) DESIGN FLOW OF BOOSTER STATION; 3) AND MAXIMUM ELECTROMAGNETIC METER VELOCITY LIMITS.

KEY NOTES

- 6" FLG X FLG DUCTILE IRON PIPE. PC-350 (TYP.)
- 3/4" HOSE BIB MIPT BRASS
- COATED STEEL PIPE SUPPORT W/ ADJUSTABLE NUT (TYP.)
- GRUNDFOS HYDRO MPC E 3CRE45-4
- SADDLE, 6" x 1" IPT
- SADDLE, 6" x 1" IPT, W/ 1" x 1/4" BUSHING
- GATE VALVE, 1" BRASS, FIPT
- STRAINER, 1" x 1" FIPT G.I.P.
- FRANKLIN ELECTRIC SINGLE PHASE 115/230 VOLTS 3/4 HP BOOSTER PUMP MODEL 5FBT07S4
- BOOSTER PUMP BRACKET
- UNION 1" SLIP SCH. 80 PVC
- WALLACE AND TIERNAN 300 99-C CHLORINE INJECTOR (10LB/DAY)
- COUPLING, 1" SLIP SCH. 80 PVC
- GAUGE GLYCER 1/4" 0-350
- CHLORINE SCALE
- GAS CHLORINE CYLINDER
- PIPE 1" CUT AND THREADED TO FIT, G.I.P. (TYP.)
- ELBOW 90° 1" FIPT G.I.P.
- PIPE 1" CUT TO FIT SCH. 80 PVC (TYP.)
- BALL VALVE 1" SLIP SCH. 80 PVC
- 6" DUCTILE IRON FLG'D X PE SPOOL (TYP.)
- 6" MUELLER LINESEAL III BUTTERFLY VALVE, FLANGED ENDS
- 6" EVOO4 ELECTROMAGNETIC METER
- SPOOL TO INCLUDE TAPPING BOSS FOR 3/4" HOSE BIB AND CAV VALVE AND PRESSURE TRANSDUCER
- 3/4" COMBINATION AIR/VACUUM VALVE, SEE SPECIFICATION 15150
- DIELECTRIC INSULATING JOINT AND FLANGE SPACER WITH BOLT ISOLATORS
- DIP MJ X MJ 90° BEND WITH THRUST BLOCK AND MEGALUG RESTRAINED JOINTS
- 6" FLG'D 90° DUCTILE IRON ELBOW
- 6" PVC PIPE, SEE SITE PLAN SHEET C-100
- 6" DI PIPE, PC 350 (WRAP IN TWO (2) LAYERS OF 8 MIL. POLYETHYTENE
- BUSHING, 1" x 3/4"
- (WRAP IN TWO (2) LAYERS OF 8 MIL. POLYETHYTENE
- NOZZLE EJECTOR
- UNION, 1" FIPT G.I.P.
- TAILWAY EJECTOR
- VALVE PRESSURE COCK 1/4" MIPT BRASS
- BUSHING 1" S X 1/4" FIPT SCH. 80 PVC
- TEE 1" SLIP SCH. 80 PVC
- ELBOW 90° 1" SLIP SCH. 80 PVC
- ADAPTER 1" S X MIPT SCH. 80 PVC
- PRESSURE REGULATOR
- BUSHING 1-1/4" X 1" G.I.P.
- BUSHING 1" S X 3/4" FIPT SCH. 80 PVC
- 1/2" PVC-SOLUTION TUBE
- TUBING
- 6" ROMAC STYLE 501 FLEXIBLE COUPLING
- 8" x 6" MJ x MJ REDUCER
- WICA C-10 PRESSURE TRANSDUCER
- 8" PVC PIPE, SEE SITE PLAN SHEET C-100



SALT LAKE CITY, UT



CONSTRUCTION ISSUE



DILKON PASS PIPELINE AND PUMP STATION

REVISIONS

REV	DATE	DESCRIPTION

LINE IS 2 INCHES
AT FULL SIZE

DESIGNED: C.WILLMORE

DRAWN: T. PRIDEMORE

CHECKED: C. WILLMORE

CHECKED: - -

APPROVED: S. BRENCHELY

FILENAME

M-101.dwg

BC PROJECT NUMBER

157520

CLIENT PROJECT NUMBER

PROCESS

DILKON PASS PUMP STATION BUILDING SECTION

DRAWING NUMBER

M-101

SHEET NUMBER
OF

31

59

[illegible]

Path: C:\BCPM\02344908 FILENAME: S-002.DWG PLOT DATE: 3/4/2022 4:29 PM CAD USER: THOMAS BOUFFARD

D

C

B

A

TABLE 1				
REQUIRED SPECIAL INSPECTIONS - STRUCTURAL SYSTEMS				
SYSTEM OR MATERIAL	REQUIRED INSPECTION	FREQUENCY OF INSPECTION		REMARKS
		CONTINUOUS	PERIODIC	
SOILS	VERIFY EXCAVATIONS ARE EXTENDED TO PROPER DEPTH AND HAVE REACHED PROPER MATERIAL		X	
	VERIFY SOIL MATERIALS BELOW FOOTINGS ARE ADEQUATE TO ACHIEVE DESIGN BEARING CAPACITY		X	
	PRIOR TO PLACEMENT OF COMPACTED FILL, OBSERVE SUBGRADE AND VERIFY THAT SITE HAS BEEN PREPARED PROPERLY		X	
	PERFORM CLASSIFICATION AND TESTING OF COMPACTED FILL MATERIALS		X	SEE TABLE 2
	VERIFY USE OF PROPER MATERIALS, DENSITIES AND LIFT THICKNESSES DURING PLACEMENT AND COMPACTION OF COMPACTED FILL	X		SEE TABLE 2
CONCRETE	INSPECT FORMWORK FOR LOCATION AND DIMENSIONS OF MEMBER BEING FORMED		X	
	VERIFY MATERIAL FOR REINFORCEMENT		X	CONTRACTOR TO SUBMIT CERTIFIED MILL TEST REPORTS
	REINFORCING STEEL PLACEMENT		X	
	INSPECT ANCHORS TO BE CAST IN CONCRETE		X	PRIOR TO AND DURING CONCRETE PLACEMENT
	INSPECT POST-INSTALLED CONCRETE ANCHORS: - HORIZONTAL AND UPWARDLY INCLINED ADHESIVE ANCHORS - OTHER ANCHORS UNLESS ICC REPORT REQUIRED CONTINUOUS INSPECTION	X	X	INSPECTION TO CONFORM TO IBC AND TO ANCHOR MANUFACTURER'S RECOMMENDATIONS AND ICC REPORTS
	VERIFY USE OF REQUIRED CONCRETE MIX DESIGN(S)		X	
	AT THE TIME FRESH CONCRETE IS SAMPLED TO FABRICATE SPECIMENS FOR STRENGTH TESTS, PERFORM SLUMP AND AIR CONTENT TESTS, AND TEMPERATURE OF CONCRETE	X		CONTINUOUS DURING PREPARATION OF SAMPLES
	CONCRETE PLACEMENT	X		
	INSPECTION FOR MAINTENANCE OF CURING PROCEDURES AND TEMPERATURE		X	VERIFY APPROPRIATE CURING METHOD HAS BEEN IMPLEMENTED AFTER EACH POUR
	VERIFY IN-SITU CONCRETE STRENGTH PRIOR TO REMOVAL OF SHORES AND FORMS FROM STRUCTURAL SLABS AND BEAMS		X	
	CEMENTITIOUS GROUTING OF BASE PLATES AND EPOXY GROUTING FOR EQUIPMENT MOUNTING	X		
STRUCTURAL STEEL	FABRICATION OF STRUCTURAL ELEMENTS			FABRICATOR SHALL BE APPROVED IN ACCORDANCE WITH IBC, CHAPTER 17 TO PERFORM WORK WITHOUT SPECIAL INSPECTION
	VERIFY MATERIAL OF ANCHOR BOLTS AND THREADED RODS		X	CONTRACTOR TO SUBMIT MANUFACTURER'S CERTIFIED TEST REPORTS
	VERIFY MATERIAL OF HIGH-STRENGTH BOLTS, NUTS AND WASHERS		X	CONTRACTOR TO SUBMIT MANUFACTURER'S CERTIFIED TEST REPORTS
	VERIFY MATERIAL FOR STRUCTURAL STEEL SHAPES, PLATES, BARS, ETC.		X	CONTRACTOR TO SUBMIT CERTIFIED MILL TEST REPORTS
	VERIFY MATERIALS FOR WELD FILLER MATERIALS		X	
	VERIFY WELDER QUALIFICATIONS		X	CONTRACTOR TO SUBMIT WELDERS CERTIFICATES
	VERIFY USE OF PROPER WELDING PROCEDURES		X	
	INSPECT COMPLETE AND PARTIAL-PENETRATION GROOVE WELDS, MULTI-PASS FILLET WELDS, AND SINGLE-PASS FILLET WELDS GREATER THAN 5/16"	X		
	INSPECT SINGLE-PASS FILLET WELDS LESS THAN OR EQUAL TO 5/16"		X	VISUALLY INSPECT ALL WELDS
	INSPECT HIGH-STRENGTH BEARING-TYPE BOLTED CONNECTIONS		X	
	VERIFY TYPE, DEPTH AND GAGE OF DECKING		X	

TABLE 1				
REQUIRED SPECIAL INSPECTIONS - STRUCTURAL SYSTEMS				
SYSTEM OR MATERIAL	REQUIRED INSPECTION	FREQUENCY OF INSPECTION		REMARKS
		CONTINUOUS	PERIODIC	
	INSPECT INSTALLATION (ATTACHMENT) OF DECKING		X	
	INSPECT FRAME TO VERIFY THAT BRACING, STIFFENERS, MEMBER LOCATIONS AND JOINT DETAILS COMPLY WITH APPROVED CONSTRUCTION DRAWINGS		X	
MASONRY	VERIFY PROPORTIONS OF SITE -PREPARED MORTAR AND GROUT		X	AT START OF MASONRY CONSTRUCTION
	VERIFY SPECIFIED TYPE, GRADE AND SIZE OF REINFORCEMENT		X	CONTRACTOR TO SUBMIT CERTIFIED MILL TEST REPORTS
	VERIFY MATERIALS FOR MASONRY UNITS, MORTAR, GROUT, ANCHORS, TIES AND ACCESSORIES		X	CONTRACTOR TO SUBMIT MANUFACTURER'S CERTIFIED COMPLIANCE REPORTS
	VERIFY TYPE, SIZE, LOCATION AND INSTALLATION OF EMBEDDED CONNECTORS AND ANCHORS		X	
	VERIFY SIZE AND LOCATION OF STRUCTURAL ELEMENTS		X	
	VERIFY TYPE, SIZE AND LOCATION OF ANCHORAGE OF MASONRY TO OTHER CONSTRUCTION		X	
	VERIFY PROTECTION PROVISIONS FOR COLD AND HOT WEATHER MASONRY CONSTRUCTION		X	
	PLACEMENT OF MASONRY UNITS AND CONSTRUCTION OF MORTAR JOINTS		X	
	REINFORCING STEEL PLACEMENT		X	
	VERIFY GROUT SPACE IS CLEAN		X	
	VERIFY PROPORTIONS OF GROUT; USE OF REQUIRED GROUT MIX DESIGN		X	
	OBSERVE GROUT PLACEMENT	X		
	OBSERVE PREPARATION OF ANY GROUT OR MORTAR SPECIMENS AND/OR PRISMS	X		CONTINUOUS DURING PREPARATION OF SAMPLES

QUALITY ASSURANCE NOTES

1. THE QUALITY OF THE WORKMANSHIP AND THE QUALITY OF THE MATERIALS OF CONSTRUCTION ARE GOVERNED BY THE INTERNATIONAL BUILDING CODE, 2015 EDITION (IBC).
2. ALL NEW STRUCTURES AND MODIFICATIONS TO EXISTING STRUCTURES TO BE CONSTRUCTED AS A PART OF THIS PROJECT ARE CLASSIFIED AS RISK CATEGORY III IN ACCORDANCE WITH THE IBC. THE STRUCTURES ARE CLASSIFIED AS SEISMIC DESIGN CATEGORY B.
3. TO ASSURE THE QUALITY OF THE CONSTRUCTION OF THIS PROJECT, STRUCTURAL TESTS, SPECIAL INSPECTION AND STRUCTURAL OBSERVATION WILL BE PERFORMED IN ACCORDANCE WITH IBC, CHAPTER 17.
4. WHERE FREQUENCY OF INSPECTION IS SPECIFIED TO BE CONTINUOUS, THE SPECIAL INSPECTOR IS EXPECTED TO BE PRESENT IN THE AREA WHERE THE WORK IS BEING PERFORMED AND PROVIDING FULL-TIME OBSERVATION OF THE WORK REQUIRING SPECIAL INSPECTION.
5. WHERE FREQUENCY OF INSPECTION IS SPECIFIED TO BE PERIODIC, THE SPECIAL INSPECTOR IS EXPECTED TO BE PRESENT IN THE AREA WHERE THE WORK HAS BEEN OR IS BEING PERFORMED AND AT THE COMPLETION OF THE WORK (PRIOR TO THE NEXT CONSTRUCTION TASK).
6. SPECIAL INSPECTIONS ARE IN ADDITION TO INSPECTIONS BY THE BUILDING OFFICIALS. CONSTRUCTION IS SUBJECT TO INSPECTION BY THE BUILDING OFFICIAL. COORDINATE WITH BUILDING DEPARTMENT TO DETERMINE REQUIRED INSPECTIONS.
7. CONTRACTOR SHALL PROVIDE ACCESS TO THE WORK FOR REQUIRED INSPECTIONS. CONTRACTOR SHALL PROVIDE NOTIFICATION IN ADVANCE OF REQUIRED INSPECTIONS, TESTING AND STRUCTURAL OBSERVATIONS.



SALT LAKE CITY, UT



CONSTRUCTION
ISSUE



DILKON PASS
PIPELINE AND
PUMP STATION

REVISIONS

REV	DATE	DESCRIPTION

LINE IS 2 INCHES
AT FULL SIZE

DESIGNED: S. BELLIS
DRAWN: T. BOUFFARD
CHECKED: J. HARPER
CHECKED:
APPROVED: C. WILLMORE
FILENAME S-002.dwg
BC PROJECT NUMBER 157520
CLIENT PROJECT NUMBER

STRUCTURAL

SPECIAL
INSPECTIONS 1

DRAWING NUMBER	
S-002	
33	SHEET NUMBER OF 59

D

C

- B

A

Path: C:\BCPW\WD2344908 FILENAME: S-003.DWG PLOT DATE: 3/4/2022 4:34 PM CAD USER: THOMAS BOUFFARD

- 1

TENSION DEVELOPMENT AND LAP SPLICE LENGTHS (IN INCHES) FOR UNCOATED BARS IN NORMAL-WEIGHT CONCRETE WITH $f_c' = 4,000$ PSI OR HIGHER

BAR SIZE	APPLICATION	CONCRETE COVER = 1.50 IN.			CONCRETE COVER = 2.00 IN.			CONCRETE COVER = 3.00 IN.		
		TOP	OTHER	MIN C/C SPACING	TOP	OTHER	MIN C/C SPACING	TOP	OTHER	MIN C/C SPACING
#3	DEVELOPMENT LAP SPLICE	12 16	12 16	3.50 3.75	12 16	12 16	4.50 4.75	12 16	12 16	6.50 6.75
#4	DEVELOPMENT LAP SPLICE	15 20	12 16	3.50 4.00	15 20	12 16	4.50 5.00	15 20	12 16	6.50 7.00
#5	DEVELOPMENT LAP SPLICE	19 24	15 19	3.75 4.25	19 24	15 19	4.75 5.25	19 24	15 19	6.75 7.25
#6	DEVELOPMENT LAP SPLICE	22 29	17 22	3.75 4.50	22 29	17 22	4.75 5.50	22 29	17 22	6.75 7.50
#7	DEVELOPMENT LAP SPLICE	37 48	28 37	4.00 4.75	33 42	25 33	5.00 5.75	33 42	25 33	7.00 7.75
#8	DEVELOPMENT LAP SPLICE	47 60	36 47	4.00 5.00	37 48	29 37	5.00 6.00	37 48	29 37	7.00 8.00

1. TABULATED VALUES ARE BASED ON GRADE 60 REINFORCING BARS AND NORMAL-WEIGHT CONCRETE.
2. TENSION DEVELOPMENT LENGTHS AND TENSION LAP SPlice LENGTHS ARE CALCULATED PER ACI 318-14, SECTIONS 25.4.2.3 AND 25.5, RESPECTIVELY.
3. LAP SPlice LENGTHS ARE LAP CLASS B = $1.3 l_d$ (ACI 318-14, SECTION 25.5.2).
4. TOP BARS ARE HORIZONTAL BARS WITH MORE THAN 12 IN. OF FRESH CONCRETE CAST BELOW THE BARS. NOTE THAT IN ADDITION TO TOP BARS IN BEAMS AND SLABS, ALL HORIZONTAL BARS IN WALLS ARE CONSIDERED TO BE TOP BARS.



C



A

LINE IS 2 INCHES
AT FULL SIZE

DRAWN: T. BOUFFA

CHECKED:

FILENAME

1575

[illegible]

SPECIAL INSPECTIONS 2



S-003

34

SHEET NUMBER
OF

59


Path: C:\BOPM\02344908 FILENAME: S-004.DWG PLOT DATE: 3/4/2022 1:23 PM CAD USER: THOMAS BOUFFARD




NOTES:

- THIS DETAIL APPLIES TO UP TO 8'-0" MAXIMUM DIMENSION FOR RECTANGULAR OPENINGS AND UP TO 8'-0" DIAMETER FOR CIRCULAR OPENINGS.
- AT OPENINGS 12" OR LESS, NO ADDITIONAL #5 DIAGONAL REINFORCING IS REQUIRED UNLESS NOTED OTHERWISE. REINFORCING SHALL BE OFFSET, STILL MAINTAINING REQUIRED SPACING, TO ALLOW FOR OPENING WHERE PRACTICAL, OR CUT AT THE OPENING AND ADDITIONAL REINFORCING ADDED PER NOTE 5.
- OPENINGS ARE NOT ALL SHOWN ON STRUCTURAL DRAWINGS. PROVIDE OPENINGS IN ACCORDANCE WITH ARCHITECTURAL, MECHANICAL AND OTHER CONTRACT DRAWINGS.
- ADDITIONAL REINFORCEMENT MAY BE OMITTED ONLY WHERE OPENING IS FRAMED BY BEAMS OR WALLS.
- ADDITIONAL REINFORCING (4) SIDES OF OPENING EQUAL TO NUMBER AND SIZE OF DISCONTINUOUS REINFORCING. WHERE AN ODD NUMBER OF REBAR ARE DISCONTINUOUS, PROVIDE (ODD NO. +1)/2 EACH SIDE OF OPENING.

S0101 NTS
ADDITIONAL REINFORCING AT OPENINGS



S0102 NTS
COMBINED OPENING TRIM BARS



MINIMUM EMBEDMENT LENGTH, L		
DIAMETER	EXPANSION ANCHOR	ADHESIVE ANCHOR
3/8"	3 1/2"	4 1/2"
1/2"	4 3/4"	6"
5/8"	5 1/2"	7 1/2"
3/4"	6 1/2"	9"
7/8"	-	10 1/2"
1"	-	12"

S0103 NTS
CONCRETE ANCHORS

- OPENINGS IN CONCRETE WHICH ARE CLOSER TO ONE ANOTHER THAN THE DIAMETER OR SHORTER SIDE OF THE LARGER OF THE TWO ARE CONSIDERED TO FORM A COMBINED OPENING.
- THESE DIAGRAMS ARE FOR COMBINED OPENINGS WHOSE LARGER DIMENSION DOES NOT EXCEED 3'-0". SEE DRAWINGS FOR OPENINGS LARGER THAN 3'-0".
- TRIM BAR EXTENSION PAST EDGES OF COMBINED OPENINGS SHALL BE 1'-0" FOR #4 BARS, 1'-6" FOR #5 BARS, AND ONE DEVELOPMENT LENGTH FOR LARGER BARS.
- DISPLACE PRINCIPAL REINFORCEMENT TO EACH SIDE OF COMBINED OPENING OR PLACE BETWEEN INDIVIDUAL OPENINGS. DO NOT CUT PRINCIPAL REINFORCEMENT.
- SEE DETAIL S0101 FOR TRIM BARS FOR INDIVIDUAL OPENINGS.
- SUBMIT SPECIAL SITUATIONS TO ENGINEER FOR REVIEW.

TRIM BAR REQUIREMENTS:

- A IF THE COMBINED OPENING IS SMALLER THAN 1'-0", PROVIDE (1) #5 EACH FACE BETWEEN OPENINGS.
- B IF THE LARGER DIMENSION OF A COMBINED OPENING EXCEEDS 1'-0" BUT THE SMALLER DIMENSION IS LESS THAN OR EQUAL TO 8", AND PROVIDED THE COMBINED OPENING IS ALIGNED WITH THE PRINCIPAL REINFORCEMENT, PROVIDE (1) #5 EACH FACE BETWEEN OPENINGS.
- C WHERE INDIVIDUAL OPENINGS OF A COMBINED OPENING FORM TWO OR MORE ROWS, THE ROWS SHALL BE SEPARATED BY AT LEAST 8" OF CONCRETE. PROVIDE (2) #5 EACH FACE BETWEEN ROWS OF OPENINGS, (1) #5 EACH FACE BETWEEN OPENINGS IN THE PERPENDICULAR DIRECTION, AND (1) #5 EACH FACE AROUND THE PERIMETER OF COMBINED OPENINGS. PROVIDE STANDARD HOOKS WHERE BARS TERMINATE WITHIN THE COMBINED OPENING.
- D

NOTES:

- MINIMUM EMBEDMENT LENGTH PER SCHEDULE UNLESS INDICATED OTHERWISE ON DRAWINGS.
- CONFORM TO ICC EVALUATION SERVICE REPORT (ES REPORT) REQUIREMENTS AND MANUFACTURER'S RECOMMENDATIONS FOR INSTALLATION.
- EXPANSION ANCHORS AND THREADED RODS SHALL BE TYPE 316 STAINLESS STEEL MATERIAL UNLESS INDICATED OTHERWISE ON THE DRAWINGS.
- HOLE DIAMETER SHALL BE IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS.



SALT LAKE CITY, UT



CONSTRUCTION ISSUE



DILKON PASS
PIPELINE AND
PUMP STATION

REVISIONS

REV	DATE	DESCRIPTION

LINE IS 2 INCHES
AT FULL SIZE

DESIGNED: S. BELLIS
DRAWN: T. BOUFFARD
CHECKED: J. HARPER
CHECKED:
APPROVED: C. WILLMORE
FILENAME
S-004.dwg
BC PROJECT NUMBER
157520
CLIENT PROJECT NUMBER


STRUCTURAL

STANDARD DETAILS
1


DRAWING NUMBER
S-004

35 SHEET NUMBER
OF 59

Path: C:\BCPM\02344908 FILENAME: S-006.DWG PLOT DATE: 3/4/2022 1:23 PM CAD USER: THOMAS BOUFFARD




TYPE A



TYPE E

EQUIPMENT PAD DIMENSIONS											
AB DIA (IN.)	1/2	5/8	3/4	7/8	1	1 1/4	1 3/8	1 1/2	1 3/4	2	
MIN PAD HT (IN.)	7 1/2	9 1/2	11	12 1/2	14	17 1/2	19	20 1/2	24	27	
MIN AB EDGE DISTANCE	4 1/2	4 1/2	4 1/2	5 1/4	6	7 1/2	8 1/4	9	10 1/2	12	


S0301
EQUIPMENT PADS
NTS



NOMINAL BEAM DEPTH, INCHES	ROWS OF BOLTS	BOLT DIA	DOUBLE ANGLE, LENGTH	COMMENTS
8-10	2	3/4"	0'-5 1/2"	-

- NOTES:
- UNLESS OTHERWISE NOTED, NUMBER OF ROWS IS EQUAL TO NUMBER OF BOLTS TO ENCLOSE BEAM WEB.
 - ALL BEAM FRAMING CONNECTIONS SHALL CONFORM TO THIS DETAIL UNLESS SPECIFICALLY NOTED OTHERWISE OR APPROVED IN WRITING BY THE ENGINEER.
 - FOR NOMINAL BEAM DEPTHS LESS THAN 8", EXTEND LONG LEG OF DOUBLE ANGLE ALONG BEAM WEB AND PROVIDE ADDITIONAL BOLT TO ENCLOSE BEAM WEB AS SHOWN.
 - PROVIDE ADDITIONAL 1 1/2" LENGTH TO DOUBLE ANGLE FOR STAGGERED BOLT CONNECTIONS WHERE REQUIRED. DIMENSION SHALL BE 3" UNLESS OTHERWISE REQUIRED FOR PROPER FABRICATION.

S0303
TYPICAL BEAM CONNECTION
NTS



SINGLE MAT REINFORCING

- NOTES:
- UNLESS NOTED OTHERWISE, SIZE AND SPACING OF CORNER OR INTERSECTION REINFORCING SHALL MATCH HORIZONTAL REINFORCING SHOWN IN SPECIFIC SECTIONS OR DETAILS. VERTICAL REINFORCING NOT SHOWN FOR CLARITY.
 - UNLESS NOTED OTHERWISE, BAR SPLICE SHALL BE LOCATED OUTSIDE OF CORNER OR INTERSECTION AREA TO AVOID CONGESTION. CONTRACTORS OPTION TO PROVIDE SINGLE BENT BAR IN LIEU OF SPLICE CONFIGURATION AT ONE END ONLY.
 - SEE GENERAL STRUCTURAL NOTES FOR SPLICE LENGTH. HORIZONTAL WALL BARS SHALL BE CONSIDERED TOP BARS FOR DEVELOPMENT AND SPLICE LENGTHS.

S0302
TYPICAL HORIZONTAL WALL REINFORCING
NTS



SALT LAKE CITY, UT



CONSTRUCTION
ISSUE



DILKON PASS
PIPELINE AND
PUMP STATION

REVISIONS

REV	DATE	DESCRIPTION

LINE IS 2 INCHES
AT FULL SIZE

DESIGNED: S. BELLIS
DRAWN: T. BOUFFARD
CHECKED: J. HARPER
CHECKED:
APPROVED: C. WILLMORE
FILENAME
S-006.dwg
BC PROJECT NUMBER
157520
CLIENT PROJECT NUMBER

STRUCTURAL


STANDARD DETAILS
3

DRAWING NUMBER
S-006

37 SHEET NUMBER
OF 59

Path: C:\BCPM\02344908 FILENAME: S-100.DWG PLOT DATE: 3/4/2022 1:23 PM CAD USER: THOMAS BOUFFARD

PLAN
NORTH



1

2

28'-8"

CL VENT

5'-2"

5'-8"

2'-8"

2'-0"

10'-0"

7'-0"

2'-0"

TYP (S0202)

MASONRY
CONTROL JOINT,
(S0205)

1
S-102

B

12'-0"

CL PIPE

2'-7 1/2"

CL FD

3'-4 1/2"

CL VENT

2'-8"

EDGE OF FOOTING

1'-6" TYP

CL PIPE

1'-6"

SLOPE

SLOPE

CL FD

FD

SLOPE

SLOPE

CL FD

FD

SLOPE

SLOPE

CL FD

FD

SLOPE

SLOPE

CL FD

FD

SLOPE

SLOPE

CL FD

FD

SLOPE

SLOPE

CL FD

FD

SLOPE

SLOPE

CL FD

FD

SLOPE

SLOPE

CL FD

FD

SLOPE

SLOPE

CL FD

FD

SLOPE

SLOPE

CL FD

FD

SLOPE

SLOPE

CL FD

FD

SLOPE

SLOPE

CL FD

FD

SLOPE

SLOPE

CL FD

FD

SLOPE

SLOPE

CL FD

FD

SLOPE

SLOPE

CL FD

FD

SLOPE

SLOPE

CL FD

FD

SLOPE

SLOPE

CL FD

FD

SLOPE

SLOPE

CL FD

FD

SLOPE

SLOPE

CL FD

FD

SLOPE

SLOPE

CL FD

FD

SLOPE

SLOPE

CL FD

FD

SLOPE

SLOPE

CL FD

FD

SLOPE

SLOPE

CL FD

FD

SLOPE

SLOPE

CL FD

FD

SLOPE

SLOPE

CL FD

FD

SLOPE

SLOPE

CL FD

FD

SLOPE

SLOPE

CL FD

FD

SLOPE

SLOPE

CL FD

FD

SLOPE

SLOPE

CL FD

FD

SLOPE

SLOPE

CL FD

FD

SLOPE

SLOPE

CL FD

FD

SLOPE

SLOPE

CL FD

FD

SLOPE

SLOPE

CL FD

FD

SLOPE

SLOPE

CL FD

FD

SLOPE

SLOPE

CL FD

FD

SLOPE

SLOPE

CL FD

FD

SLOPE

SLOPE

CL FD

FD

SLOPE

SLOPE

CL FD

FD

SLOPE

SLOPE

CL FD

FD

SLOPE

SLOPE

CL FD

FD

SLOPE

SLOPE

CL FD

FD

SLOPE

SLOPE

CL FD

FD

SLOPE

SLOPE

CL FD

FD

SLOPE

SLOPE

CL FD

FD

SLOPE

SLOPE

CL FD

FD

SLOPE

SLOPE

CL FD

FD

SLOPE

SLOPE

CL FD

FD

SLOPE

SLOPE

CL FD

FD

SLOPE

SLOPE

CL FD

FD

SLOPE

SLOPE

CL FD

FD

SLOPE

SLOPE

CL FD

FD

SLOPE

SLOPE

CL FD

FD

SLOPE

SLOPE

CL FD

FD

SLOPE

SLOPE

CL FD

FD

SLOPE

SLOPE

CL FD

FD

SLOPE

SLOPE

CL FD

FD

SLOPE

SLOPE

CL FD

FD

SLOPE

SLOPE

CL FD

FD

SLOPE

SLOPE

CL FD

FD

SLOPE

SLOPE

CL FD

FD

SLOPE

SLOPE

CL FD

FD

SLOPE

SLOPE

CL FD

FD

SLOPE

SLOPE

CL FD

FD

SLOPE

SLOPE

CL FD

FD

SLOPE

SLOPE

CL FD

FD

SLOPE

SLOPE

CL FD

FD

SLOPE

SLOPE

CL FD

FD

SLOPE

SLOPE

CL FD

FD

SLOPE

SLOPE

CL FD

FD

SLOPE

SLOPE

CL FD

FD

SLOPE

SLOPE

CL FD

FD

SLOPE

SLOPE

CL FD

FD

SLOPE

SLOPE

CL FD

FD

SLOPE

SLOPE

CL FD

FD

SLOPE

SLOPE

CL FD

FD

SLOPE

SLOPE

CL FD

FD

SLOPE

SLOPE

CL FD


FD

SLOPE

SLOPE

Path: C:\BCP\W\02344908 FILENAME: S-101.DWG PLOT DATE: 3/4/2022 1:23 PM CAD USER: THOMAS BOUFFARD

PLAN
NORTH



1

2


1'-0" 6'-4" 6'-0" 28'-8" 6'-0" 6'-4" 1'-0"

B

1'-0" 12'-0"


A

2'-0"



C
S-102

C8x11.5




1
S-102

C8x11.5


SLOPE

W8x13, TYP

C8x11.5



B
S-102



A
S-102

EDGE OF ROOF DECKING

SLOPE CMU WALL
TO MATCH ROOF PITCH,
SEE DETAIL (S0204) TYP

ROOF DECK TO BE 1 1/2" VERO TYPE "PLB-36" 20
GA METAL DECK OR APPROVED EQUAL. FASTEN
DECK WITH HILTI X-ENP-19L15 AT 12" OC AT
PERIMETER AND INTERIOR SUPPORTS AND
PUNCHLOCK VSC2 AT 12" OC AT SIDE LAPS, (2)
SPAN MINIMUM.

(S0303) SIM
AT CORNERS PROVIDE
SINGLE ANGLE ONLY

CMU WALL LINTEL BELOW,
TYP. SEE DETAIL (S0203)

PLAN

SCALE: 1/2" = 1'-0"

GENERAL NOTES

1. SEE CIVIL FOR BUILDING COORDINATES.
2. SEE ARCHITECTURAL, ELECTRICAL, AND MECHANICAL DRAWINGS FOR ADDITIONAL INFORMATION.
3. COORDINATE ALL OPENINGS WITH ARCHITECTURAL, ELECTRICAL, AND MECHANICAL DRAWINGS.
4. COORDINATE SIZE AND LOCATION OF ELEC/MECH PADS WITH APPROVED EQUIPMENT SUBMITTALS AND ELECTRICAL AND MECHANICAL DRAWINGS.



SALT LAKE CITY, UT



CONSTRUCTION ISSUE



DILKON PASS PIPELINE AND PUMP STATION

REVISIONS

REV	DATE	DESCRIPTION

LINE IS 2 INCHES
AT FULL SIZE

DESIGNED: S. BELLIS

DRAWN: T. BOUFFARD

CHECKED: J. HARPER

CHECKED:

APPROVED: C. WILLMORE

FILENAME

S-101.dwg

BC PROJECT NUMBER

157520

CLIENT PROJECT NUMBER

STRUCTURAL

DILKON PASS PUMP STATION BUILDING ROOF FRAMING PLANS

DRAWING NUMBER


S-101

39 SHEET NUMBER
OF 59


Path: C:\USERS\KWOESSNER\DDTG CLOUD SYNC FOLDER\BUSINESS DEVELOPMENT\DLKON2-DD (CURRENT)\DRAWINGS\DLKON PASS PUMP STATION_A_BASE.DWG PLOT DATE: 3/14/2022 9:25 AM CAD USER: KATIE WOESSNER

BUILDING CODE ANALYSIS

AHJ	NAVAJO NATION (STRUCTURAL DESIGN CRITERIA: NAVAJO COUNTY)	
BUILDING CODES	2015 INTERNATIONAL BUILDING CODE 2015 INTERNATIONAL MECHANICAL CODE 2015 INTERNATIONAL FUEL GAS CODE 2015 INTERNATIONAL PLUMBING CODE 2015 INTERNATIONAL ENERGY CONSERVATION CODE 2017 NATIONAL ELECTRICAL CODE 2012 INTERNATIONAL FIRE CODE	FIRE EXTINGUISHERS IBC 906.3.1: FIRE EXTINGUISHERS PROVIDED PER IBC TABLE 906.3(1), MIN. KEY BOXES IFC 506.1: KEY BOXES PER UL 1037 IS WILL BE PROVIDED IN LOCATIONS APPROVED BY THE FIRE CODE OFFICIAL ACCESSIBILITY OCCUPANCY GROUP F-2: EXEMPT FROM ACCESSIBILITY REQUIREMENTS PER IBC 1103.2.9 EGRESS DISTANCE TO EXITS: (TABLE 1014.3) F-2 75 FT MAXIMUM, WITHOUT SPRINKLER SYSTEM OCCUPANCY LOADS: (TABLE 1004.1.2) F-2 OCCUPANCY 220 SF / 300 (MECHANICAL EQUIPMENT ROOM) = 1 EXITS REQUIRED EXITS = 1 ACUAL EXITS = 1
OCCUPANCY	F-2 LOW HAZARD	
CONSTRUCTION TYPE	TYPE II-B	
ALLOWABLE AREAS	23,000 SF / 3 STORIES / 55 FT	
ACTUAL AREAS	220 SF / 1 STORY / 11'-6" FT	



1 CODE PLAN
A102 SCALE: 1/4" = 1'-0"



2 FLOOR PLAN
A102 SCALE: 3/8" = 1'-0"

CHEMICAL TABLE																	
CHEMICAL				HAZARD						MAX ALLOWABLE QUANTITY PER CONTROL AREA					NFPA 704 IDENTIFICATION		
NAME	CAS NUMBER	OTHER NAME	FORMULA	TYPE	CLASSIFICATION	STATE	SOLUTION STRENGTH	ACTUAL AMOUNT	CONTAINER	BASIC	SPRINKLERED BUILDING OR CABINETS	SPRINKLERED BUILDING AND CABINETS	OCCUPANCY	HEALTH	FIRE	REACTIVITY	SPECIFIC
CHLORINE	7782-50-5	---	Cl-	PHYSICAL	GAS-LIQUEFIED	GAS	100%	150 LBS	500 GAL	500 LBS	1,000 LBS	2,000 LBS	F-2	3	0	0	OX
				HEALTH	CORROSIVE												

- KEY NOTES
- 1 8" CMU WALL, WATER REPELLENT FULL EXTENT
 - 2 HM DOOR AND FRAME, PAINT, RE: DOOR SCHEDULE
 - 3 EQUIPMENT, RE: MECH
 - 4 CONCRETE PAD, RE: CIVIL
 - 5 FIRE EXTINGUISHER
 - 6 INLINE EXHAUST FAN, MOTORIZED DAMPER, AND LOUVER, RE: MECH
 - 7 5' LONG CONCRETE SPLASHBLOCK
 - 8 ELECTRICAL EQUIPMENT, RE: ELEC
 - 9 FLOOR DRAIN, RE: MECH



SALT LAKE CITY, UT



CONSTRUCTION ISSUE



DILKON PASS PIPELINE AND PUMP STATION

REVISIONS

REV	DATE	DESCRIPTION

LINE IS 2 INCHES AT FULL SIZE

DESIGNED: K. WOESSNER
DRAWN: K. WOESSNER
CHECKED: G. SHORT
CHECKED: ---
APPROVED: G. SHORT

FILENAME
DILKON PUMP STATION_A_BASE
BC PROJECT NUMBER
157520
CLIENT PROJECT NUMBER
00357.21


ARCH

CODE & FLOOR PLAN

DRAWING NUMBER
A-101

41 SHEET NUMBER OF 59

Path: C:\USERS\KWOESSNER\DDTG CLOUD SYNC FOLDER\BUSINESS DEVELOPMENT\DILKON\2-DD (CURRENT)\DRAWINGS\DILKON PASS PUMP STATION_A_BASE.DWG FILENAME: DILKON PASS PUMP STATION_A_BASE.DWG PLOT DATE: 3/4/2022 9:19 AM CAD USER: KATIE WOESSNER



- KEY NOTES**
- 1 STANDING SEAM METAL ROOF PANEL
 - 2 GUTTER - PRE-FINISHED SHEET METAL
 - 3 FASCIA - PRE-FINISHED SHEET METAL
 - 4 DOWNSPOUT - PRE-FINISHED SHEET METAL
 - 5 SNOWGUARD



SALT LAKE CITY, UT



CONSTRUCTION
ISSUE



DILKON PASS
PIPELINE AND
PUMP STATION

REVISIONS

REV	DATE	DESCRIPTION

LINE IS 2 INCHES
AT FULL SIZE

DESIGNED: K. WOESSNER

DRAWN: K. WOESSNER

CHECKED: G. SHORT

CHECKED: ---

APPROVED: G. SHORT

FILENAME

DILKON PASS PUMP STATION_A_BASE

BC PROJECT NUMBER

157520

CLIENT PROJECT NUMBER

00357.21

ARCH

ROOF PLAN

DRAWING NUMBER


A-102

42


SHEET NUMBER
OF

59


Path: C:\USERS\KWOESSNER\DDTG CLOUD SYNC FOLDER\BUSINESS DEVELOPMENT\DLKON2-DD (CURRENT)\DRAWINGS\DLKON PASS PUMP STATION_A_BASE.DWG PLOT DATE: 3/14/2022 9:20 AM CAD USER: KATIE WOESSNER




1 NORTH ELEVATION
A201 3/8"=1'-0"



2 EAST ELEVATION
A201 3/8"=1'-0"



3 SOUTH ELEVATION
A201 3/8"=1'-0"




4 WEST ELEVATION
A201 3/8"=1'-0"

KEY NOTES

- 8" CMU WALL, SMOOTH FACE, WATER REPELLENT FULL EXTENT, COLOR A
- HM DOOR AND FRAME, PAINT, RE: DOOR SCHEDULE
- STANDING SEAM METAL ROOF OVER METAL DECK
- GUTTER - PRE-FINISHED SHEET METAL
- FASCIA - PRE-FINISHED SHEET METAL
- DOWNSPOUT - PRE-FINISHED SHEET METAL
- CONCRETE CURB, RE: STRUCT
- INLINE EXHAUST FAN, MOTORIZED DAMPER, AND LOUVER, RE: MECH
- CONCRETE SPLASHBLOCK
- 8" CMU WALL, SPLIT FACE, WATER REPELLENT FULL EXTENT, COLOR B
- SNOWGUARD
- EXTERIOR LIGHTING, RE: ELEC
- ELECTRICAL EQUIPMENT, RE: ELEC



SALT LAKE CITY, UT



CONSTRUCTION
ISSUE



DILKON PASS
PIPELINE AND
PUMP STATION

REVISIONS

REV	DATE	DESCRIPTION

LINE IS 2 INCHES
AT FULL SIZE

DESIGNED: K. WOESSNER

DRAWN: K. WOESSNER

CHECKED: G. SHORT

CHECKED: ---

APPROVED: G. SHORT

FILENAME

DILKON PUMP STATION_A_BASE

BC PROJECT NUMBER

157520

CLIENT PROJECT NUMBER

00357.21

ARCH

BUILDING
ELEVATIONS

DRAWING NUMBER


A-201

43

SHEET NUMBER
OF

59

Path: C:\USERS\KWOESSNER\DDTG CLOUD SYNC FOLDER\BUSINESS DEVELOPMENT\DLKON2-DD (CURRENT)\DRAWINGS\DLKON PASS PUMP STATION_2022.3.3 FILENAME: DLKON PUMP STATION_A_BASE.DWG PLOT DATE: 3/14/2022 9:20 AM CAD USER: KATIE WOESSNER



- KEY NOTES
- 1 8" CMU WALL, WATER REPELLENT FULL EXTENT
 - 2 CONCRETE FOUNDATION, RE: STRUCT
 - 3 CONCRETE PAD, RE: CIVIL
 - 4 HM DOOR AND FRAME, PAINT, RE: DOOR SCHEDULE
 - 5 STANDING SEAM METAL ROOF ON 2 LAYERS 30# BUILDING FELT OVER SELF-ADHERING UNDERLAYMENT, 4" NAILBASE INSULATION, AND METAL FRAMING
 - 6 GUTTER - PRE-FINISHED SHEET METAL
 - 7 FASCIA - PRE-FINISHED SHEET METAL
 - 8 SOFFIT - PRE-FINISHED SHEET METAL
 - 9 INLINE EXHAUST FAN, MOTORIZED DAMPER, AND LOUVER, RE: MECH



SALT LAKE CITY, UT



CONSTRUCTION
ISSUE



DILKON PASS
PIPELINE AND
PUMP STATION

REVISIONS

REV	DATE	DESCRIPTION

LINE IS 2 INCHES
AT FULL SIZE

DESIGNED: K. WOESSNER
DRAWN: K. WOESSNER
CHECKED: G. SHORT
CHECKED: ---
APPROVED: G. SHORT

FILENAME
DLKON PUMP STATION_A_BASE
BC PROJECT NUMBER
157520
CLIENT PROJECT NUMBER
00357.21
ARCH

BUILDING SECTIONS


DRAWING NUMBER
A-202

44 SHEET NUMBER
OF 59


Path: C:\USERS\KWOESSNER\DDTG_CLOUD_SYNC_FOLDER\BUSINESS_DEVELOPMENT\DLKON2-DD (CURRENT)\DRAWINGS\DLKON PASS PUMP STATION_2022.3.3 FILENAME: DLKON PUMP STATION_A_BASE.DWG PLOT DATE: 3/14/2022 9:20 AM CAD USER: KATIE WOESSNER

DOOR SCHEDULE		DOOR SCHEDULE NOTES:												
DOORS		GEN.					FRAMES							
DOOR NO.	TYPE	DIMENSIONS			MATERIAL	FINISH	HDWRE	TYPE	DETAILS			MATERIAL	FINISH	REMARKS / RATING
		W	H	TH					SILL	HEAD	JAMB			
1	A	3'-0"	7'-2"	1-3/4"	HM	PAINT	1	1	3/A301	1/A301	2/A301	HM	PAINT	---
2	B	6'-4"	7'-2"	1-3/4"	HM	PAINT	2	2	3/A301	1/A301	2/A301	HM	PAINT	---


- CLEAR INSULATING GLASS:
- OVERALL UNIT THICKNESS: 1 INCH
 - MINIMUM THICKNESS OF EACH GLASS LITE: 6 MM
 - OUTDOOR LITE: FULLY TEMPERED FLOAT GLASS
 - INTERSPACE CONTENT: AIR
 - INDOOR LITE: FULLY TEMPERED FLOAT GLASS
 - SAFETY GLAZING REQUIRED



DOOR ELEVATIONS
1/2"=1'-0"




FRAME ELEVATION
1/2"=1'-0"




WALL DETAIL AT EAVE
1-1/2"=1'-0"

WALL DETAIL AT RAKE
1-1/2"=1'-0"




WALL DETAIL AT INTERIOR
1-1/2"=1'-0"




DOOR HEAD DETAIL
1-1/2"=1'-0"


DOOR JAMB DETAIL
1-1/2"=1'-0"



DOOR SILL DETAIL
1-1/2"=1'-0"



LOUVER HEAD/SILL DETAIL
1-1/2"=1'-0"



LOUVER JAMB DETAIL
1-1/2"=1'-0"



SALT LAKE CITY, UT



CONSTRUCTION
ISSUE



DILKON PASS
PIPELINE AND
PUMP STATION

REVISIONS

REV	DATE	DESCRIPTION

LINE IS 2 INCHES
AT FULL SIZE

DESIGNED: K. WOESSNER

DRAWN: K. WOESSNER

CHECKED: G. SHORT

CHECKED: ---

APPROVED: G. SHORT

FILENAME

DILKON PUMP STATION_A_BASE

BC PROJECT NUMBER

157520

CLIENT PROJECT NUMBER

00357.21

ARCH

DOOR SCHEDULE
AND DETAILS

DRAWING NUMBER

A-301



45 SHEET NUMBER
OF 59

C

B

A

DESCRIPTION (TYP)

INST
 LINE 45
 LINE 46

SELECTOR SWITCH:
3 POSITION
X = CLOSED CONTACT
O = OPEN CONTACT

K

KEY INTERLOCK

2. NOT ALL SYMBOLS OR ABBREVIATIONS SHOWN ON DRAWINGS E-001 AND E-002 ARE USED IN SUBSEQUENT DRAWINGS.



CONSTRUCTION ISSUE



DILKON PASS PIPELINE AND PUMP STATION

REVISIONS

[illegible]

LINE IS 2 INCHES
AT FULL SIZE

DESIGNED: K. CHANDLER

DRAWN: D. EHMA

CHECKED: H. PAGE

CHECKED: ---

APPROVED: S. BRENCHIE

FILENAME

E-002.dwg

BC PROJECT NUMBER
157588

137320
CLIENT PROJECT

1. *Journal of the American Medical Association*, 2000; 284: 2689-2695.

ELECTRIC,





CONTROL AND ONE-LINE DIAGRAM LEGENDS AND SYMBOLS

DRAWING NUMBER




E-002

47


NUMBER



Path: C:\USERS\DEHMANN\PCP\WD2344918 FILENAME: E-004.DWG PLOT DATE: 2/25/2022 1:51 PM CAD USER: DANIEL EHMANN



DOUBLE MAT REINFORCEMENT



SINGLE MAT REINFORCEMENT

NOTES

- OD = OUTSIDE DIAMETER OF CONDUIT.
- \"S\" = CLEAR SPACE BETWEEN REINFORCING.
- MAXIMUM OD = T/4 OR S - 1/2\".
- PLACE CONDUIT UNDER SLAB AND ENCASE IN CONCRETE WHERE OD GREATER THAN T/4 OR S - 1/2\".
- PROVIDE PVC OR PVC COATED CONDUITS WHERE IN CONTACT WITH REINFORCING.

EMBEDDED RACEWAYS SLAB ON GRADE DETAIL (E2202) SCALE: NONE



SALT LAKE CITY, UT



CONSTRUCTION ISSUE



DILKON PASS PIPELINE AND PUMP STATION

REVISIONS

REV	DATE	DESCRIPTION

LINE IS 2 INCHES
AT FULL SIZE

DESIGNED: K. CHANDLER
DRAWN: D. EHMANN
CHECKED: H. PACE
CHECKED: ---
APPROVED: S. BRENCHELY
FILENAME
E-004.dwg
BC PROJECT NUMBER
157520
CLIENT PROJECT NUMBER

ELECTRICAL

STANDARD DETAILS 2

DRAWING NUMBER






E-004

49

SHEET NUMBER
OF

59

Path: C:\USERS\DEHMAN\PCP\DWID2344918 FILENAME: E-005.DWG PLOT DATE: 2/25/2022 1:51 PM CAD USER: DANIEL EHMANN



SALT LAKE CITY, UT



CONSTRUCTION
ISSUE



DILKON PASS
PIPELINE AND
PUMP STATION


REVISIONS		
REV	DATE	DESCRIPTION
LINE IS 2 INCHES AT FULL SIZE		
DESIGNED: K. CHANDLER		
DRAWN: D. EHMANN		
CHECKED: H. PACE		
CHECKED: ---		
APPROVED: S. BRENCHLEY		
FILENAME E-005.dwg		
BC PROJECT NUMBER 157520		
CLIENT PROJECT NUMBER		

ELECTRICAL

STANDARD DETAILS
3

DRAWING NUMBER
E-005
SHEET NUMBER
50 OF 59


Path: C:\USERS\DEHMANN\PCP\WD2344918 FILENAME: E-100.DWG PLOT DATE: 3/28/2022 1:07 PM CAD USER: DANIEL EHMANN



PLAN
SCALE: 3/32" = 1'-0"



PLAN
NORTH



GENERAL NOTES


1. PROVIDE ELECTRICAL, INSTRUMENTATION, AND TELEMETRY SYSTEM.
2. POWER UTILITY: NAVAJO TRIBAL UTILITY AUTHORITY (NTUA), (928) 729-5721.

KEY NOTES

1. UNDERGROUND CIRCUITS PER DRAWING E-102, POWER UTILITY REQUIREMENTS TO PREVAIL.
2. PROVIDE SERVICE ENTRANCE SECTION METER, ARRESTOR ON OUTSIDE OF BUILDING.
3. FIBER OPTIC CIRCUIT SC-1.
4. EXISTING OVERHEAD SERVICE LINE AND POWER POLE.
5. PROVIDE SLACK ENCLOSURE AND 100 FOOT CABLE ON POLE. CARLON SLK12 OR EQUAL. TERMINATION OF FIBERS AT EXISTING POWERLINE/FO CABLE ROUTE BY NTUA, REFER TO DRAWING C-100.
6. FIBER OPTIC PULLBOX



SALT LAKE CITY, UT



CONSTRUCTION ISSUE



DILKON PASS PIPELINE AND PUMP STATION

REVISIONS

REV	DATE	DESCRIPTION

LINE IS 2 INCHES
AT FULL SIZE

DESIGNED: K. CHANDLER

DRAWN: D. EHMANN

CHECKED: H. PACE

CHECKED: ---

APPROVED: S. BRENCHEY

FILENAME

E-100.dwg

BC PROJECT NUMBER

157520

CLIENT PROJECT NUMBER

ELECTRICAL

DILKON PASS PUMP STATION SITE PLAN

DRAWING NUMBER

E-100

SHEET NUMBER
OF

52



59

Call at least two full working days
before you begin excavation.

ARIZONA 811
Arizona Blue Stake, Inc.


Dial 8-1-1 or 1-800-STAKE-IT (782-5348)
In Maricopa County: (602) 263-1100

Path: C:\USERS\DEHMANN\PC\WD2344918 FILENAME: E-101.DWG PLOT DATE: 3/3/2022 2:30 PM CAD USER: DANIEL EHMANN



ELECTRICAL
PLAN

SCALE: 1/2" = 1'-0"



DILKON PASS PUMP STATION

LOAD SUMMARY AT 480 VAC

LOAD DESCRIPTION	KVA	HP	480 VAC FLA
BOOSTER PUMP 1 VFD		25	34
BOOSTER PUMP 2 VFD		25	34
BOOSTER PUMP 3 VFD (STANDBY)		25	
TRANSFORMER FOR PANEL-A	15		31.3
SUBTOTAL:	15	75	99.3
PLUS 25%:			9
AMPERE TOTAL:			107.8

LUMINAIRE SCHEDULE

TYPE	DESCRIPTION	MODEL #
A1 1/25	LITHONIA WST LED - SURFACE MOUNT, RUGGED DIE-CAST ALUMINUM HOUSING, ACRYLIC LENS, HIGH-EFFECIENCY LED'S, ZERO UPLIGHT, NIGHTTIME FRIENDLY, IP65 RATED, CONSISTENT WITH LEED AND GREEN GLOBE CRITERIA FOR ELIMINATING WASTEFUL UPLIGHT, 120VAC	LITHONIA WST LED P2 3000 50K VF MVOLT DDBTXD
A2 1/31	LITHONIA FEM LED - SURFACE MOUNT, FIBERGLASS HOUSING, REPLACEABLE DIFFUSER LENS, HIGH-EFFICIENCY LED'S, 4000K TEMPERATURE STANDARD, CSA CERTIFIED TO UL AND C-UL STANDARDS, 120VAC	LITHONIA FEM L48 4000LM LPAFL MD MVOLT GZ10 40K 80CRI
EM1 1/3	LITHONIA ELM2 LED - SURFACE MOUNT, THERMOPLASTIC HOUSING, POLYCARBONATE LENS, LED SYSTEM, 90 MINUTE EMERGENCY LAMP CAPACITY, NICKEL CADMIUM BATTERY, MEETS UL 924, NFPA 101, NEC AND OSHA ILLUMINATION STANDARDS, 120VAC	LITHONIA ELM2 LED HO
EM2 1/1	LITHONIA LQM - SURFACE MOUNT, THERMOPLASTIC HOUSING, LED SYSTEM, 90 MINUTE EMERGENCY LAMP CAPACITY, NICKEL CADMIUM BATTERY, MEETS UL 924, NFPA 101, NEC AND OSHA ILLUMINATION STANDARDS, 120VAC	LITHONIA LQM S W 3 R 120/277 EL N

GENERAL NOTES


- GENERAL REQUIREMENTS: SPECIFICATION 16000.
- TESTING: SPECIFICATION 16030.
- ARC FLASH HAZARD ANALYSIS AND LABELING: SPECIFICATION 16431.
- CIRCUITS: DRAWING E-102.
- SCHEDULE AND COORDINATE WORK TO MINIMIZE WATER SYSTEM CONTROL OUTAGES. REFER TO SPECIFICATION 01014 AND 17900.
- SUBMIT ELECTRICAL EQUIPMENT LAYOUT PRIOR TO CONDUIT ROUGH-IN.

KEY NOTES

- SERVICE ENTRANCE SECTION
- MAIN DISCONNECT SWITCH
- PUMP MANAGEMENT UNIT
- PUMP 1
- PUMP 2
- PUMP 3
- SUCTION LEVEL SWITCH
- DISCHARGE PRESSURE SWITCH
- LOAD CENTER DISCONNECT SWITCH
- FLOW METER
- FLOW INDICATOR
- TELEMETRY PLC
- TRANSFORMER AND LOAD CENTER
- TELEMETRY ANTENNA ON 2" x 20'-0" PIPE, ANCHORED TO BUILDING. ALIGN TO DILKON PASS TANK SITE. PROVIDE ANTENNA CABLE IN CONDUIT. PROVIDE CGB FITTING AND EXPOSE LOOP OF CABLE FOR FINAL CONNECTION TO ANTENNA. MAKE PENETRATION TO BUILDING WATER TIGHT.
- HEATER
- FLOW AMI UNIT
- FAN, DRAWING H-101
- MOTORIZED DAMPER
- DOOR SWITCH
- THERMOSTAT
- CHLORINE LEAK DETECTOR. LOCATE SENSOR BELOW AT HEIGHT PER MANUFACTURER. MOUNT BEACON ABOVE.
- AIR TEMPERATURE SENSOR/SWITCH
- SUCTION PRESSURE TRANSDUCER
- DISCHARGE PRESSURE TRANSDUCER
- CHLORINATOR CONTROLLER
- SCADA NETWORK CABINET



SALT LAKE CITY, UT



CONSTRUCTION
ISSUE



DILKON PASS
PIPELINE AND
PUMP STATION

REVISIONS

REV	DATE	DESCRIPTION

LINE IS 2 INCHES
AT FULL SIZE

DESIGNED: K. CHANDLER

DRAWN: D. EHMANN

CHECKED: H. PACE

CHECKED: ---

APPROVED: S. BRENCHEY

FILENAME

E-101.dwg

BC PROJECT NUMBER

157520

CLIENT PROJECT NUMBER

ELECTRICAL

DILKON PASS PUMP
STATION PLAN

DRAWING NUMBER

E-101

52

SHEET NUMBER
OF



59

Path: C:\USERS\DEHMANN\PCPWD\2344918 FILENAME: E-110.DWG PLOT DATE: 2/25/2022 1:51 PM CAD USER: DANIEL EHMANN



DILKON PASS TANK
PLAN
SCALE: 1" = 100'-0"

0 50 100 200
SCALE: 1" = 100'-0"



CONTROL ONE-LINE DIAGRAM
DETAIL
SCALE: NONE

GENERAL NOTES


1. REPLACE TELEMETRY PLC.
2. GENERAL REQUIREMENTS: SPECIFICATION 16000.
3. TESTING: SPECIFICATION 16030.
4. SCHEDULE AND COORDINATE WORK TO MINIMIZE WATER SYSTEM CONTROL OUTAGES. REFER TO SPECIFICATION 01014 AND 17900.

KEY NOTES

1. EXISTING PANEL
2. EXISTING OVERHEAD SERVICE LINE AND POWER POLE.
3. EXISTING TANK LEVEL (PRESSURE) TRANSDUCER IN VAULT.
4. REPLACE TELEMETRY PLC
5. RETAIN EXISTING ANTENNA AND TRANSMISSION LINE
6. PROVIDE PER NTUA - TECHNICAL PROVISIONS 4.0 FOR MOTOR CONTROL CENTER AND TANK CONTROL PANEL - AC TANK PANEL.
7. PROVIDE 10 FOOT COPPER GROUND ROD DRIVEN IN EARTH. PROVIDE #6 BOND TO EXISTING GROUND SYSTEM.



SALT LAKE CITY, UT



CONSTRUCTION
ISSUE



DILKON PASS
PIPELINE AND
PUMP STATION

REVISIONS

REV	DATE	DESCRIPTION

LINE IS 2 INCHES
AT FULL SIZE

DESIGNED: K. CHANDLER

DRAWN: D. EHMANN

CHECKED: H. PACE

CHECKED: ---

APPROVED: S. BRENCHEY

FILENAME

E-110.dwg

BC PROJECT NUMBER

157520

CLIENT PROJECT NUMBER

ELECTRICAL

DILKON PASS
STORAGE TANK
SITE PLAN

DRAWING NUMBER

E-110

SHEET NUMBER
OF

54


59

Call at least two full working days
before you begin excavation.

ARIZONA 811
Arizona Blue Stake, Inc.

Dial 8-1-1 or 1-800-STAKE-IT (782-5348)
In Maricopa County: (602) 263-1100

Path: C:\USERS\DEHMANN\BPC\WD2344920 FILENAME: I-001.DWG PLOT DATE: 2/25/2022 1:26 PM CAD USER: DANIEL EHMANN



GENERAL NOTES


1. LOWER GREASEWOOD TANK PROVIDES WATER FOR THE WOOD CHOP AND DILKON WATER SYSTEM.
2. PROVIDE REPLACEMENT DILKON PASS PUMP STATION AT LOCATION SOUTH OF THE EXISTING. BOOSTER FILLS DILKON PASS TANK.
3. PROVIDE REPLACEMENT PLC FOR THE DILKON PASS TANK.
4. SCHEDULE AND COORDINATE WORK TO MINIMIZE WATER SYSTEM CONTROL OUTAGES. REFER TO SPECIFICATION 01014 AND 17900.

KEY NOTES

1. REPLACE PUMP STATION AND TELEMETRY.
2. REPLACE TELEMETRY PLC.
3. SCADA SWITCH AND FIBER OPTIC SWITCH.
4. FIBER OPTIC CABLE AND CONNECTION TO EXISTING FIBER OPTIC LOOP BY NTUA.



SALT LAKE CITY, UT



CONSTRUCTION ISSUE



DILKON PASS PIPELINE AND PUMP STATION

REVISIONS

REV	DATE	DESCRIPTION

LINE IS 2 INCHES AT FULL SIZE

DESIGNED: K. CHANDLER

DRAWN: D. EHMANN

CHECKED: H. PACE

CHECKED: ---

APPROVED: S. BRENCHELEY

FILENAME

I-001.dwg

BC PROJECT NUMBER

157520

CLIENT PROJECT NUMBER

INSTRUMENTATION

DILKON PASS COMMUNICATIONS BLOCK DIAGRAM

DRAWING NUMBER














































I-001

55

SHEET NUMBER OF

59

Path: P:\2021\21161 DILKON PASS BPS & PIPELINE\DRAWINGS FILENAME: M 21161 DILKON PASS BPS & PIPELINE.DWG PLOT DATE: 3/2/2022 5:12 PM CAD USER: ETHAN RIGBY

MECHANICAL LEGEND					
SYMBOL	ABR.	DESCRIPTION	SYMBOL	ABR.	DESCRIPTION
GENERAL TERMINOLOGY			AIR SIDE		WET SIDE
	A2	DETAIL NUMBER DESIGNATION CORRESPONDING WITH GRID LOCATION			EXISTING AIR DUCT TO BE REMOVED
					EXISTING AIR DUCT TO REMAIN
	MA 1	MECHANICAL EQUIPMENT DESIGNATION EQUIPMENT ITEM DESIGNATION			NEW AIR DUCT
					NEW SPIRAL DUCT
	D-1 CFM	REGISTER, GRILL OR DIFFUSER DESIGNATION WITH BALANCING CFM LISTED BELOW			NEW MEDIUM PRESSURE DUCT
					BURIED OR UNDER FLOOR DUCT
	R-1	GRILLE, OR LOUVER DESIGNATION WHERE BALANCING NOT REQUIRE			FLEXIBLE AIR DUCT
					LINED DUCT
		REVISION DESIGNATOR AND NUMBER			VANED ELBOW
					RADIUS ELBOW
	POC	POINT OF CONNECTION			FLEXIBLE AIR DUCT CONNECTION
	POR	POINT OF REMOVAL			VOLUME DAMPER
	GC	GENERAL CONTRACTOR			SUPPLY AIR DIFFUSER
	MC	MECHANICAL CONTRACTOR			RETURN AIR, FRESH AIR, AND TRANSFER AIR
	ATC	CONTROL CONTRACTOR			CEILING MOUNTED EXHAUST FAN OR EXHAUST GRILLE
	EC	ELECTRICAL CONTRACTOR			RETURN OR OUTSIDE AIR DUCT UP
	FPC	FIRE PROTECTION CONTROL			SUPPLY DUCT UP
	NIC	NOT IN CONTRACT			EXHAUST AIR INTAKE UP
	NTS	NOT TO SCALE			RETURN OR OUTSIDE AIR DUCT DOWN
	C	COMMON			SUPPLY DUCT DOWN
	NC	NORMALLY CLOSED			EXHAUST DUCT DOWN
	NO	NORMALLY OPEN			ROUND DUCT UP
		ROUND DUCT DOWN		AP	ACCESS PANEL
		EXISTING EQUIPMENT TO BE REMOVED			EXISTING EQUIPMENT TO REMAIN
		NEW EQUIPMENT			NEW EQUIPMENT

MECHANICAL GENERAL NOTES:	
GENERAL	
GM-1	THE MECHANICAL INSTALLATION SHALL CONFORM TO THE 2018 EDITION OF THE IMC WITH UTAH ANNOTATIONS AND LOCAL AUTHORITY REQUIREMENTS.
GM-2	MECHANICAL INFORMATION IS NOT LIMITED TO THE MECHANICAL DRAWINGS. CONTRACTOR SHALL BE RESPONSIBLE FOR INFORMATION ON ALL OTHER CONSTRUCTION DOCUMENTS INCLUDING DRAWINGS BY OTHER DISCIPLINES AND SPECIFICATIONS.
GM-3	A - EACH DRAWING SHEET HAS BEEN PREPARED TO SUPPLEMENT EACH OTHER AND THEY SHALL BE INTERPRETED AS AN INTEGRAL UNIT WITH ITEMS SHOWN AND NOTED ON ONE AND NOT THE OTHER BEING FURNISHED AND INSTALLED AS THOUGH SHOWN AND CALLED OUT IN ALL PLACES. B - THE CONTRACTOR WILL BE HELD RESPONSIBLE FOR THE INSTALLATION OF THE SYSTEMS ACCORDING TO THE TRUE INTENT AND MEANING OF THE CONTRACT DOCUMENTS. C - THE CONTRACTOR SHALL INSTALL ALL EQUIPMENT WITH PROPER SERVICE ACCESS AND CLEARANCES ACCORDING TO MANUFACTURERS RECOMMENDATIONS. THE CONTRACTOR SHALL REVIEW SUPPLIERS BID PACKAGES FOR COMPLETENESS AND COMPLIANCE TO THE SPECIFICATIONS, SCHEDULES, AND DESIGN INTENT (ALL EQUIPMENT AND METHODS). THE CONTRACTOR SHALL REMOVE AND REINSTALL CORRECTLY AT HIS OWN EXPENSE ANY EQUIPMENT NOT IN COMPLIANCE. D - THE CONTRACTOR SHALL CONSULT MANUFACTURERS INSTALLATION INSTRUCTIONS FOR SIZES, METHODS, ACCESSORIES, AND CLEARANCES IN SPACE AVAILABLE PRIOR TO BIDDING PROJECT. E - ANYTHING NOT CLEAR OR IN CONFLICT WILL BE EXPLAINED BY MAKING APPLICATION TO THE ENGINEER IN WRITING.
GM-4	ANY AND ALL ALTERATIONS TO THE SYSTEM SHOWN SHALL BE THE RESPONSIBILITY OF THIS CONTRACTOR. ARCHITECT SHALL BE NOTIFIED IN WRITING PRIOR TO CHANGES.
GM-5	CONTRACTOR SHALL FIELD VERIFY ALL DIMENSIONS AND LOCATIONS.
GM-6	THE WORKING DRAWINGS ARE DIAGRAMMATIC. THEY DO NOT SHOW EVERY OFFSET, BEND, OR ELBOW NECESSARY FOR THE COMPLETE INSTALLATION IN THE SPACE PROVIDED. ALL LOCATIONS FOR MECHANICAL EQUIPMENT SHALL BE FIELD VERIFIED AND COORDINATED WITH ALL DRAWINGS. THE CONTRACTOR SHALL PROVIDE OR COORDINATE WITH THE GENERAL CONTRACTOR PROVISIONS FOR BLOCK OUTS OR CORE DRILLS THROUGH STRUCTURE. CHANGES REQUIRED IN WORK SPECIFIED IN DIV 22 AND 23 CAUSED BY NEGLECT TO SECURE APPROVAL SHALL BE MADE AT NO COST TO THE OWNER.
GM-7	THE INSTRUCTION TO "PROVIDE" ALSO INCLUDES INSTALLATION.
GM-8	THE CONTRACTOR SHALL ASSUME ALL RESPONSIBILITY IN HANDLING AND DISPOSING OF REFRIGERANTS, OILS, ETC. ALL SUCH MATERIALS SHALL BE HANDLED, DISPOSED, AND USED ON ACCORDANCE WITH ALL LOCAL, STATE, AND FEDERAL LAWS.
GM-9	THE MECHANICAL CONTRACTOR SHALL VERIFY MOTOR VOLTAGES WITH THE ELECTRICAL DRAWING PRIOR TO ORDERING MOTORIZED EQUIPMENT AND CONTROLS.
GM-10	SUPPLIERS SHALL REVIEW ALL DRAWINGS PRIOR TO SUBMITTING PRICES TO THE CONTRACTOR. ALL QUESTIONS AND DISCREPANCIES SHALL BE BROUGHT TO THE ENGINEERS ATTENTION PRIOR TO BIDDING.
GM-11	CONTRACTOR SHALL THOROUGHLY REVIEW AND SIGN SUBMITTALS FOR COMPLETENESS AND COMPLIANCE TO THE SPECIFICATIONS PRIOR TO ENGINEERS REVIEW. SUPPLIERS SHALL HIGHLIGHT OR MARK ALL INFORMATION REQUIRED TO SHOW COMPLIANCE TO THE SPECIFICATIONS. ALL REQUESTED EXCEPTIONS TO THE DRAWINGS, OR SCHEDULES SHALL BE CLEARLY NOTED AND EXPLAINED. SUBMITTAL REVIEW AND ACCEPTANCE IS FOR DESIGN CONCEPT ONLY, AND DOES NOT AT ANY TIME RELIEVE THE CONTRACTOR OF RESPONSIBILITY TO MEET SPECIFICATIONS, CAPACITIES, OR DESIGN INTENT.
GM-12	INSTALLATION AND SELECTION OF MATERIALS AND EQUIPMENT SHALL ADHERE TO THE REQUIREMENTS OF ASHRAE/IEES 90.1-2016 ENERGY EFFICIENT DESIGN OF NEW BUILDINGS EXCEPT LOW RISE AND ENFORCED BY THE LAWS OF THE STATE OF UTAH AND THE LOCAL AUTHORITY HAVING JURISDICTION.
GM-13	PROVIDE OPERATION AND MAINTENANCE (O&M) MANUALS TO THE OWNER. SUBMIT TO ENGINEER ELECTRONICALLY FOR REVIEW AND COMPLETENESS. THIS SHALL INCLUDE MINIMUM 1 YEAR LABOR WARRANTY, ORGANIZED APPROVED SUBMITTALS, O&M DOCUMENTS FOR ALL EQUIPMENT, CONTROLS DIAGRAMS, SEQUENCE OF OPERATIONS, TAB REPORT, ETC. DOCUMENT SHALL BE AN ORGANIZED AND BOOKMARKED PDF.


GM-14	CONTRACTOR SHALL KEEP AN UP TO DATE SET OF MECHANICAL AND PLUMBING DRAWINGS IN HIS CUSTODY SHOWING ALL CHANGES IN RED, CLEARLY DEFINED AND NEATLY DRAFTED BY HIM. AT THE END OF CONSTRUCTION, HE SHALL TURN THESE DRAWINGS OVER TO THE ENGINEER. RECORD DRAWINGS MUST BE COMPLETED AND SUBMITTED PRIOR TO FINAL SITE OBSERVATION.
GM-15	PROVIDE TAGS AND LABELS ON NEW PIPING, DUCTWORK, AND EQUIPMENT. EQUIPMENT TAGS SHALL BE METAL WITH DATA ENGRAVED OR STAMPED FOR PERMANENT ATTACHED ON EQUIPMENT AND SHALL INCLUDE MANUFACTURER, PRODUCT NAME, MODEL NUMBER, SERIAL NUMBER, CAPACITY, OPERATING AND POWER CHARACTERISTICS, AND ESSENTIAL DATA. THESE SHALL BE LOCATED IN AN ACCESSIBLE AND VISIBLE LOCATION. PIPING MARKERS SHALL BE COLOR CODED WITH LETTERING INDICATING SERVICE AND FLOW DIRECTION. DUCT LABELS SHALL BE LOCATED WHERE DUCTS ENTER INTO CONCEALED SPACES AND A MAXIMUM INTERVAL OF 50 FEET IN EXPOSED OR ACCESSIBLE CEILINGS. THESE SHALL INDICATE SERVICE AND FLOW DIRECTION.
GM-16	SEE STRUCTURAL PLANS FOR OFFICIAL SEISMIC AND WIND CLASSIFICATIONS. PROVIDE SEISMIC CALCULATIONS AND DESIGN AS DEFERRED SUBMITTAL FOR ALL COMPONENTS REQUIRED BY IBC BY LICENSED SEISMIC ENGINEER. BUILDING IMPORTANCE FACTOR = 1.0. COMPONENT IMPORTANCE FACTOR SHALL BE THE SAME AS BUILDING UNLESS SPECIFIED DIFFERENTLY IN THE IBC.
	AIR SIDE
GA-1	MECHANICAL CONTRACTOR SHALL PROVIDE AND INSTALL SMOKE AND FIRE DAMPERS AS REQUIRED BY LOCAL CODES AND AUTHORITIES.
GA-2	SHEET METAL DUCT SIZES SHOWN ON DRAWINGS ARE FREE AREA DIMENSIONS.
GA-3	PROVIDE AND INSTALL BALANCING DAMPERS IN ALL SUPPLY AND EXHAUST AIR BRANCH DUCTS. BALANCE TO CFM SHOWN ON PLAN. TESTING AND BALANCING SHALL BE PERFORMED BY AABC OR NEBB CERTIFIED TAB CONTRACTOR. BALANCE REPORT SHALL BE ISSUED TO THE ENGINEER OF RECORD FOR REVIEW.
GA-4	SEE ARCHITECTURAL REFLECTED CEILING PLAN FOR EXACT LOCATION OF DIFFUSERS AND GRILLES.
GA-5	PROVIDE TURNING VANES IN ALL ELBOWS OF RECTANGULAR DUCT.
GA-6	C.F.M. LISTED IS ACTUAL AIR.
GA-7	ALL DUCTWORK SHALL BE GALVANIZED STEEL FABRICATED TO SMACNA STANDARDS FOR THE VELOCITY, PRESSURE, AND GEOMETRY INVOLVED. DUCT JOINTS SHALL BE SEALED USING HARD CAST TAPE. TYPE AND APPLICATION TECHNIQUES SHALL BE AS RECOMMENDED BY THE MANUFACTURER FOR THE INTENDED USE AND LOCATION.
GA-8	DUCT LINER SHALL BE ATTACHED TO INSIDE OF DUCTWORK WITH ADHESIVE COATING BETWEEN THE DUCT AND LINER AND FURTHER SECURED BY PINS MECHANICALLY FASTENED TO DUCT. PINS ADHESIVELY ATTACHED ARE NOT ACCEPTABLE ALL EDGES OF LINER SHALL BE THOROUGHLY COATED WITH ADHESIVE AND TIGHTLY BUTTED. LINER SHALL BE FIBERGLASS WITH BLACK CLOTH FINISH ON SMACNA STANDARDS AND ALL REQUIREMENTS OF THE MANUFACTURER. LINER AND ADHESIVE SHALL MEET ALL REQUIREMENTS OF FEDERAL, STATE, AND LOCAL CODES.
GA-9	DUCTWORK ROUTED OUTSIDE OF BUILDING SHALL BE INSULATED AS REQUIRED BY ASHRAE/IEES 90.1-2016. INSULATION SHALL BE MADE UP OF DUCT LINER, EXTERNAL DUCT WRAP WITH A WEATHERPROOF COVER OR A COMBINATION THERE OF AS NEEDED TO MEET REQUIREMENTS. INSULATION SYSTEM SHALL MEET UBC, IMC, ASTM, UL, AND NFPA STANDARDS AND REQUIREMENTS.



SALT LAKE CITY, UT



WHW
ENGINEERING INC.
PROFESSIONAL MECHANICAL ENGINEERING
1500 East 2500 South Suite 200
SALT LAKE CITY, UTAH 84119
(801)462-0000 FAX (801)462-0002
EMAIL: ecobacco@whw-engineering.com



CONSTRUCTION
ISSUE



DILKON PASS
PIPELINE AND
PUMP STATION

REVISIONS

REV	DATE	DESCRIPTION

LINE IS 2 INCHES
AT FULL SIZE

DESIGNED: E. RIGBY

DRAWN: E. RIGBY

CHECKED: J. LARSEN

CHECKED:-----

APPROVED: W. PACKER

FILENAME

H-001.dwg

BC PROJECT NUMBER

157520

CLIENT PROJECT NUMBER

00357.21

HVAC

HVAC LEGEND AND
GENERAL NOTES

DRAWING NUMBER


H-001

56


SHEET NUMBER
OF

59

Path: P:\2021\21161 DILKON PASS BPS & PIPELINE\DRAWINGS FILENAME: M 21161 DILKON PASS BPS & PIPELINE.DWG PLOT DATE: 3/2/2022 5:13 PM CAD USER: ETHAN RIGBY



PLAN
SCALE: 1/2" = 1'-0"



SECTION
SCALE: 1/2" = 1'-0"


- SHEET NOTES:**
1. PROVIDE INLINE EXHAUST FAN, MOTORIZED DAMPER, AND LOUVER. INTERLOCK WITH FRESH AIR INLET DAMPER AND DISTRICT SCADA SYSTEM.
 2. PROVIDE INTAKE LOUVER, LINED DUCT ELBOW, AND MOTORIZED DAMPER. INTERLOCK DAMPER WITH EXHAUST FAN AND DISTRICT SCADA CONTROL SYSTEM.
 3. PROVIDE ELECTRIC UNIT HEATERS. INSTALL PER MANUFACTURE'S RECOMMENDATIONS. TIE TEMPERATURE CONTROL INTO SCADA SYSTEM.
 4. DUCTWORK & LOUVERS IN CHLORINE ROOM TO BE ALUMINUM.
 5. FAN & DAMPER TO BE OPERATED ON SWITCH PLACED NEAR DOOR. PROVIDE WITH SIGNAGE ON DOOR FOR FAN TO BE TURNED ON FOR 5 MINUTES PRIOR TO ENTERING.



SALT LAKE CITY, UT



WHW
ENGINEERING INC.
PROFESSIONAL MECHANICAL ENGINEERING
1500 EAST 2500 SOUTH SUITE 200
SALT LAKE CITY, UT 84119
(801) 462-8800 FAX (801) 462-8802
EMAIL: eed@whw-engineering.com



CONSTRUCTION
ISSUE



DILKON PASS
PIPELINE AND
PUMP STATION

REVISIONS

REV	DATE	DESCRIPTION

LINE IS 2 INCHES
AT FULL SIZE

DESIGNED: E. RIGBY

DRAWN: E. RIGBY

CHECKED: J. LARSEN

CHECKED:-----

APPROVED: W. PACKER

FILENAME

H-101.dwg

BC PROJECT NUMBER

157520

CLIENT PROJECT NUMBER

00357.21

HVAC

DILKON PASS PUMP
STATION HVAC
PLAN AND SECTION

DRAWING NUMBER


H-101

57


SHEET NUMBER
OF

59


Path: P:\2021\21161 DILKON PASS BPS & PIPELINE\DRAWINGS FILENAME: M 21161 DILKON PASS BPS & PIPELINE.DWG PLOT DATE: 3/2/2022 5:13 PM CAD USER: ETHAN RIGBY



C5 ELECTRIC UNIT HEATER DETAIL
SCALE: NONE



B5 IN-LINE EXHAUST FAN DETAIL
SCALE: NONE




A5 DUCT THRU WALL DETAIL
SCALE: NONE



SALT LAKE CITY, UT



WHW
ENGINEERING INC.
PROFESSIONAL MECHANICAL ENGINEERING
1154 EAST 2100 SOUTH SUITE 200
SALT LAKE CITY, UTAH 84119
(801) 462-1000 FAX 462-1002
EMAIL: ec@whw-engineering.com



CONSTRUCTION
ISSUE



DILKON PASS
PIPELINE AND
PUMP STATION

REVISIONS

REV	DATE	DESCRIPTION

LINE IS 2 INCHES
AT FULL SIZE

DESIGNED: E. RIGBY

DRAWN: E. RIGBY

CHECKED: J. LARSEN

CHECKED:-----

APPROVED: W. PACKER

FILENAME

H-102.dwg

BC PROJECT NUMBER

157520

CLIENT PROJECT NUMBER

00357.21

HVAC

HVAC DETAILS

DRAWING NUMBER

H-102

58

SHEET NUMBER
OF

59

Path: P:\2021\2161 DILKON PASS BPS & PIPELINE\DRAWINGS FILENAME: M 2161 DILKON PASS BPS & PIPELINE.DWG PLOT DATE: 3/2/2022 5:13 PM CAD USER: ETHAN RIGBY

EXHAUST FAN SCHEDULE										
SYMBOL	MANUFACTURER & MODEL No.	SERVES	C.F.M.	STATIC PRESSURE IN. WG.	MAX NOISE SONES	MOTOR			OPER. WT. (LBS)	SCHEDULE NOTES
						V - Ø - Hz	HP	RPM		
<div>EF1</div>	COOK 100 ACWB OR80	CHLORINE ROOM	350	0.35	7.6	115-1-60	1/6	1725	47	1,3,5,6
<div>EF2</div>	COOK DB9	PUMP ROOM	1750	0.35	11.5	115-1-60	1/2	869	98	1,2,3,4
1. MANUFACTURER TO BE LOREN COOK, CARNES, GREENHECK, TWIN CITY JENCO, OR PRIOR APPROVED EQUAL. 2. INLINE FAN, SUPPORT FROM SPRING HANGERS. 3. PROVIDE WITH BACK-DRAFT DAMPER. 4. SEE DETAIL E ON SHEET E-102 FOR ONE-LINE CONTROL DIAGRAM. 5. FAN TO OPERATE BY SWITCH NEAR LIGHT. SIGNAGE ON DOOR TO RUN FAN FOR 5 MINUTES BEFORE ENTERING. 6. FAN PROVIDED SHALL BE COATED INSIDE AND OUT IN PHENOLIC EPOXY COATING. ALL INTERNAL FERROUS MATERIALS SHALL ALSO BE PROVIDE COATED WITH PHENOLIC EPOXY COATING. ALL FASTENERS SHALL BE STAINLESS STEEL HARDWARE.										

ELECTRIC UNIT HEATER SCHEDULE											
SYMBOL	MANUFACTURERS AND MODEL NO.	CFM	BTUH	ELECTRICAL			RPM	AIR TEMP RISE (F)	THROW (FT)	WEIGHT (LBS)	SCHEDULE NOTES
				SERVICE	KW	HP					
<div>UH1</div>	MODINE HER30	380	10200	208-1-60	3	1/40	1550	25	12	34	1,2
<div>UH2</div>	MODINE HER30	380	10200	208-1-60	3	1/40	1550	25	12	34	1,2
1. MANUFACTURER TO BE MODINE, MARLEY, QMARK, MARKEL, CHORMALOX, INDEECO, OR PRIOR APPROVED EQUAL. 2. PROVIDE WITH TEMPERATURE SENSOR AND TIE INTO SCADA SYSTEM. COORDINATE WITH SCADA CONTRACTOR.											

REGISTER, LOUVER, & GRILLE SCHEDULE									
SYMBOL	TYPE	SERVICE	MAX CFM	NOMINAL SIZE	THROAT SIZE	CEILING TYPE	FT./MIN.	MANUF. & MODEL	SCHEDULE NOTES
<div>L-1</div>	WALL	INTAKE	1750	34X34	34X34	N/A	500	RUSKIN ELF811	1,2,3,4,5
<div>L-2</div>	WALL	EXHAUST	1750	28X40	28X40	N/A	600	RUSKIN ELF811	1,2,3,4,5
<div>L-3</div>	WALL	INTAKE	350	16x16	14x14	N/A	500	RUSKIN ELF811	1,2,3,4,5
<div>EG-1</div>	DUCT	EXHAUST	750	24X12	24X12	DUCT MOUNTED	500	PRICE 500	2,4,5
1. SEAL ALL PENETRATIONS WEATHER TIGHT. 2. MAXIMUM FT/MIN AT CFM LISTED. 3. PROVIDE TRANSITION TO LOUVER THROAT SIZE AS REQUIRED TO DUCTWORK SHOWN ON PLAN. 4. MANUFACTURER TO BE RUSKIN, GREENHECK, POTTORF, CARNES, OR PRIOR APPROVED EQUAL. 5. FINISH SHALL BE SPECIFIED BY ARCHITECT.									


CONTROL DAMPER SCHEDULE					
SYMBOL	SIZE	NO. REQUIRED	LOCATION	MANUF.& MODEL	COMMENTS
<div>MD1</div>	32"X32"	1	PUMP RM.	RUSKIN CD40	2,3,4
<div>MD2</div>	14"X14"	1	CHLORINE RM.	RUSKIN CD40	1,3,4
1. DAMPER TO BE LOW LEAKAGE OF ALUMINUM CONSTRUCTION. 2. ACTUATOR TO BE BELIMO 120/1/60. 3. DAMPER MANUFACTURER TO BE RUSKIN, GREENHECK, POTTORF, CARNES, OR PRIOR APPROVED EQUAL.					



SALT LAKE CITY, UT



WHW
ENGINEERING INC.
PROFESSIONAL MECHANICAL ENGINEERING
1184 East 2100 South Suite 200
SALT LAKE CITY, UT 84143
(801)462-1100 FAX 462-8832
EMAIL: ecobacco@whw-engineering.com



CONSTRUCTION
ISSUE



DILKON PASS
PIPELINE AND
PUMP STATION

REVISIONS

REV	DATE	DESCRIPTION

LINE IS 2 INCHES
AT FULL SIZE

DESIGNED: E. RIGBY

DRAWN: E. RIGBY

CHECKED: J. LARSEN

CHECKED:-----

APPROVED: W. PACKER

FILENAME

H-501.dwg

BC PROJECT NUMBER

157520

CLIENT PROJECT NUMBER

00357.21

HVAC

HVAC SCHEDULES


DRAWING NUMBER

H-501

59

SHEET NUMBER
OF

59



NOTES:

1. SELECT EITHER PAGE 2a OR 2b BASED ON METER SIZE.

2. TEST DURATION SHALL BE FOR 2 HOURS.

DATE PERFORMED: _____. LAB SAMPLE NO.: _____. INITIALED (NTUA): _____.

INDEX	SHEET
1" WATER SERVICE	1 of 5
MATERIAL LIST: 5/8" x 3/4" METER	2a of 5
MATERIAL LIST: 1" METER	2b of 5
GENERAL NOTES	3 of 5
PROPOSED CONSTRUCTION DRAWING	4 of 5
INDIVIDUAL AS-BUILT	5 of 5

AS-BUILT LOCATION OF TAP	
SYSTEM NAME	
PROJECT NO.	
SHEET NO.	
LINE NO.	
STATION NO.	

SHEET 1 OF 7

DESIGNED BY:	NTUA
SURVEYED BY:	
DRAWN BY:	NTUA
APPROVED BY:	NTUA
DATE:	04/08
PROJECT NO.	
SCALE:	NTS
ACAD FILENAME:	Water Standard
DWG. NO.	WS-1.DWG

NAVAJO TRIBAL UTILITY AUTHORITY 1" WATER SERVICE FOR A 5/8" x 3/4" OR 1" METER	
EQ-ENGINEERING	FT.DEPANCE, AZ

REVISIONS			
No.	Date	Brief	By
01	04/08	Revised	L.H.
02			
03			
04			
05			
06			



DESIGNED BY:	NTUA
SURVEYED BY:	NTUA
DRAWN BY:	NTUA
APPROVED BY:	NTUA
DATE:	04/08
PROJECT NO.:	NTS
SCALE:	AS SHOWN
ADD FILENAME:	Water Standard
DWG. NO.:	WS-10.010

MATERIAL LIST: 1" SERVICE WITH 5/8" x 3/4" METER PT. 10.010

REVISIONS
No. Date 01 04/08 02 03 04 05 06
Brief Revised
By



MATERIAL LIST		
ITEM	QUAN	DESCRIPTION
1	1	SADDLE, BRASS, 1" FIPT x APPROPRIATE PIPE TYPE, O.D., AND LINE PRESSURE
2	1	CORPORATION STOP, 1" MIPT x 1" FIPT, MUELLER H-10046, OAE
3	1	CURB STOP, 1" FIPT x 1" FIPT, MINNEAPOLIS PATTERN W/ O-RING, MUELLER H-10287, OAE
4	A.R.	CONCRETE BLOCK OR BRICK
5	A.R.	CONCRETE COLLAR, 18" SQUARE x 4" THICK, W/ #4 REBARS, E.W.O.C.
6	1	CURB VALVE BOX, EXTENSION TYPE, MUELLER H-10302, W/ 2" x 1 1/2" BUSHING, OAE
7	2	STATIONARY ROD 36" LONG, MUELLER PART #84338, SECURED TO THE CURB STOP W/ COTTER PIN
8	1	COPPERSETTER W/ VALVED 12" RISER FOR 5/8" x 3/4" WATER METER, FORD NO. VB72-12W-FF-44, OAE, W/ 1" IP UNION NUT/SWIVEL ASSEMBLY CONNECTION ON INLET, OUTLET, AND BRACING EYE
8a	1	TANDEM COPPERSETTER WITH VALVED 12" RISER, 5/8" x 3/4" WATER METER, FORD NO. TVB-72-12W-FF-44, OAE, W/ TWO REGULATOR ADAPTERS FOR THE PRV
9	1	METER CAN, 20" O.D. x 30" HT., DFW PLASTIC, DFW 2030 B SERIES "T" TOP
10	1	METER BOX COVER W/ FROST PLATE, FOR 20" METER CAN, 11 1/2" MINIMUM LID
		OPENING, CASTING M-70
11	6	INSTA-TITE FITTING, 1" MIPT x 1" STAB FOR SIDR 7 P.E. PIPE, MUELLER H15426
12	1	CONNECTOR/ADAPTER, 1" MIPT x APPROPRIATE PIPE TYPE AND O.D.
13	A.R.	PIPE, 1" P.E., ASTM D-2239, SIDR 7, 200 PSI, 200' MAX.
14	1	METER, POSITIVE DISPLACEMENT, NEPTUNE, SR, 5/8" x 3/4", GALLONS, W/ FROST PLATE
15	1	PRV, WILKENS 600 OR WATTS 25 AUB, 3/4" FIPT
16	1	ADAPTER, 3", HUB x FIPT PVC-DWV
17	1	CLEANOUT PLUG, 3" MIPT, PVC-DWV
18	1	RISER, 3" x 36" LONG, PVC-DWV
19	1	STABILIZER, 1/2" O.D. x 12" LONG PIPE, PVC, SCH. 40
20	A.R.	BLUE CARSONITE MARKER POST
21	A.R.	"WATERLINE WARNING" DECAL (FOR ITEM 20)

NOTES:

1. A.R. = AS REQUIRED
2. DECAL TO BE AFFIXED TO ITEM NO. 20.
3. NORMAL FLOW RATE = 1-20 GPM.
4. NTUA WILL NOT PROVIDE WATER METERS FOR SUBDIVISIONS AND DEVELOPERS.
5. WATER METER SERIAL NUMBER: _____
6. SADDLE SIZE: _____

DESIGNED BY:	NTUA
SURVEYED BY:	NTUA
DRAWN BY:	NTUA
APPROVED BY:	NTUA
DATE:	04/08
PROJECT NO.:	NTS
SCALE:	AS SHOWN
ADD FILENAME:	Water Standard
DWG. NO.:	WS-1b.DWG

NAVAJO TRIBAL UTILITY AUTHORITY
By: <i>[Signature]</i>
MATERIAL LIST: 1" SERVICE
WITH 1" METER
PT. JEROME, AZ

REVISIONS	
No.	Date
01	04/08
02	
03	
04	
05	
06	



MATERIAL LIST		
ITEM	QUAN	DESCRIPTION
1	1	SADDLE, BRASS, 1" FIPT x APPROPRIATE PIPE TYPE, O.D., AND LINE PRESSURE
2	1	CORPORATION STOP, 1" MIPT x 1" FIPT, MUELLER H-10046, OAE
3	1	CURB STOP, 1" FIPT x 1" FIPT, MINNEAPOLIS PATTERN W/ O-RING, MUELLER H-10287, OAE
4	A.R.	CONCRETE BLOCK OR BRICK
5	A.R.	CONCRETE COLLAR, 18" SQUARE x 4" THICK, W/ #4 REBARS, E.W.O.C.
6	1	CURB VALVE BOX, EXTENSION TYPE, MUELLER H-10302, W/ 2" x 1 1/2" BUSHING, OAE
7	2	STATIONARY ROD, 36" LONG, MUELLER PART #84338, SECURED TO THE CURB STOP W/ COTTER PIN
8	1	COPPERSETTER W/ VALVED 12" RISER, 1" WATER METER, FORD NO. VB74-12W-FF-44,
		OAE, W/ 1" IP UNION NUT/SWIVEL ASSEMBLY CONNECTION ON INLET, OUTLET, AND BRACING EYE
8a	1	TANDEM COPPERSETTER WITH VALVED 12" RISER, 1" WATER METER, FORD NO. TVB-74-12W-FF-44,
		OAE, W/ TWO REGULATOR ADAPTERS FOR THE PRV
9	1	METER CAN, 20" O.D. x 30" HT., DFW PLASTIC, DFW 2030 B SERIES "T" TOP
10	1	METER BOX COVER W/ FROST PLATE, FOR 20" METER CAN, 11 1/2" MINIMUM LID
		OPENING, CASTING M-70
11	6	INSTA-TITE FITTING, 1" MIPT x 1" STAB FOR SIDR 7 P.E. PIPE, MUELLER H15426
12	1	CONNECTOR/ADAPTER, 1" MIPT x APPROPRIATE PIPE TYPE AND O.D.
13	A.R.	PIPE, 1" P.E., ASTM D-2239, SIDR 7, 200 PSI, 200' MAX.
14	1	METER, POSITIVE DISPLACEMENT, SENSUS, SR, 1", GALLONS, W/ FROST PLATE
15	1	PRV, WILKENS 600 OR WATTS 25 AUB, 1" FIPT
16	1	ADAPTER, 3", HUB x FIPT PVC-DWV
17	1	CLEANOUT PLUG, 3" MIPT, PVC-DWV
18	1	RISER, 3" x 36" LONG, PVC-DWV
19	1	STABILIZER, 1/2" O.D. x 12" LONG PIPE, PVC, SCH. 40
20	A.R.	BLUE CARSONITE MARKER POST
21	A.R.	"WATERLINE WARNING" DECAL (FOR ITEM 20)

NOTES:

1. A.R. = AS REQUIRED
2. DECAL TO BE AFFIXED TO ITEM NO. 20.
3. NORMAL FLOW RATE = 3-50 GPM.
4. WATER METER SERIAL NUMBER: _____
5. SADDLE SIZE: _____

1. PROVIDE 10' MINIMUM HORIZONTAL SEPARATION IN SEPARATE TRENCHES BETWEEN WATER AND SEWER SERVICES, PAST THE BUILDING PLUMBING. PROVIDE 5' MINIMUM HORIZONTAL SEPARATION BETWEEN WATER SERVICE AND OTHER UTILITIES. FOR WATER AND SEWER CROSSING. PROVIDE A MINIMUM OF 12" VERTICAL CLEARANCE, PIPE O.D. TO PIPE O.D. IF WATER SERVICE CROSSES OTHER UTILITIES, ALL STIPULATIONS FOR THE OTHER UTILITY MUST BE MET.
2. BUILDING PLUMBING, WATER AND SEWER SERVICES TO BE INSTALLED IN ACCORDANCE WITH THE NATIONAL PLUMBING CODE ADOPTED BY THE NAVAJO NATION.
3. WATER SERVICES SHALL HAVE A MINIMUM COVER OF 36" AND SHALL BE INSTALLED IN CONFORMANCE WITH NTUA STANDARDS.
4. SADDLES SHALL BE SINGLE STRAP/BAND TYPE, FOR STEEL PIPE O.D. PVC. SADDLES SHALL BE DOUBLE STRAP/BAND TYPE, FOR D.I., A.C., OR C-900 PIPE. ON EXISTING 2" PIPING, A 2" x 1" PVC TEE SHALL BE USED. CONTACT NTUA HEADQUARTERS ENGINEERING ON PIPING SMALLER THAN 2".
5. PROVIDE THE AS-BUILT SWING TIE INFORMATION FOR THE TAP POINT AND OTHER APPURTENANCES INSTALLED, ON SHEET 5 of 5.
6. THE WATER METER SHALL BE CENTERED AND SET A MAX. OF 24" BELOW THE TOP OF THE METER BOX COVER.
7. THE METER CAN SHALL BE LOCATED JUST BEYOND THE SIDEWALK AT THE PROPERTY LINE OR WITH OWNER'S PERMISSION A MINIMUM OF 10' FROM THE BUILDING.
8. WATER SERVICE LINES ARE LIMITED TO A MAXIMUM OF 200'. IF THE PRESSURE AT THE HOME SITE IS ABOVE 70 PSI, INSTALL THE APPROPRIATE TANDEM COPPERSETTER WITH AN INDIVIDUAL PRV (ITEM 8A).
9. USE FIELD MARKERS WHERE APPROPRIATE.
10. SUBMIT CONSTRUCTION COST OF NEW INSTALLATION UP TO AND INCLUDING THE METER. INDICATE AS FOLLOWS: A. MATERIAL COST, B. LABOR COST, C. EQUIPMENT COST, D. TOTAL CONSTRUCTION COST. THE COST SHALL BE SHOWN ON SHEET 5 of 5 AND THE TRANSFER AGREEMENT.
11. SHEETS 4 OF 5 AND 5 OF 5 ARE FOR RESIDENTIAL INSTALLATIONS ONLY. ALL OTHER PROJECTS, SUBMIT 4 SETS OF COMPLETE DRAWINGS.


SHEET 4 OF 7

DESIGNED BY:	NTUA
SURVEYED BY:	
DRAWN BY:	NTUA
APPROVED BY:	NTUA
DATE:	04/08
PROJECT NO.	
SCALE:	NTS
ACAD FILENAME:	Water Standard
DWG. NO.	WS-1c.DWG

NAVAJO TRIBAL UTILITY AUTHORITY <small>By Civil Engineering Department</small>	
GENERAL NOTES FOR WATER SERVICE	
HQ-ENGINEERING	FT.DEFIANCE, AZ

REVISIONS			
No.	Date	Brief	By
01	04/08	Revised	L.H.
02			
03			
04			
05			
06			





SHEET 1 OF 2

DESIGNED BY:	NTUA-HQ
SURVEYED BY:	-
DRAFTED BY:	NTUA-HQ
APPROVED BY:	NTUA-HQ
DATE:	01/2019
PROJECT NO.:	-
SCALE:	NTS
ACAD FILENAME:	2019 NTUA Std. Dwg. for Water.dwg
DETAIL NO.:	WS-4b

NAVAJO TRIBAL UTILITY AUTHORITY
ENGINEERING & CONSTRUCTION OPERATIONS DIVISION

4" x 2" P.R.V.

NTUA HEADQUARTERS

FT. DEFIANCE, AZ

REVISIONS

No.	Date	Brief	By
01	09/15	2015 Addition	A.S.
02	01/19	2019 Update	A.S.
03			
04			
05			
06			



4" x 2" P.R.V.

#

MATERIAL LIST

ITEM	QTY	DESCRIPTION
1	1	4" CLA-VAL, PRESSURE REDUCING VALVE, THREADED ENDS, STAINLESS STEEL (S.S.) TRIM & PILOT TUBING, 90 SERIES W/ OPTIONS A, B, C, D, V & M
2	A.R.	4" DUCTILE IRON (D.I.) PIPE, CLASS 350, PLAIN END, CUT AS NEEDED
3	1	4" DRESSER COUPLING (6" LONG FOR D.I. PIPE)
4	2	4" GATE VALVE, F.I.P.T., N.R.S., R.H.T., BRASS HAND WHEEL
5	2	2" DOUBLE STRAP W/ 2" x 3/4" BUSHING AND 3/4" x 1/4" BUSHING FOR PRESSURE GAGE
6	2	PRESSURE GAUGE W/ 1/4" BRASS SHUTOFF VALVE
7	1	2" CLA-VAL, PRESSURE REDUCING VALVE, THREADED ENDS, STAINLESS STEEL (S.S.) TRIM & PILOT TUBING, 90 SERIES W/ OPTIONS A, B, C, D, V & M
8	A.R.	2" S.S. PIPE, THREADED, CUT AS NEEDED
9	1	2" DRESSER COUPLING (6" LONG FOR S.S. PIPE)
10	2	2" GATE VALVE, F.I.P.T., N.R.S., R.H.T., BRASS HAND WHEEL
11	4	4" x 2" TAP SADDLE
12	2	2" 90° S.S. ELBOW, F.I.P.T.
13	1	2" S.S. HOSE BIB
14	1	2" S.S. TEE W/ 2" x 3/4" BUSHING AND 3/4" x 1/4" BUSHING FOR HOSE BIB
15	2	VAULT BORE DONUT, 6" O.D. / 4" I.D.
16	2	4" D.I. 'E-Z' FLANGED ADAPTER
17	2	4" GATE VALVE, M.J., RESILIENT SEAT, FLANGED, N.R.S., R.H.T., W/ 2" OPERATING NUT
18	4	VALVE BOX, 2-PIECE SCREW TYPE, 5-1/4" SHAFT W/ CAST IRON DROP LID
19	-	4" C-900 PVC PIPE
20	2	2" CORPORATION STOP, MIPT x FIPT
21	2	INSTALL 2" FLUSH VALVE PER NTUA STD. DTL. WS-11 (AFTER THE CORP. STOP)
22	1	'LANE' POLYPROPYLENE VAULT LADDER W/ PULL-UP HANDRAIL (5 RUNG)
23	1	9' x 6' x 6' (INT. DIM.) PRECAST CONCRETE VAULT (4,000 PSI MIN.), 6" THICK WALLS W/ 6" THICK REINFORCED CONCRETE TOP (NON-TRAFFIC RATED) AND 6" REINFORCED CONCRETE BASE
24	1	ACCESS COVER, 6' x 6' (INT. DIM) SQ., INSULATED, DOUBLE DOOR COVER AND SAFETY GRATE, ALUMINUM CHANNEL FRAME W/ T-HANDLE SLAM LOCK AND COVERED PADLOCK CLIP
25	A.R.	VAULT JOINTS TO BE SEALED WITH BITUMASTIC GASKET
26	4	24" x 24" x 4" CONCRETE COLLAR W/ #4 REBAR, E.W., INDICATE PIPE SIZE & FLOW DIRECTION
27	5	ADJUSTABLE METAL PIPE SUPPORT (UNDER 4" VALVES AND AT 2" 90° ELBOWS & 2" P.R.V.)
28	5	12" x 12" x 4" CONC. BLOCK
29	-	NOT USED
30	A.R.	CONCRETE ANCHOR BLOCK PER NTUA STD. DTL. WS-19 & WS-19a
31	4	6" DIA. BOLLARDS AT 12" MIN. FROM VAULT CORNERS PER MAG. STD. 140, TYPE 1

GENERAL NOTES:

1. PROVIDE ADEQUATE CLEARANCE BETWEEN FLANGE BOLTS AND VAULT WALLS FOR MAINTENANCE.
2. GATE VALVES TO BE SUPPORTED ON 95% STANDARD PROCTOR.
3. ALL PIPES AND FITTINGS 4" OR LESS TO BE STAINLESS STEEL.
4. HEX HEAD BOLTS/NUTS TO BE STAINLESS STEEL, TYPE 304.
5. A.R. = AS REQUIRED.
6. INSTALL GATE VALVE AND FLUSH VALVE WITHIN 25 FT OF PRV VAULT.

SHEET 2 OF 2

DESIGNED BY:	NTUA-HQ
SURVEYED BY:	-
DRAFTED BY:	NTUA-HQ
APPROVED BY:	NTUA-HQ
DATE:	01/2019
PROJECT NO.	-
SCALE:	NTS
ACAD FILENAME:	2019 NTUA Std. Dtl. for Water day
DETAIL NO.	WS-4c

 NAVAJO TRIBAL UTILITY AUTHORITY
 ENGINEERING & CONSTRUCTION OPERATIONS DIVISION

 MATERIAL LIST:
 4" x 2" P.R.V.


NTUA HEADQUARTERS

FT.DEFIANCE, AZ

REVISIONS

No.	Date	Brief	By
01	09/15	2015 Addition	A.S.
02	01/19	2019 Update	A.S.
03			
04			
05			
06			





MATERIAL LIST		
ITEM	QUAN	DESCRIPTION
1	3	1" x 3" NIPPLE, BRASS
2	2	1" x 90° ELBOW, BRASS
3	1	1" CURB STOP VALVE, FIPT, MUELLER H-10287, OAE
4	1	1" COMBINATION AIR RELEASE/VACUUM VALVE
5	1	1" O.D. PIPE, BRASS, 12" MIN.
6	1	STATIONARY ROD, 42"
7	1	METER CAN, 36" O.D. x 30" DEPTH, SONOLOC
8	1	METER CAN COVER W/ DOUBLE LID (FROST PLATE) FOR 36" O.D. CAN, CASTING M-70
9	1	1" x 6" NIPPLE, BRASS
10	1	SADDLE, BRASS, 1" TAP x APPROPRIATE PIPE O.D. SIZE
11	3 CF*	1" TO 2" FILTER ROCK
12	X	1" UNION

*CF = CUBIC FEET

DESIGNED BY:	NTUA
SURVEYED BY:	
DRAWN BY:	NTUA
APPROVED BY:	NTUA
DATE:	04/08
PROJECT NO.	
SCALE:	NTS
ACAD FILENAME:	Water Standard
DWG. NO.	WS-10.DWG

NAVAJO TRIBAL UTILITY AUTHORITY
By Civil Infrastructure Department

AIR RELEASE VALVE DETAIL


BQ-ENGINEERING

FT. DEFENCE, AZ

REVISIONS

No.	Date	Brief	By
01	04/08	Revised	L.H.
02			
03			
04			
05			
06			





MATERIAL LIST

ITEM	QUAN	DESCRIPTION
1	1	2' GATE VALVE, C.I., FIPT, RW, NRS, RHT, W/ 2' OPERATING NUT, MUELLER A-2360-37
2	1	VALVE BOX, SCREW-TYPE, C.I., 2 PIECE, 5 1/4" SHAFT, TYLER 6850
3	1	2" x 3' PIPE (MIN.), G.I., COATED OR POLYWRAPPED
4	1	2" x 45" ELBOW, G.I., W/ 1/8" WEEP HOLE
5	1	2" PIPE, G.I. x CUT TO LENGTH AS NEEDED
6	1	2" CAP, G.I. W/ 1/8" VENT HOLE
7	1	2" PIPE, PVC CUT TO LENGTH AS NEEDED
8	1	2" ADAPTER, PVC, SLIP-GASKET x MIPT, SDR-21
9	A.R.	CONCRETE THRUST BLOCK, (DO NOT COVER JOINTS OR BOLTS), MIN. 1.5 CUBIC FEET
10	1.5 CF	CLEAN GRAVEL
11	1	MAIN LINE SADDLE OR TEE
12	A.R.	#4 REBAR

DESIGNED BY: NTUA
 SURVEYED BY: NTUA
 DRAWN BY: NTUA
 APPROVED BY: NTUA
 DATE: 04/08
 PROJECT NO.
 SCALE: NTS
 ACAD FILENAME: Water Standard
 DWG. NO. WS-11.DWG

NAVAJO TRIBAL UTILITY AUTHORITY
 Navajo Tribal Utility Authority

2" FLUSH VALVE DETAIL



BQ-ENGINEERING

FT. DEFENCE, AZ

REVISIONS

No.	Date	Brief	By
01	04/08	Revised	L.H.
02			
03			
04			
05			
06			





NOTES:


1. IF APPROPRIATE, USE SERIES 2000 PV MEGALUG GLANDS FOR SDR-21, PVC TO SECURE GATE VALVE(S) TO OTHER FITTINGS/PIPE, USE OTHER MEGALUGS FOR DIFFERENT OUTSIDE DIAMETER PIPE/TYPE.
2. DO NOT COVER JOINTS AND BOLTS WITH CONCRETE.
3. SEE WS-13 FOR APPROPRIATE LOCATION OF MARKER POST.

DESIGNED BY:	NTUA
SURVEYED BY:	
DRAWN BY:	NTUA
APPROVED BY:	NTUA
DATE:	04/08
PROJECT NO.	
SCALE:	NTS
ACAD FILENAME:	Water Standard
DWG. NO.	WS-14.DWG


NAVAJO TRIBAL UTILITY AUTHORITY <small>By Civil Engineering Department</small>	
WATER MAIN VALVE INSTALLATION	
EQ-ENGINEERING	FT.DEPANCE, AZ

REVISIONS			
No.	Date	Brief	By
01	04/08	Revised	L.H.
02			
03			
04			
05			
06			







TEE
(PLAN VIEW)




DEAD END CAPPED OR PLUG
(PLAN VIEW)




CROSS
(PLAN VIEW)




90° ELBOW
(PLAN VIEW)




45° ELBOW
(PLAN VIEW)



VERTICAL BENDS
(SECTION VIEW)



VERTICAL GRAVITY THRUST BLOCK
(SECTION VIEW)



BEARING AREA
(SECTION VIEW)

NOTES:

1. DO NOT COVER GASKETED JOINTS AND NUTS/BOLTS.

MINIMUM BEARING AREAS IN SQUARE FEET

PIPE SIZE	TEE & PLUG	90° ELBOW	45° OR 22 1/2° ELBOW	CROSS
2"	0.5	0.5	0.5	0.5
4"	1.5	2.0	1.5	1.0
6"	3.0	4.5	2.5	2.0
8"	5.0	7.5	4.0	4.0
10"	8.0	11.0	6.5	5.5
12"	11.0	15.5	9.0	8.0
14"	15.0	21.0	12.0	10.5
16"	19.0	27.0	15.5	13.5
18"	24.0	34.0	19.0	17.0

SHEET 1 OF 2

DESIGNED BY:	NTUA
SURVEYED BY:	
DRAWN BY:	NTUA
APPROVED BY:	NTUA
DATE:	04/08
PROJECT NO.	
SCALE:	NTS
ACAD FILENAME:	Water Standard
DWG. NO.	WS-19.DWG

NAVAJO TRIBAL UTILITY AUTHORITY
By Civil Engineering Department

GRAVITY/THRUST
BLOCK DETAILS

BQ-ENGINEERING

FT.DENANCE, AZ

REVISIONS

No.	Date	Brief	By
01	04/08	Revised	L.H.
02			
03			
04			
05			
06			



GRAVITY THRUST BLOCK
(ALSO TO BE USED IN UNSTABLE TRENCH CONDITIONS)
RESULTANT THRUST IN POUNDS OF FITTINGS AT 100 PSI WATER PRESSURE

TOTAL POUNDS					
PIPE SIZE	DEAD END	90° ELBOW	45° ELBOW	22 1/2° ELBOW	11 1/4° ELBOW
3"	1,232	1,742	943	481	241
4"	1,810	2,559	1,385	706	355
6"	3,739	5,288	2,862	1,459	733
8"	6,433	9,097	4,923	2,510	1,261
10"	9,677	13,685	7,406	3,776	1,897
12"	13,685	19,353	10,474	5,340	2,683
14"	18,385	26,001	14,072	7,174	3,604
16"	23,799	33,628	18,199	9,278	4,661
18"	29,865	42,235	22,858	11,653	5,855
20"	36,644	51,822	28,046	14,298	7,183
24"	52,279	73,934	40,013	20,398	10,249
30"	80,425	113,738	61,554	31,380	15,766
36"	115,209	162,931	88,177	44,952	22,585
42"	155,528	219,950	119,036	60,684	30,489
48"	202,683	286,637	155,127	79,083	39,733
54"	260,214	367,999	199,160	101,531	51,011
60"	298,121	421,606	228,172	116,321	58,442
64"	338,707	479,004	259,235	132,157	66,398

NOTES:

1. THE THRUST (IN TOTAL POUNDS) IN THE CHART IS BASED ON DUCTILE IRON OUTSIDE DIAMETER PIPE DIMENSION. SURGES SHOULD BE CONSIDERED AT TWICE THE NORMAL OPERATING PRESSURE. THE VOLUME OF THE GRAVITY THRUST BLOCK IS BASED ON CONCRETE AT 150 LBS./FT³.
2. TO OBTAIN VOLUME OF CONCRETE REQUIRED, USE:
VOLUME OF CONCRETE(FT³)= THRUST(LBS.) x SYSTEM PRESSURE(Psi)/100 PSI // 150 LBS./FT³.

E.G.: CALCULATE THE VOLUME OF THE GRAVITY THRUST BLOCK FOR AN 8" x 45° BEND AT AN OPERATING PRESSURE OF 80 PSI.

ANSWER: 4923 LBS. x 80 PSI/100 PSI DIVIDED BY 150 LBS./CUBIC FT. = 52.5 CUBIC FEET OR 2 CUBIC YARDS.


SHEET 2 OF 2

DESIGNED BY:	NTUA
SURVEYED BY:	
DRAWN BY:	NTUA
APPROVED BY:	NTUA
DATE:	04/08
PROJECT NO.	
SCALE:	NTS
ACAD FILENAME:	Water Standard
DWG. NO.	WS-19a.DWG



NAVAJO TRIBAL UTILITY AUTHORITY <small>By Civil Engineering Department</small>	
GRAVITY/THRUST BLOCK CHART	
BQ-ENGINEERING	FT.DEFIANCE, AZ

REVISIONS			
No.	Date	Brief	By
01	04/08	Revised	L.H.
02			
03			
04			
05			
06			






REVISION	DATE	BRIEF	BY
U.S. DEPARTMENT OF HEALTH AND HUMAN SERVICES PUBLIC HEALTH SERVICE INDIAN HEALTH SERVICE NAVAJO NATION			
STANDARD DRAWING No. W-33 HDPE WASH CROSSING DETAIL FOR 4" THRU 12" PIPE			
NAVAJO ENGINEERING & CONSTRUCTION AUTHORITY			
DRAWN BY: WZS	CHECKED BY: S.C.	APPR. BY: S.C.	AUTOCAD
DATE: 8/24/16	DATE: 8/24/16	DATE: 8/24/16	DRAWING




1	7/99	STANDARDIZED	B.M.
REVISION	DATE	BRIEF	BY
U.S. DEPARTMENT OF HEALTH AND HUMAN SERVICES PUBLIC HEALTH SERVICE INDIAN HEALTH SERVICE NAVAJO NATION			
NAVAJO NATION, STANDARD DRAWING NO. W-34 FENCE DETAIL FOR STORAGE TANK & PUMPHOUSE			
OFFICE OF ENVIRONMENTAL HEALTH AND ENGINEERING NAVAJO AREA OFFICE, WINDOW ROCK, ARIZONA			
DRAWN BY: L.S. DATE: 12/92	CHECKED BY: P.S. DATE: 12/92	APPR. BY: P.S. DATE: 12/92	AUTOCAD DRAWING

SILT FENCE DETAILS




INSTALLATION NOTES

1. THE SILT FENCING CONSISTS OF 3' SEDIMENT CONTROL FABRIC CLOTH WITH BURIED-TOE AND WOODEN OR STEEL POSTS (TEE OR U TYPE) 10' AND SHALL COMPLY WITH AASHTO M-288.
2. WHEN TWO SECTIONS OF FILTER CLOTH ADJOIN EACH OTHER THEY SHALL BE OVERLAPPED BY 6" AND FOLDED. MAINTENANCE SHALL BE PERFORMED AS NEEDED AND MATERIAL REMOVED WHEN "BULGES" DEVELOP IN THE SILT FENCE.




SILT FENCE:
PLAN VIEW

REVISION	DATE	BRIEF	BY
DEPARTMENT OF HEALTH AND HUMAN SERVICES U.S. PUBLIC HEALTH SERVICE INDIAN HEALTH SERVICE NAVAJO NATION			
NAVAJO NATION STANDARD DRAWING NO. W-39 SILT FENCE DRAWING 1 OF 2			
PUBLIC LAW 86-121 OFFICE OF ENVIRONMENTAL HEALTH AND ENGINEERING NAVAJO AREA OFFICE, WINDOW ROCK, ARIZONA			
DRAWN BY: TL DATE: 9/01	CHECKED BY: RG DATE: 9/01	APPR. BY: BM DATE: 9/01	AUTOCAD DRAWING



SEDIMENT CONTROL FENCE INSTALLATION DETAIL




SECTION A-A

REVISION	DATE	BRIEF	BY
DEPARTMENT OF HEALTH AND HUMAN SERVICES U.S. PUBLIC HEALTH SERVICE INDIAN HEALTH SERVICE NAVAJO NATION			
NAVAJO NATION STANDARD DRAWING NO. W-39 SILT FENCE DRAWING 2 OF 2			
PUBLIC LAW 86-121 OFFICE OF ENVIRONMENTAL HEALTH AND ENGINEERING NAVAJO AREA OFFICE, WINDOW ROCK, ARIZONA			
DRAWN BY: TL DATE: 9/01	CHECKED BY: RG DATE: 9/01	APPR. BY: BM DATE: 9/01	AUTOCAD DRAWING

STRAW BALE DETAILS

(For Check Dams to Retain Water and Sediment)




TYPICAL STRAW BALE STAKING AND TRENCHING DETAIL

INSTALLATION NOTES

1. STRAW BALES MAY BE USED FOR DIKES PROVIDED THEY ARE PROPERLY ANCHORED WITH STEEL FENCE POSTS OR 2" X 2" X 4' WOOD STAKES (TWO PER BALE) ANCHORED 1.5' INTO THE NATURAL GROUND. STRAW BALES SHALL BE CERTIFIED 0.5% WEED FREE. DO NOT USE STRAW BALES IN AREAS OF CONCENTRATED FLOW AND CUT DITCHES.

GENERAL NOTES

1. THE CONTRACTOR SHALL HAVE ON-SITE A COPY OF THE STORM WATER POLLUTION PREVENTION PLAN (SWPPP) WITH PROJECT SPECIFIC COVER SHEET.
2. CONSTRUCT CHECK DAMS AND/OR FILTERS IN STRATEGIC LOCATIONS ON THE PROJECT TO FILTER STORM RUNOFF BEFORE IT LEAVES THE PROJECT CONSTRUCTION LIMITS OR ENTERS A WASH. SEE PROJECT CONSTRUCTION PLANS FOR LOCATIONS OF CHECK DAMS & FILTERS.
3. CLEAN ALL SEDIMENT BASIN AND TRAPS OF ACCUMULATED SEDIMENT WHEN HALF FULL OF SEDIMENT.
4. THE CONTRACTOR SHALL INSPECT AND MAINTAIN ALL SWPPP MEASURES MONTHLY AND AFTER EACH SIGNIFICANT STORM EVENT (I.E. 0.5 IN. OF MOISTURE IN 24 HOURS).
5. THE CONTRACTOR, IN CONSULTATION WITH THE PROJECT ENGINEER SHALL ADJUST THE DIMENSIONS AND/OR LOCATIONS OF TEMPORARY SEDIMENT AND EROSION CONTROL DEVICES TO FIT ACTUAL FIELD CONDITIONS. ALL ADJUSTMENTS WILL BE DOCUMENTED ON THE INSPECTION FORMS INCLUDED WITH THE SWPPP.
6. REMOVE AND DISPOSE OF EROSION CONTROL MEASURES WHEN THE PERMANENT EROSION CONTROL MEASURES ARE SATISFACTORILY ESTABLISHED.



REVISION	DATE	BRIEF	BY
DEPARTMENT OF HEALTH AND HUMAN SERVICES U.S. PUBLIC HEALTH SERVICE INDIAN HEALTH SERVICE NAVAJO NATION			
NAVAJO NATION STANDARD DRAWING NO. W-40 STRAW BALES			
PUBLIC LAW 86-121 OFFICE OF ENVIRONMENTAL HEALTH AND ENGINEERING NAVAJO AREA OFFICE, WINDOW ROCK, ARIZONA			
DRAWN BY: TL DATE: 9/01	CHECKED BY: RG DATE: 9/01	APPR. BY: BM DATE: 9/01	AUTOCAD DRAWING


NAVAJO TRIBAL UTILITY AUTHORITY

CONTROL PANEL LAYOUT




AC TANK CONTROL PANEL

SCHEDULE OF DRAWINGS			
PAGE	FILENAME	TITLE	NOTES
1	AC_CV	COVERSHEET	SCHEDULE OF DRAWINGS
2	AC_DIO	DISCRETE I/O	WIRING
3	AC_AIO	ANALOG I/O	WIRING
4	AC_PWR	POWER DISTRIBUTION	WIRING
5	AC_BP	BACKPLANE LAYOUT	BP W/ BOM
6	AC_CBL	COMM CABLES PINOUT	WIRING



NO.	DATE	DESCRIPTION	BY
 NAVAJO TRIBAL UTILITY AUTHORITY			
SCALE: NONE	REVISIONS		BY DATE
DATE:			
DRN:	CRD:		
APVD:			
TITLE: AC TANK PANEL		NO. #	
COVER SHEET		SHEET 1 OF 6	

POWER DISTRIBUTION THIS PAGE REFLECTS "LOGICAL" SCHEMATIC SEE "DC DISTRIBUTION" DRAWING AND "AC DISTRIBUTION" DRAWING FOR POINT TO POINT TERMINATIONS





LEGEND

Field Terminations	-----
Panel Wiring	_____



01	3/19	DWG UPDATES		NTUA
NO.	DATE	DESCRIPTION		BY
 NAVAJO TRIBAL UTILITY AUTHORITY				
SCALE:	NONE	REVISIONS	BY	DATE
DATE:	-	-	-	-
DRN:	-	-	-	-
APVD:	-	-	-	-
TITLE	AC TANK CONTROL PANEL			
DISCRETE I/O			SHEET 2 OF 6	

POWER DISTRIBUTION THIS PAGE REFLECTS "LOGICAL" SCHEMATIC SEE "DC DISTRIBUTION" DRAWING AND "AC DISTRIBUTION" DRAWING FOR POINT TO POINT TERMINATIONS



LEGEND	
Field Terminations	-----
Panel Wiring	_____

01	3/19	DWG. UPDATES	NTUA
NO.	DATE	DESCRIPTION	BY
NAVAJO TRIBAL UTILITY AUTHORITY			
SCALE: NONE	REVISIONS		BY DATE
DATE:			
DRN:	CRD:		
APVD:			
TITLE: AC TANK CONTROL PANEL			W.O.#
ANALOG I/O			SHEET 3 OF 6




NOTE: SEE OPTIONS BELOW IF ADDITIONAL RADIO IS REQUIRED, IMPLEMENT ONE OF THE TWO OPTIONS BELOW. OTHERWISE, THIS AREA CAN BE LEFT VACANT FOR ANY FUTURE POWER REQUIREMENTS:

OPTION #1; WHEN INSTALLING A 24 VDC RADIO, WIRE RADIO DIRECTLY TO TERMINALS 17 & 24 ON TS1.

OPTION #2; WHEN INSTALLING A 12-13.8 VDC RADIO, INSTALL DC/DC CONVERTER POWERED BY TERMINALS 17 & 24 ON TS1, THEN WIRE RADIO DIRECTLY TO THE DC/DC CONVERTER.

LEGEND	
Field Terminations	-----
Panel Wiring	_____


01	3/19	DWG UPDATES	NTUA
NO.	DATE	DESCRIPTION	BY
NAVAJO TRIBAL UTILITY AUTHORITY			
SCALE:	REVISIONS		BY DATE
DATE:			
DRN:	CRD:		
APVD:			
TITLE AC TANK CONTROL PANEL			W.O.#
POWER DISTRIBUTION			SHEET 4 OF 6



BILL OF MATERIALS				
ITEM	QTY	PART NO.	DESCRIPTION	MFG
1	1	A30H24DLP	SINGLE-DOOR TYPE 4 ENCLOSURE	HOFFMAN
2	1	A30P24	BACKPLANE	HOFFMAN
3*	.	M340	MODICON M340 BOM	SCHNEIDER ELECTRIC
3a	1	BMXXBM0400	4-SLOT RACK	SCHNEIDER ELECTRIC
3b	1	BMXCPS3020	MODULE POWER SUPPLY	SCHNEIDER ELECTRIC
3c	1	BMXP342020	MODULE CPU PROCESSOR	SCHNEIDER ELECTRIC
3d	1	BMXDM16025	MODULE DIGITAL INPUT/OUTPUT	SCHNEIDER ELECTRIC
3e	1	BMXAMM0600	MODULE ANALOG INPUT/OUTPUT	SCHNEIDER ELECTRIC
3f	2	BMXFTB2010	REMOVABLE CONNECTION BLOCK - SCREW CLAMP	SCHNEIDER ELECTRIC
3g*	1	BMXNOM0200	SERIAL LINK	SCHNEIDER ELECTRIC
4	1	FL SWITCH SFN 5TX	MODULE INDUSTRIAL ETHERNET	PHOENIX CONTACT
5	1	QUINT4-PS/1AC/ 24DC/5	SWITCH POWER SUPPLY	PHOENIX CONTACT
6	.	.	22.5-28.5V ADJUSTABLE	.
7	14	UT2,5	UT2,5 TERMINALS	PHOENIX CONTACT
8	10	UT4TG	FUSE TERMINAL BASE	PHOENIX CONTACT
9	7	P-FU5X20LED24	FUSE PLUG	PHOENIX CONTACT
10	4	P-FU5X20LA250	FUSE PLUG	PHOENIX CONTACT
11	6	UT2,5PE	GROUNDING TERMINAL	PHOENIX CONTACT
12	15	E/NS35N	END CLAMP	PHOENIX CONTACT
13	3	FBS 20-6 BU #3032208	FIXED BRIDGE	PHOENIX CONTACT
14	3	FBS 20-5 BU #3036929	INSERTION BRIDGE	PHOENIX CONTACT
15	8	D-UT2,5/10	END COVER	PHOENIX CONTACT
16	4	ATP-UT	PARTITION PLATES	PHOENIX CONTACT
17	2	QUINT4-UPS/24DC /24DC/10	UNINTERRUPTIBLE POWER SUPPLY	PHOENIX CONTACT
18	2	UPS-BAT/VRLA/ 24DC/1.3AH	ENERGY STORAGE	PHOENIX CONTACT
19	.	.	.	PHOENIX CONTACT
20	12	TTC-6-TVSD-C- 24DC-UT-I	SURGE PROTECTION #2906831	PHOENIX CONTACT
21	6	TTC-6-LCP #2908729	END COVER	PHOENIX CONTACT
22	16	TTC-6-MOV-C- 24DC-UT-I	SURGE PROTECTION # 2906837	PHOENIX CONTACT
23	1	PLT-SEC-T3-120 -FM #2905228	TYPE 3 SURGE PROTECTION DEVICE	PHOENIX CONTACT
24	AN	F2X4LG6	TYPE F NARROW SLOT WIRING DUCT	PANDUIT
25	AN	C2LG6	WIRING DUCT COVER	PANDUIT
26	1	TMC 61C 10A #0902072	CIRCUIT BREAKER	PHOENIX CONTACT
26a	1	UT6-TMCM 10A #0916610	CIRCUIT BREAKER	PHOENIX CONTACT
27	AN	1492DR6	EXTENDED DIN RAIL	ALLEN BRADLEY
28	AN	1492-DR5	DIN RAIL	ALLEN BRADLEY
29	1	IS-50NX-C2	LIGHTNING ARRESTER	POLYPHASER
30	1	D-AH1001A	HEATER 100W 115V .9A	HOFFMAN
31	1	DRUBGF115	DIN RAIL UTILITY BOX	HUBBELL
32	1	ORBIT OR TRANSNET	902 - 928 MHz RADIO	GEMDS
33	1	CAT6	SPREAD SPECTRUM CABLE - PLC TO HMI	BELDEN
34*	1	.	CABLE - PLC TO MODEM (TO LENGTH)	.
35*	1	MINI-PS-12-24 DC/5-15/2	DC/DC CONVERTER	PHOENIX CONTACT


AN - As needed
3* - BOM - To include items 3a-3g.
3g* - Include in the event item 35* is required.
34* - Include (1) additional in the event item 33* is required.
35* - Include in the event a 13.8 VDC radio is required.

01	3/19	DWG UPDATES	NTUA
NO.	DATE	DESCRIPTION	BY
NAVAJO TRIBAL UTILITY AUTHORITY			
SCALE:	NONE	REVISIONS	BY DATE
DATE:	.	.	.
DRN:	CRD:	.	.
APVD:	.	.	.
TITLE AC TANK CONTROL PANEL			SHEET 5 OF 6



A

CABLE DIAGRAM: PLC TO RADIO


01	3/19	DWG UPDATES	NTUA
NO.	DATE	DESCRIPTION	BY
<div><div>NAVAJO TRIBAL UTILITY AUTHORITY</div></div>			
SCALE:	NONE	REVISIONS	BY DATE
DATE:	.	.	.
DRN:	DRD:	.	.
APVD:	.	.	.
TITLE	AC TANK CONTROL PANEL		W.O.#
	CABLE PINOUT		SHEET 6 OF 6

NAVAJO TRIBAL UTILITY AUTHORITY
PUMP CONTROL PANEL LAYOUT


SCHEDULE OF DRAWINGS			
SHEET	FILENAME	TITLE	NOTES
1	PLC_CV	COVERSHEET	SCHEDULE OF DRAWINGS
2	PLC_DIO	DISCRETE I/O	WIRING
3	PLC_AI	ANALOG INPUT	WIRING
3A	PLC_AO	ANALOG OUTPUT	WIRING
4	PLC_PWR	POWER DISTRIBUTION	WIRING
5	PLC_BP	BACKPLANE LAYOUT	BP W/ BOM
5A	PLC_SOP	SWING OUT PANEL	BP W/ BOM
6	PLC_CBL	COMM CABLES PINOUT	



PLC CONTROL PANEL

01	3/22	DWG MODIFICATION "DILKON PASS BOOSTER"	NTUA
NO.	DATE	DESCRIPTION	BY
 NAVAJO TRIBAL UTILITY AUTHORITY			
SCALE:	NONE	REVISIONS	BY DATE
DATE:			
DRN:	DRN:		
APVD:			
TITLE: PLC CONTROL PANEL			NO. #
COVER SHEET			SHEET 1 OF 6

POWER DISTRIBUTION THIS PAGE REFLECTS "LOGICAL" SCHEMATIC SEE "DC DISTRIBUTION" DRAWING AND "AC DISTRIBUTION" DRAWING FOR POINT TO POINT TERMINATIONS




LEGEND

Field Terminations -----

Panel Wiring _____

02	12/21	DWG UPDATES "DILKON PASS BOOSTER"	NTUA	
01	3/19	DWG UPDATES	NTUA	
NO.	DATE	DESCRIPTION	BY	
NAVAJO TRIBAL UTILITY AUTHORITY				
SCALE:	NONE	REVISIONS	BY	DATE
DATE:				
DRN:	DRN:			
APVD:				
TITLE: PLC CONTROL PANEL DISCRETE I/O (BOOSTER WITH BOOSTERPAQ)			SHEET 2 OF 6	

POWER DISTRIBUTION THIS PAGE REFLECTS "LOGICAL" SCHEMATIC SEE "DC DISTRIBUTION" DRAWING AND "AC DISTRIBUTION" DRAWING FOR POINT TO POINT TERMINATIONS



LEGEND

Field Terminations -----

Panel Wiring _____

03	3/22	DWG MODIFICATIONS "DILKON PASS BOOSTER"	NTUA
02	12/21	DWG UPDATES	NTUA
01	3/19	DWG UPDATES	NTUA
NO.	DATE	DESCRIPTION	BY
NAVAJO TRIBAL UTILITY AUTHORITY			
SCALE:	NONE	REVISIONS	BY DATE
DATE:	.	.	.
DRN:	DRD:	.	.
APVD:	.	.	.
TITLE: PLC CONTROL PANEL ANALOG INPUT (BOOSTER WITH BOOSTERPAQ)			NO.#
			SHEET 3 OF 6

POWER DISTRIBUTION THIS PAGE REFLECTS "LOGICAL" SCHEMATIC SEE "DC DISTRIBUTION" DRAWING AND "AC DISTRIBUTION" DRAWING FOR POINT TO POINT TERMINATIONS

— GRND


—N

—L1

— GRND

— DCC


— +24 VDC



LEGEND

Field Terminations	-----
Panel Wiring	_____

03	3/22	DWG MODIFICATIONS "DILKON PASS BOOSTER"	NTUA
02	12/21	DWG UPDATES	NTUA
01	3/19	DWG UPDATES	NTUA
NO.	DATE	DESCRIPTION	BY




NAVAJO TRIBAL UTILITY AUTHORITY


SCALE: NONE		REVISIONS		BY	DATE
DATE:	-	-	-	-	-
DRN:	-	OKD.	-	-	-
APVD:	-	-	-	-	-

TITLE	PLC CONTROL PANEL ANALOG OUTPUT (BOOSTER WITH BOOSTERPAQ)	W.O.#
		SHEET 3a OF 6


24VDC DISTRIBUTION




24VDC DISTRIBUTION (UPS)



120VAC DISTRIBUTION





GRND



LEGEND	
Field Terminations	-----
Panel Wiring	_____



01	12/16	DWG UPDATES	NTUA
NO.	DATE	DESCRIPTION	BY
NAVAJO TRIBAL UTILITY AUTHORITY			
SCALE:	REVISIONS		BY DATE
DATE:			
DRN:	CRD:		
APVD:			
TITLE PLC CONTROL PANEL			NO.#
POWER DISTRIBUTION			SHEET 4 OF 6



BILL OF MATERIALS				
ITEM	QTY	PART NO.	DESCRIPTION	MFG
1	1	A-363012LP	SINGLE-DOOR TYPE 12 ENCLOSURE	HOFFMAN
2	1	A-36P30	BACKPLANE	HOFFMAN
3*	.	M340	MODICON M340 BOM	SCHNEIDER
3a	1	BMXXBP0800	8-SLOT RACK	ELECTRIC
3b	1	BMXCPS3020	MODULE POWER SUPPLY	ELECTRIC
3c	1	BMXP342020	MODULE CPU PROCESSOR	ELECTRIC
3d	1	BMXDD1602	MODULE DIGITAL INPUT	ELECTRIC
3e	1	BMXDDM16025	MODULE DIGITAL INPUT/OUTPUT	ELECTRIC
3f	1	BMXAMI0810	MODULE ANALOG INPUT	ELECTRIC
3g	1	BMXAM00210	MODULE ANALOG OUTPUT	ELECTRIC
3h	3	BMXFTB2010	REMOVABLE CONNECTION BLOCK - SCREW CLAMP	ELECTRIC
3i	1	BMXFTB2800	REMOVABLE CONNECTION BLOCK - CAGE SPRING	ELECTRIC
4	1	HMIQT04310	7.5 GRAPHIC TERMINAL TOUCHSCREEN (MAGELIS)	SCHNEIDER
5	1	FL SWITCH 1008N	INDUSTRIAL ETHERNET SWITCH	ELECTRIC
6	1	QUINT4-PS/1AC/ 24DC/10	POWER SUPPLY 22.5-28.5V ADJUSTABLE	PHOENIX
7	26	UT2,5	UT2,5 TERMINALS	CONTACT
8	16	UT4TG	FUSE TERMINAL BASE	PHOENIX
9	12	P-FU5X20LED24	FUSE PLUG	CONTACT
10	4	P-FU5X20LA250	FUSE PLUG	CONTACT
11	7	UT2,5PE	GROUNDING TERMINAL	PHOENIX
12	15	E/NS35N	END CLAMP	CONTACT
13	4	FBS 20-6 BU #3032208	FIXED BRIDGE	PHOENIX
14	4	FBS 20-5 BU #3036929	INSERTION BRIDGE	CONTACT
15	6	D-UT2,5/10	END COVER	PHOENIX
16	6	ATP-UT	PARTITION PLATES	CONTACT
17	1	QUINT4-UPS/24DC/ 24DC/10	UNINTERRUPTIBLE POWER SUPPLY	PHOENIX
18	1	UPS-BAT/PB/ 24DC/4.0AH	ENERGY STORAGE	CONTACT
19
20	20	TTC-6-TVSD-C- 24DC-UT-I #2906831	SURGE PROTECTION	PHOENIX
21	7	TTC-6-LCP #2908729	END COVER	CONTACT
22	56	TTC-6-MOV-C- 24DC-UT-I #2906837	SURGE PROTECTION	CONTACT
23	1	PLT-SEC-T3-120 -FM-UT	TYPE 3 SURGE PROTECTION DEVICE	PHOENIX
24	AN	F2X4LG6	TYPE F NARROW SLOT WIRING DUCT	CONTACT
25	AN	C2LG6	WIRING DUCT COVER	PANDUIT
26	1	TMC 71C 10A #0902072	CIRCUIT BREAKER	PHOENIX
26a	1	UT6-TMCM 10A #0916610	CIRCUIT BREAKER	CONTACT
27	AN	1492DR6	EXTENDED DIN RAIL	ALLEN
28	AN	1492-DR5	DIN RAIL	BRADLEY
29	1	IS-50NX-C2	LIGHTNING ARRESTER	ALLEN
30	1	ORBIT OR TRANSNET	902 - 928 MHz RADIO SPREAD SPECTRUM	BRADLEY
31	2	CAT6	ETHERNET PATCH CABLE (4' - BLACK)	POLYPHASER
32	.	.	CABLE - PLC TO MODEM (TO LENGTH)	GEMDS
33	1	DRUBGF115	DIN RAIL UTILITY BOX	BELDEN

AN - As needed
3* - BOM - To include items 3a-3h.


02	3/22	DWG MODIFICATIONS "DILKON PASS BOOSTER"	NTUA	
01	3/19	DWG UPDATES	NTUA	
NO.	DATE	DESCRIPTION	BY	
NAVAJO TRIBAL UTILITY AUTHORITY				
SCALE:	NONE	REVISIONS	BY	DATE
DATE:
DRN:	OKD.	.	.	.
APVD:
TITLE	PLC CONTROL PANEL			NO. #
	BACKPLANE			SHEET 5 OF 6



BILL OF MATERIALS				
ITEM	QTY	PART NO.	DESCRIPTION	MFG
1	1	A-36H30DLP	SINGLE-DOOR TYPE 4 ENCLOSURE	HOFFMAN
2	1	A-36P30	BACKPLANE	HOFFMAN
2a	1	A-NADFK	SWING OUT PANEL KIT	HOFFMAN
3*	.	M340	MODICON M340 BOM	MODICON
3a	1	BMXXBM0800	8-SLOT RACK MODULE	MODICON
3b	1	BMXCPS3020	POWER SUPPLY MODULE	MODICON
3c	1	BMX342020	CPU PROCESSOR MODULE	MODICON
3d	1	BMXDDI1602	DIGITAL INPUT MODULE	MODICON
3e	1	BMXDDM16025	DIGITAL INPUT/OUTPUT MODULE	MODICON
3f	1	BMXAMI0410	ANALOG INPUT MODULE	MODICON
3g	1	BMXAMO0210	ANALOG OUTPUT MODULE	MODICON
3h	4	BMXFTB2010	REMOVABLE CONNECTION BLOCK - SCREW CLAMP	MODICON
4	1	HMIQT04310	7.5 GRAPHIC TERMINAL TOUCHSCREEN (MAGELIS)	SCHNEIDER
5	1	FL SWITCH SFN 8TX	INDUSTRIAL ETHERNET SWITCH	ELECTRIC
6	1	QUINT-PS/1AC/ 24DC/10	POWER SUPPLY 22.5-28.5V ADJUSTABLE	PHOENIX CONTACT
6a	1	QUINT-UPS/24DC /24DC/10/3.4AH	UNINTERRUPTIBLE POWER SUPPLY	PHOENIX CONTACT
7	26	UT2,5	UT2,5 TERMINALS	PHOENIX CONTACT
8	16	UT4TG	FUSE TERMINAL BASE	PHOENIX CONTACT
9	12	P-FU5X20LED24	FUSE PLUG	PHOENIX CONTACT
10	4	P-FU5X20LA250	FUSE PLUG	PHOENIX CONTACT
11	6	UT2,5PE	GROUNDING TERMINAL	PHOENIX CONTACT
12	15	E/NS35N	END CLAMP	PHOENIX CONTACT
13	4	FBI 20-6 BU #3032208	FIXED BRIDGE	PHOENIX CONTACT
14	4	FBS 20-5 BU #3036929	INSERTION BRIDGE	PHOENIX CONTACT
15	6	D-UT2,5/10	END COVER	PHOENIX CONTACT
16	6	ATP-UT	PARTITION PLATES	PHOENIX CONTACT
17	2	ATP-UK	PARTITION PLATES	PHOENIX CONTACT
18	4	DP-UKK3/5BK #2770833	SLKK5 SPACER PLATE	PHOENIX CONTACT
19	4	D-UKK3/5BK #2770228	SLKK5 ENDCOVER	PHOENIX CONTACT
20	12	TT-UK5/24DC #2794699	TERMITRAB UK5 W/SUPPRESSOR DIODE	PHOENIX CONTACT
21	3	D-TERMITRAB UK5	END COVER	PHOENIX CONTACT
22	56	TT-SLKK5/24DC #2794903	TERMITRAB SLKK5 W/VARISTOR 24DC (MOV)	PHOENIX CONTACT
23	1	PT2PE/S120FM	TERMITRAB AC SURGE PROTECTION	PHOENIX CONTACT
24	AN	F2X4LG6	TYPE F NARROW SLOT WIRING DUCT	PANDUIT
25	AN	C2LG6	WIRING DUCT COVER	PANDUIT
26	1	TMC 61C 10A #0902072	CIRCUIT BREAKER	PHOENIX CONTACT
26a	1	UT6-TMCM 10A #0916610	CIRCUIT BREAKER	PHOENIX CONTACT
27	AN	1492DR6	EXTENDED DIN RAIL	ALLEN BRADLEY
28	AN	1492-DR5	DIN RAIL	ALLEN BRADLEY
29	1	IS-50NX-C2	LIGHTNING ARRESTER	POLYPHASER
30	1	ORBIT OR TRANSNET	902 - 928 MHz RADIO SPREAD SPECTRUM	GEMDS
31	2	CAT6	ETHERNET PATCH CABLE (4' - BLACK)	BELDEN
32	1	.	CABLE - PLC TO MODEM (TO LENGTH)	.
33	1	DRUBGF115	DIN RAIL UTILITY BOX	HUBBELL

AN - As needed
3* - BOM - To include items 3a-3h.

01	12/16	DRAWING	NTUA
NO.	DATE	DESCRIPTION	BY
NAVAJO TRIBAL UTILITY AUTHORITY			
SCALE: NONE	REVISIONS		BY DATE
DATE:			
DRN:	CRD:		
APVD:			
TITLE: PLC CONTROL PANEL WITH SWING OUT PANEL BACKPLANE			SHEET 5A OF 6



A

CABLE DIAGRAM: PLC TO RADIO

01	12/16	DWG UPDATES	NTUA
NO.	DATE	DESCRIPTION	BY
NAVAJO TRIBAL UTILITY AUTHORITY			
SCALE:	NONE	REVISIONS	BY DATE
DATE:	.	.	.
DRN:	OKD:	.	.
APVD:	.	.	.
TITLE: PLC CONTROL PANEL			W.O.#
CABLE PINOUT			SHEET 6 OF 6