

Addendum # 2

Upper Moenkopi Well

IHS Project PH 15-U77 / EA 02-20

1. **ITEM:** Clarification on Water Main Road Bore

Resolution: The following update to the bid schedule is made:

Change Water Main Road Bore and Highway Crossing on Bid Schedule of Moenkopi Upper Well plans from 200 feet to 100 feet. The casing length shall be 100', extending a minimum of 30' past each side of the pavement.

2. **ITEM:** Modification of Bid due dates.

Resolution: The following update to the Advertisement for Bids:

Bids By Mail: Change the must be received time and date to 11 a.m. (MST): Wednesday, October 13th, 2022

In Person Bids: Change the must be received time and date to before 11 a.m. local time Thursday, October 14th, 2022

3. **ITEM:** Precast Building manufacturer Oldcastle no longer does above ground buildings

Resolution: The following update to TP 43.04

Modify section 43.04 to state: The prefabricated pump house buildings shall be equal to the standard concrete two room 11'-0" x 14'-0" x 10'-0" (minimum dimensions) buildings as manufactured by New World Management, or equal. 1090 S. Gilbert Rd STE 106-187, Gilbert, AZ 85296, (916) 620-0016, Contact: Doug Domas (doug.domas@managenw.com) or Dan Rysavy (dan.rysavy@managenw.com)